SPECIFICATION

DFO P/N C2-00517 FLOATING DOCK CONSTRUCTION PUGWASH, NS

ISSUED FOR TENDER

OWNER/AGENT:

FISHERIES AND OCEANS/PÊCHES ET OCÉANS CANADA 2920 HIGHWAY 104, ANTIGONISH, NS B2G 2K6

DATE:

June 9, 2023

SPECIFICATION INDEX

P/N C2-00517 Floating Dock Construction Pugwash, NS Page 1

SECTION

DFO

TITLE

PAGE (S)

Di	visi	ion	01	- General Requirements	
01	10	10		General Instructions	13
01	29	00		Project Particulars and Measurement	4
01	29	83		Payment Procedures for Testing	2
				Laboratory Services	
01	33	00		Submittal Procedures	8
01	35	24		Special Procedures on Fire Safety Requirements	6
01	35	28		Health and Safety Requirements	19
01	35	44		Environmental Protection Procedures	15
01	45	00		Testing and Quality Control	5
01	50	00		Temporary Facilities	4
01	56	00		Temporary Barriers and Enclosures	2
01	61	00		Common Product Requirements	6
01	74	11		Cleaning	2
01	74	21		Construction/Demolition Waste Management and	
				Disposal	7
01	78	00		Closeout Submittals	3
Di	visi	ion	02	- Existing Conditions	
02	41	16		Sitework, Demolition, and Removal	3
Di	visi	ion	03	- Concrete	
03	10	00		Concrete Forming and Accessories	6
03	20	00		Concrete Reinforcing	5
03	30	00		Cast in Place Concrete	11
Di	visi	ion	05	- Metals	
05	50	00		Metal Fabrications	4
05	51	00		Aluminum Gangway	3
Di	visi	ion	06	- Wood and Plastics	
06	05	73		Wood Treatment	4

SPECIFICATION INDEX

P/N C2-00517 Floating Dock Construction Pugwash, NS

DFO

Page 2

Division 31 - Earth	hwork	
31 23 10 Excava	tion, Trenching, and Backfilling	8
31 23 26 Rock F	'ill	3
31 32 21 Geotex	tiles	6
31 53 16 Struct	ural Timber	7
Division 35 - Water	rway and Marine Construction	
35 20 23 Dredgi	ing	14
35 31 19 Revetm	lent	5

DFO LI P/N C2-00517 Floating Dock Construction Pugwash, NS

PAGE 1 OF 1

DRAWING NO.	DESCRIPTION			
1 of 6	EXISTING CONDITIONS & DREDGE LIMITS			
2 of 6	SITE PLAN GENERAL ARRANGEMENT OF NEW WORK			
3 of 6	SITE SECTIONS & REINFORCED CONCRETE DETAILS			
4 of 6	FLOATING DOCK PLAN, ELEVATION, SECTION, AND DETAILS			
5 of 6	FLOATING DOCK ELEVATIONS, SECTIONS & DETAILS			
6 of 6	FLOATING DOCK STRONG ARM & GANGWAY PLANS, ELEVATIONS & DETAILS			

DFO P/N C2-00517 Floating Dock Construc Pugwash, NS	GENER	AL INSTRUCTIONS	Section 01 10 10 Page 1
<u>1.1 SCOPE</u>	.1	The work covered un consists of the fur plant, labour, equi material for Floati Construction, Pugwa in strict accordance specifications and drawings and subject and conditions of co	nder this contract nishing of all pment and ng Dock ash, Nova Scotia, with accompanying at to all terms contract.
1.2 DESCRIPTION OF WORK	.1	In general, work un consists of but will be limited to the f .1 Removal and re- existing armour sto berm material as in .2 Dredging of th as indicated on the disposal of dredged existing containmer .3 Supply and ins docks, strongarms a continuous concrete .4 Modifications approach including type 1 gravels.	der this contract 1 not necessarily collowing: instatement of one and core stone ndicated. he harbour bottom d material in the t berm. stall new floating and gangways, and e retaining wall. to the berm installation of
1.3 SITE OF WORK	.1	Work will be carrie Nova Scotia in the on the accompanying	ed out at Pugwash, location as shown g drawings.
<u>1.4 DATUM</u>	.1	Datum used for this benchmark CHS BM 2- the old bridge abut approach road to th elevation +5.808m a	project is 1983 located at ment, near the le old salt wharf, above Chart Datum
	.2	Bidders are advised Tide Tables issued Oceans in order to tidal conditions af	l to consult the by Fisheries and make sure of the ffecting work.

Section 01 10 10 DFO GENERAL INSTRUCTIONS P/N C2-00517 Page 2 Floating Dock Construction Pugwash, NS 1.5 FAMILIARIZATION .1 Before submitting a bid, it is recommended that bidders visit the WITH SITE site and its surroundings to review and verify the form, nature and extent of the work, materials needed for the completion of the work, the means of access to the site, severity, exposure and uncertainty of weather, soil conditions, any accommodations they may require, and in general shall obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their bid. No allowance shall be made subsequently in this connection on account of error or negligence to properly observe and determine the conditions that will apply. .2 Contractors, bidders or those they invite to site are to review specification Section 01 35 28 -Health and Safety Requirements before visiting site. Take all appropriate safety measures for any visit to site, either before or after acceptance of bid. Perform work in accordance with the 1.6 CODES AND .1 latest edition of the National STANDARDS Building Code of Canada, FC Standard 373 - Standard for Piers and Wharves (http://www.hrsdc.gc.ca/eng/labour/f ire protection/policies standards/co mmissioner/373/page00.shtml), and any other code of provincial or local application including all amendments up to project bid closing date provided that in any case of

conflict or discrepancy, the more stringent requirements shall apply.

DFO	GENER	AL INSTRUCTIONS	Section 01 10 10
P/N C2-00517			Page 3
Floating Dock Construc	tion		
Pugwash, NS			
	.2	Materials and workm or exceed requireme standards, codes an documents.	anship must meet nts of specified d referenced
<u>1.7 TERM ENGINEER</u>	.1	Unless specifically otherwise, the term used in the Specifi the Drawings shall Departmental Repress defined in the Gene the Contract.	stated Engineer where cations and on mean the entative as ral Conditions of
1.8 SETTING OUT WORK	.1	Set grades and layo from control points established by Depa Representative.	ut work in detail and grades rtmental
	.2	Assume full respons execute complete la locations, lines an indicated or as dir Departmental Repres	ibility for and yout of work to d elevations ected by entative.
	.3	Provide devices nee construct work.	ded to layout and
	.4	Supply such devices edges and templates facilitate Departme Representative's in	as straight required to ntal spection of work.
	.5	Supply stakes and o markers required fo work.	ther survey r laying out
1.9 COST BREAKDOWN	.1	Before submitting f claim submit breakd price in detail as Departmental Repres aggregating contrac Departmental Repres provide the require application of prog	irst progress own of Contract directed by entative and t price. entative will d forms for ress payment.

Section 01 10 10 DFO GENERAL INSTRUCTIONS P/N C2-00517 Page 4 Floating Dock Construction Pugwash, NS .2 Provide cost breakdown in same format as the numerical and subject title system used in this specification project manual and thereafter sub-divided into major work components as directed by Departmental Representative. .3 Upon approval by Departmental Representative, cost breakdown will be used as basis for progress payment. 1.10 WORK SCHEDULE & .2 Submit within 7 work days of COMPLETION DATE notification of acceptance of bid, a construction schedule showing commencement and completion of all work within the time stated on the Bid and Acceptance Form and the date stated in the bid acceptance letter. .3 Provide sufficient details in schedule to clearly illustrate entire implementation plan, depicting efficient coordination of tasks and resources, to achieve completion of work on time and permit effective monitoring of work progress in relation to established milestones. .4 As a minimum, work schedule to be prepared and submitted in the form of Bar (GANTT) Charts, indicating work activities, tasks and other project elements, their anticipated durations and planned dates for achieving key activities and major project milestones provided in

sufficient details and supported by

GENERAL INSTRUCTIONS

P/N C2-00517 Floating Dock Construction Pugwash, NS

DFO

Section 01 10 10 Page 5

narratives to demonstrate a reasonable plan for completion of project within designated time, e.g., show target dates for the placement of each crib, if applicable. Generally Bar Charts derived from commercially available computerized project management system are preferred but not mandatory.

- .5 Submit schedule updates on a minimum monthly basis and more often, when requested by Departmental Representative, due to frequent changing project conditions. Provide a narrative explanation of necessary changes and schedule revisions at each update.
- .6 The schedule, including all updates, shall be to Departmental Representative's approval. Take necessary measures to complete work within approved time. Do not change schedule without Departmental Representative's approval.
- .7 All work on the project will be completed within the time indicated on the Bid and Acceptance Form.

1.11 ABBREVIATIONS

.1 Following abbreviations of standard specifications have been used in this specification and on the drawings: CGSB - Canadian Government Specifications Board CSA - Canadian Standards Association NLGA - National Lumber Grades Authority ASTM - American Society for Testing and Materials DFO GENERAL INSTRUCTIONS P/N C2-00517 Floating Dock Construction Pugwash, NS .2 Where these abbreviations and

standards are used in this project, latest edition in effect on date of bid call will be considered applicable.

Section 01 10 10

Page 6

1.12 QUARRY AND EXPLOSIVES

- Make own arrangements with .1 Provincial authorities and owners of private properties, for the guarrying and transportation of rock and all materials and machinerv necessary for work over their property, roads or streets as case may be.
- 1.13 SITE OPERATIONS .1 Arrange for sufficient space adjacent to project site for conduct of operations, storage of materials and so on. Exercise care so as not to obstruct or damage public or private property in area. Do not interfere with normal day-to-day operations in progress at site. All arrangements for space and access will be made by Contractor.
 - Remove snow and ice as required to .2 maintain safe access in a manner that does not damage existing structures or interfere with the operations of others.

1.14 PROJECT MEETINGS

- Departmental Representative will .1 arrange project meetings and assume responsibility for setting times and recording minutes.
 - .2 Project meetings will take place on site of work unless so directed by the Departmental Representative.

DFO	GENER	AL	INSTRUCTIONS	Section 01 10 10
P/N C2-00517				Page 7
Floating Dock Construc	tion			-
Pugwash, NS				
	.3	De as: min co mee	partmental Repres sume responsibili nutes of meetings pies to all parti etings.	entative will ty for recording and forwarding es present at the
	.4	Ha pre	ve a responsible : esent at all proj	member of firm ect meetings.
1.15 PROTECTION	.1	Sto be dar	ore all materials incorporated int mage by any means	and equipment to o work to prevent •
	.2	Rej equ sto Dej no	pair or replace a uipment damaged i orage to the sati partmental Repres cost to Canada.	ll materials or n transit or sfaction of entative and at
1.16 EXISTING SERVICES	.1	Whe con ca: gov of	ere work involves nnecting to exist rry out work at t verning authoriti disturbance to s	breaking into or ing services, imes directed by es, with minimum ite operations.
	.2	Be: loo in Dep fin	fore commencing w cation and extent area of work and partmental Repres ndings.	ork, establish of service lines notify entative of
	.3	Sul apj Rej	bmit schedule to proval from Depar presentative for	and obtain tmental any shut-down or ervice or

closure of active service or facility. This includes disconnection of electrical power and communication services to tenant's operational areas. Adhere to approved schedule and provide notice to affected parties.

DFO P/N C2-00517 Floating Dock Construct	GENER ction	AL INSTRUCTIONS	Section 01 10 10 Page 8
Pugwash, NS	.4	Provide temporary s directed by Departm Representative, to facility systems.	ervices, when ental maintain critical
	.5	Provide adequate br trenches which cros roads to permit nor	idging over s walkways or mal traffic.
	.6	Where unknown servi encountered, immedi Departmental Repres confirm findings in	ces are ately advise entative and writing.
	.7	Protect, relocate o existing active ser required. When inac encountered, cap of approved by authori jurisdiction over s locations of mainta and abandoned servi	r maintain vices as tive services are f in manner ties having ervice. Record ined, re-routed ce lines.
1.17 DOCUMENTS <u>REQUIRED</u>	.1	Maintain at job sit of the following: .1 Contract Drawi .2 Specifications .3 Addenda .4 Reviewed Shop .5 List of outsta drawings .6 Change Orders .7 Other modifica .8 Field Test Rep .9 Copy of Approv .10 Site specific Plan and other safe documents .11 Other document elsewhere in the Co	e, one copy each ngs Drawings nding shop tions to Contract orts ed Work Schedule Health and Safety ty related s as stipulated entract Documents.
1.18 PERMITS	.1	Obtain and pay for certificates and li required by Municip Federal and other A	all permits, censes as al, Provincial, uthorities.

DFO			GENER	AL INSTRUCTIONS	Section 01 10 10
P/N C2-00)517				Page 9
Floating	Dock	Construc	tion		2
Pugwash,	NS				
			.2	Provide appropriate	notifications of
				project to municipa	l and provincial
				inspection authorit	ies.
			.3	Obtain compliance c	ertificates as
				prescribed by legis	lative and
				regulatory provisio	ns of municipal,
				provincial and fede	ral authorities
				as applicable to th	e performance of
				work.	L
			.4	Submit to Departmen	tal
				Representative, cop	y of application
				submissions and app	roval documents
				received for above	referenced
				authorities.	
			.5	Submit to Departmen	tal
				Representative, cop	y of quarry
				permit, if applicab	le, prior to
				start of quarry ope	rations.
			.6	Comply with all req	uirements,
				recommendations and	advice by all
				regulatory authorit	ies unless
				otherwise agreed in	writing by
				Departmental Repres	entative. Make
				requests for such a	eviations to
				chese requirements	work
				advance of related	WOIK.
1.19 CUTT	ING.	FITTING	.1	Execute cutting, in	cluding
AND PATCH	HING		• –	excavation, fitting	and patching
				required to make wo	rk fit properly.
			0	Mhono nou ucul or a	
			• 2	where new work conn	ects with ovisting work is
				altered cut natch	and make good to
				match existing work	
					-
			.3	Do not cut, bore, o	r sleeve load-
				bearing members.	

.4 Make cuts with clean, true, smooth edges. Make patches inconspicuous in final assembly.

DFO P/N C2-00517 Floating Dock Construc Pugwash, NS	GENER tion	AL INSTRUCTIONS	Section 01 10 10 Page 10
1.20 LOCATION OF EQUIPMENT	.1	Location of equipmes power pedestals and or specified shall is approximate. Actual be as required to so time of installation reasonable. Obtain Departmental Represe	nt, fixtures, outlets, shown be considered as location shall uit conditions at n and as is approval of entative.
	.2	Locate equipment, f distribution system minimum interference usable space and in manufacturer's recons safety, access and p	ixtures and s to provide e and maximum accordance with mmendations for maintenance.
	.3	Inform Departmental when impending insta conflicts with other components. Follow actual location.	Representative allation r new or existing directives for
	.4	Submit field drawing relative position o services and equipme by Departmental Rep.	gs to indicate f various ent when required resentative.
1.21 FISH HABITAT	.1	This work is being area where fish hab affected. Perform we with rules and regu- fish habitat.	conducted in an itat may be ork to conform lations governing
	.2	Contact the Protect Marine Development Infrastructure Unit 2508, at least 48 h of starting any wor	ion Program, and at (709) 772- ours in advance k on site.
1.22 NOTICE TO SHIPPING/MARINERS	.1	Notify the Marine Contraffic Services' Contract Services' Contract Services' Contract Services and Ocean (709) 772-2083, ten to commencement and	ommunications and entre, of s Canada, at (10) days prior upon completion

DFO P/N C2-00517 Floating Dock Construc Pugwash, NS	GENER tion	AL INSTRUCTIONS	Section 01 10 10 Page 11
		of the work, in orde the issuance of Not Shipping/Mariners.	er to allow for ices to
	.2	During construction barges utilized mus- accordance with the the Canada Shipping Regulations.	any vessels or t be marked in provisions of Act Collision
1.23 ACCEPTANCE	.1	Prior to the issuand Certificate of Subs Performance, in comp Departmental Repress check of all work. (discrepancies before inspection and accep	ce of the tantial pany with entative , make a Correct all e final ptance.
1.24 WORKS COORDINATION	.1	The contractor shall for coordinating the various trades, when such trades interface other.	l be responsible e work of the re the work of ces with each
	.2	Convene meetings be whose work interface that they are fully areas and the exten- interfacing is required each trade with the specifications of the trade, as required, in planning and cars respective work.	tween trades es and ensure aware of the t of where ired. Provide plans and he interfacing to assist them rying out their
	.3	Canada will not be a or held accountable costs incurred as a failure to carry our work. Disputes betwee trades as a result of being informed of the extent of interface	responsible for for any extra result of the t coordination een the various of their not he areas and work shall be

Section 01 10 10 DFO GENERAL INSTRUCTIONS Page 12 P/N C2-00517 Floating Dock Construction Pugwash, NS the sole responsibility of the General Contractor and shall be resolved at no extra cost to Canada. Construction operations, including 1.25 CONTRACTOR'S USE .1 OF SITE storage of materials for this contract, not to interfere with the fishing activity and/or operations at this harbour facility. Contractor's use of site is to be coordinated with the Cheticamp Harbour Authority, attention Mr. Stephen Ferdinand at (902)664-8778. .2 The contractor shall be responsible for arranging the storage of materials on or off site, and any materials stored at the site which interfere with any of the day to day activities at or near the site will be moved promptly at the Contractor's expense, upon request by Departmental Representative. .3 Contractor will take adequate precautions to protect existing concrete decks and asphalt when operating tracked equipment. Exercise care so as not to obstruct .4 or damage public or private property in the area. At completion of work, restore area .5 to its original condition. Damage to ground and property will be repaired by Contractor. Remove all construction materials, residue, excess, etc., and leave site in a

condition acceptable to Departmental

Representative.

DFO P/N C2-00517 Floating Dock Construct	GENER tion	AL INSTRUCTIONS	Section 01 10 10 Page 13
rugwash, NS			
1.26 WORK COMMENCEMENT	.1	Mobilization to pro commence immediatel acceptance of bid a Site Specific Safet otherwise agreed by Representative.	ject site is to y after nd submission of y Plan, unless Departmental
	.2	Project work on sit as soon as possible continuous reasonab unless otherwise ag Departmental Repres	e is to commence , with a le work force, reed by entative.
	.3	Weather conditions, construction season challenges and the work site may requi longer working days work force to compl within the specifie time.	short , delivery location of the re the use of and additional ete the project d completion
	.4	Make every effort t sufficient material delivered to site a possible date after bid and replenished	o ensure that and equipment is t the earliest acceptance of as required.
1.27 FACILITY SMOKING ENVIRONMENT	.1	Comply with smoking	restrictions.
1.28 INTERPRETATION OF DOCUMENTS	.1	Supplementary to th Precedence article Conditions of the C Division 01 section over the technical sections in other D	e Order of of the General ontract, the s take precedence specification ivisions of the

Specification Manual.

DFO PROJECT PARTICULARS P/N C2-00517 AND MEASUREMENT Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

1.1 DESCRIPTION .1 This section details the measurement method to be used for payment purposes. Incidental items covered in the various sections of the Specification are to be allowed for in the pricing of each pay item.

- 1.2 MEASUREMENT FOR PAYMENT
- .1 **LUMP SUM ITEMS:** The following items are to be measured separately for costing purposes, then combined and submitted as one item under Lump Sum items in the tender Documents:

Division 01

Departmental Representative's Site Office: All work associated with the supply, maintenance, and removal from site of the Departmental Representative's site office per Section 01 50 00 of the Specification will constitute a lump sum for measurement purposes.

Mobilization and Demobilization: will be measured for payment by the lump sum. For measurement purposes this item will be considered 50% complete upon commencement of the project and 100% complete upon project completion.

Division 02

Sitework, Demolition, and Removals: Sitework, demolition, and removals including disposal off-site will be measured for payment by the lump sum including:

.1 All normal removals as required to complete the work. All items to be verified by a site

DFO	PROJECT PARTICULARS	Section 01 29 00
P/N C2-00517	AND MEASUREMENT	Page 2
Floating Dock	Construction	
Pugwash, NS		

visit prior to submission of a tender.

- .3 Any regrading of the site required to provide the final grades as indicated on the drawings up to the underside of new Type 2 fill.
- .4 All excavation, repairs and relocation of armour stone at the existing breakwater.
- .5 All excavation and reinstallation of existing corestone berm material required to install new retaining walls.

Division 35

Dredging: Dredging for the new floating docks will not be measured for payment and will be a Lump Sum item. The Lump Sum price will also include the cost of roadway construction (if applicable) and all means required to dispose of dredge spoils in the adjacent containment berm and graded with 2% cross slope as noted.

To aid in contractor bidding, the total estimated dredge quantity based on 2017 soundings is 1200 m³. Should this quantity vary, no additional payment will be considered.

.2 UNIT PRICE ITEMS: The following items outline the unit of measurement for unit price items as indicated in the tender documents.

Division 03

Reinforced Concrete Retaining Wall: Supply and installation of DFO PROJECT PARTICULARS Section 01 29 00 P/N C2-00517 AND MEASUREMENT Page 3 Floating Dock Construction Pugwash, NS

> reinforced concrete abutments and retaining walls including excavation, 300mm thick levelling course, drainage sleeves, and metal attachment for strongarms will be measured for payment by the cubic metre. Contractor to provide all plant, equipment, material, and labour including but not limited to formwork, falsework, concrete, cold weather protection, reinforcing steel, steel strongarm attachment, anchor bolts, precast footing, and cast-in-place walls.

Division 05

Steel Strongarms: Supply and installation of steel strongarms shall be measured by payment per each. Contractor to provide all plant, equipment, material, and labour including but not limited to galvanizing, pin connections to abutment and floating docks, neoprene gaskets between strongarms and aluminum gangways, and steel strongarms as indicated.

Aluminum Gangways: Supply and installation of aluminum gangways shall be measured by payment per each. Contractor to provide all plant, equipment, material, and labour including but not limited to flip plates at ends of gangways, connection of gangway to steel strongarms, and aluminum gangways as indicated.

Division 31

<u>Type 1 Fill:</u> The supply and installation of Type 1 Fill will be DFO PROJECT PARTICULARS Section 01 29 00 P/N C2-00517 AND MEASUREMENT Page 4 Floating Dock Construction Pugwash, NS

> measured for payment by the tonne. Contractor to provide all plant, equipment, material, and labour including but not limited to supply and placement of Type 1 fill as indicated on the drawings.

> Type 2 Fill: The supply and installation of Type 2 Fill will be measured for payment by the tonne. Contractor to provide all plant, equipment, material, and labour including but not limited to supply and placement of Type 2 fill as indicated on the drawings.

> <u>Geotextiles:</u> The supply and installation of geotextiles for the reinstated rip rap revetment slopes and underneath the Type 1 Fill will be measured for payment by the square metre. Contractor to provide all plant, equipment, material, and labour including but not limited to supply and placement of geotextile as indicated on the drawings.

<u>Floating Docks</u>: The supply and installation of floating docks will be measured for payment per each. Contractor to provide all plant, equipment, material, and labour including but not limited to timber, fastenings, and buoyancy compartments. DFO PAYME P/N C2-00517 TESTING Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

<u>1.1 SECTION INCLUDES</u> .1 Inspecting and testing by inspecting firms or testing laboratories designated by Departmental Representative.

- 1.3 APPOINTMENT AND .1 PAYMENT
- Departmental Representative will appoint and pay for services of testing laboratory except for the following: Inspection and testing required .1 by laws, ordinances, rules, regulations or orders of public authorities. .2 Inspection and testing performed exclusively for Contractor's convenience. Mill tests and certificates of .3 compliance. .4 Tests specified to be carried out by Contractor under the supervision of Departmental Representative. .5 Tests requested by Departmental representative to confirm material specifications when the applicable manufacturer's documentation or test results are unavailable. Additional tests specified in .6 the following paragraph.
 - .2 Where tests or inspections by designated testing laboratory reveal Work not in accordance with contract requirements, pay costs for additional tests or inspections as required by Departmental

DFO PAYMENT PROCEDURES FOR Section 01 29 83 P/N C2-00517 TESTING LABORATORY SERVICES Page 2 Floating Dock Construction Pugwash, NS Representative to verify acceptability of corrected work. 1.4 CONTRACTOR'S .1 Provide labour, equipment and facilities to: RESPONSIBILITIES Provide access to Work to be .1 inspected and tested. .2 Facilitate inspections and tests. .3 Make good Work disturbed by inspection and test. .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples. Notify Departmental Representative .2 sufficiently in advance of operations to allow for assignment of laboratory personnel and scheduling of test. .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory. .4 Pay costs for uncovering and making good Work that is covered before required inspection or testing is completed and approved by Departmental Representative. PART 2 - PRODUCTS 2.1 NOT USED .1 Not Used. PART 3 - EXECUTION

3.1 NOT USED .1 Not Used.

DFO SUBM P/N C2-00517 Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

- 1.1 SECTION INCLUDES .1 Shop drawings and product data.
 - .2 Samples.
 - .3 Certificates.

1.2 SUBMITTAL GENERAL REQUIREMENTS

- .1 Submit to Departmental Representative for review submittals listed, including shop drawings, samples, certificates and other data, as specified in other sections of the Specifications.
 - .2 Submit with reasonable promptness and in orderly sequence so as to allow for Departmental Representative's review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
 - .3 Do not proceed with work until relevant submissions are reviewed by Departmental Representative.
 - .4 Present shop drawings, product data, samples and mock-ups in SI Metric units.
 - .5 Where items or information is not produced in SI Metric units, provide soft converted values.
 - .6 Review submittals prior to submission to Departmental Representative. Ensure during review that necessary

DFO SUBMITTAL PROCEDURES P/N C2-00517 Floating Dock Construction Pugwash, NS

requirements have been determined and verified, required field measurements or data have been taken, and that each submittal has been checked and co-ordinated with requirements of Work and Contract Documents. .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected. Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations. Verify field measurements and . 8 affected adjacent work and coordinate. .9 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals. Contractor's responsibility for .10 deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review. Submittal format: paper

.7

.11 originals, or alternatively clear and fully legible photocopies of originals. Facsimiles are not acceptable, except in special circumstances pre-approved by Departmental

Section 01 33 00 DFO SUBMITTAL PROCEDURES P/N C2-00517 Page 3 Floating Dock Construction Pugwash, NS Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted and be returned for resubmission. Make changes or revision to .12 submissions which Departmental Representative may require, consistent with Contract Documents and resubmit as directed by Departmental Representative. When resubmitting, notify Departmental Representative in writing of any revisions other than those requested. Keep one reviewed copy of each .13 submittal document on site for duration of Work. The term "shop drawings" means 1.3 SHOP DRAWINGS AND .1 PRODUCT DATA drawings, diagrams, illustrations, schedules, performance charts, product data, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work. .2

- .2 Shop drawings only required for details that are not sufficiently detailed in the contract drawings. Confirm with Departmental Representative prior to submitting shop drawings.
- .3 Number of Shop Drawings: submit sufficient copies of shop drawings which are required by the General Contractor and subcontractors plus 2 copies which will be retained by Departmental

	Representative. Ensure sufficient numbers are submitted to enable one complete set to be included in each of the maintenance manuals specified, if applicable.
.4	Shop Drawings Content and Format: .1 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where items or equipment attach or connect to other items or equipment, confirm that all interrelated work have been coordinated, regardless of section or trade from which the adjacent work is being supplied and installed.
	.2 Shop Drawings Format: .1 Opaque white prints or photocopies of original Drawings or standard drawings modified to clearly illustrate work specific to project requirements. Maximum sheet size to be 1000 x 707 mm. .2 Product Data from Manufacturer's standard catalogue sheets, brochures, literature, performance charts and diagrams, used to illustrate standard manufactured products, to be original full colour brochures, clearly marked indicating applicable data and deleting information not applicable to project.

DFO SUBM P/N C2-00517 Floating Dock Construction Pugwash, NS

SUBMITTAL PROCEDURES DFO P/N C2-00517 Floating Dock Construction Pugwash, NS

Non or poorly legible drawings, photocopies or facsimiles will not be accepted and returned not reviewed. Supplement manufacturer's .3 standard drawings and literature with additional information to provide details applicable to project. .4 Delete information not applicable to project on all submittals. Allow 10 calendar days for Departmental Representative's review of each submission. Adjustments or corrections made on shop drawings by Departmental Representative are not intended to change Contract Price. If adjustments affect value of Work, advise Departmental Representative in writing prior to proceeding with Work. If upon review by Departmental Representative, no errors or omissions are discovered or if only minor corrections and comments are made, fabrication and installation may proceed upon receipt of shop drawings. If shop drawings are rejected and noted to be Resubmitted, do not proceed with that portion of work until resubmission and review of corrected shop drawings, through same submission procedures indicated

.3

.5

.6

.7

above.

DFO SUBMITTAL PROCEDURES Section 01 33 00 P/N C2-00517 Page 6 Floating Dock Construction Pugwash, NS .8 Accompany each submission with

Accompany each submission with transmittal letter, containing: .1 Date. .2 Project title and project number. .3 Contractor's name and address. .4 Identification and quantity of each shop drawing, product data and sample. Other pertinent data. .5 .9 Submissions shall include: .1 Date and revision dates. .2 Project title and project number. Name and address of: . 3 .1 Subcontractor. .2 Supplier. Manufacturer. .3 .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents. Cross references to .5 particular details of contract drawings and specifications section number for which shop drawing submission addresses. Details of appropriate .6 portions of Work as applicable: Fabrication. .1 .2 Layout, showing dimensions, including identified field dimensions, and clearances. .3 Setting or erection details. .4 Capacities. Performance .5 characteristics. .6 Standards.

P/N C2-00517 Floating Dock Construction Pugwash, NS

DFO

- .7 Operating weight.
 .8 Wiring diagrams.
 .9 Single line and schematic diagrams.
 .10 Relationship to adjacent work.
- .10 After Departmental Representative's review, distribute copies.
- The review of shop drawings by .11 the Departmental Representative or their delegated representative is for sole purpose of ascertaining conformance with general concept. This review shall not mean that Fisheries and Oceans Canada approves the detail design inherent in the shop drawings, responsibility for which shall remain with Contractor submitting same, and such review shall not relieve Contractor of responsibility for errors or omissions in shop drawings or of responsibility for meeting all requirements of the construction and Contract Documents. Without restricting generality of foregoing, Contractor is responsible for dimensions to be confirmed and correlated at job site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for coordination of Work of all subtrades.

DFO P/N C2-00517 Floating Dock Construc Pugwash, NS	SUBMITTAL tion	PROCEDURES	Section 01 33 00 Page 8
1.4 SCHEDULES, PERMITS AND CERTIFICATES	AND .1	Upon acceptanc to Departmenta copy of Work S various other permits, certi and project ma specified in o the Specificat	e of bid, submit l Representative chedule and schedules, fication documents nagement plans as ther sections of ions.
	.2	Submit copy of compliance Cer by Regulatory jurisdiction a to the Work.	permits, notices, tificates received Agencies having nd as applicable
	.3	Submission of be in accordan General Requir specified in t	above documents to ce with Submittal ements procedures his section.

DFO SPECIAL PROCEDURES ON Section 01 35 24 P/N C2-00517 FIRE SAFETY REQUIREMENTS Page 1 Floating Dock Construction Pugwash, NS 1.1 SECTION INCLUDES .1 Fire Safety Requirements. .2 Hot Work Permit. 1.2 RELATED WORK .1 Section 01 35 25 - Special Procedures on Lockout Requirements. .2 Section 01 35 28 - Health and Safety Requirements. Fire Protection Standards issued by 1.3 REFERENCES .1 Fire Protection Services of Human Resources Development Canada as follows: FC No. 301-latest edition .1 Standard for Construction Operations (http://www.hrsdc.gc.ca/eng/labour/ fire protection/policies standards/ commissioner/301/page01.shtml). FC No. 302-latest edition .2 Standard for Welding and Cutting (http://www.hrsdc.gc.ca/eng/labour/ fire protection/policies standards/ commissioner/302/page01.shtml). Hot Work defined as: 1.4 DEFINITIONS .1 .1 Welding work. Cutting of materials by use of .2 Torch or other open flame devices. .3 Grinding with equipment which produces sparks. 1.5 SUBMITTALS .1 Submit copy of Hot Work Procedures and sample of Hot Work permit to Departmental Representative for review, within 14 calendar days after notification of acceptance of bid.

DFO SPECIAL PROCEDURES ON Section 01 35 24 P/N C2-00517 FIRE SAFETY REQUIREMENTS Page 2 Floating Dock Construction Pugwash, NS .2 Submit in accordance with the Submittal General Requirements specified in Section 01 33 00. 1.6 FIRE SAFETY .1 Implement and follow fire safety measures during Work. Comply with REQUIREMENTS following: .1 National Fire Code, 2010. Fire Protection Standards FC .2 301 and FC 302. Federal and Provincial . 3 Occupational Health and Safety Acts and Regulations as specified in Section 01 35 28. .2 In event of conflict between any provisions of above authorities the most stringent provision will apply. Should a dispute arise in determining the most stringent requirement, Departmental Representative will advise on the course of action to be followed. 1.7 HOT WORK Obtain Departmental Representative's .1 written "Authorization to Proceed" AUTHORIZATION before conducting any form of Hot work on site. To obtain authorization submit to .2 Departmental Representative: Contractor's typewritten Hot .1 Work Procedures to be followed on site as specified below. .2 Description of the type and frequency of Hot Work required. Sample Hot Work Permit to be .3 used. Upon review and confirmation that .3 effective fire safety measures will be implemented during performance of

hot work, Departmental

DFO SPECIAL PROCEDURES ON Section 01 35 24 P/N C2-00517 FIRE SAFETY REQUIREMENTS Page 3 Floating Dock Construction Pugwash, NS

Representative will provide authorization to proceed as follows: Issue one written .1 "Authorization to Proceed" covering the entire project for duration of work or; Separate work, or segregate .2 certain parts of work, into individual entities. Each entity requiring a separately written "Authorization to Proceed" from Departmental Representative. Follow Departmental Representative's directives in this regard. .4 Requirement for individual authorization based on: Nature or phasing of work; .1 .2 Risk to Facility operations; .3 Quantity of various trades needing to perform hot work on project or; Other situation deemed .4 necessary by Departmental Representative to ensure fire safety on premises. .5 Do not perform any Hot Work until receipt of Departmental Representative's written "Authorization to Proceed" for that portion of work. In tenant occupied Facility, .6 coordinate performance of Hot Work with Facility Manager through the Departmental Representative. When directed, perform Hot Work only during non-operative hours of Facility. Follow Departmental Representative's directives in this

regard.

DFO P/N C2-00517 Floating Dock Constr Pugwash, NS	SPECIA FIRE SA ruction	AL PROCEDURES ON Section 01 35 24 FETY REQUIREMENTS Page 4
1.8 HOT WORK PROCEDURES	.1	Develop and implement safety procedures and work practices to be followed during the performance of Hot Work.
	.2	<pre>Procedures to include: .1 Requirement to perform hazard assessment of site and immediate hot work area for each hot work event in accordance with Hazard Assessment and Safety Plan requirements of Section 01 35 28. .2 Use of a Hot Work Permit system for each hot work event. .3 The step by step process of how to prepare and issue permit. .4 Permit shall be issued by Contractor's site Superintendent, or other authorized person designated by Contractor, granting permission to worker or subcontractor to proceed with hot work. .5 Provision of a designated person to carry out a Fire Safety Watch for a minimum of 60 minutes immediately upon completion of the hot work. .6 Compliance with fire safety codes and standards specified herein and occupational health and safety regulations specified in Section 01 35 28.</pre>
	.3	Generic procedures, if used, must be edited and supplemented with pertinent information tailored to reflect specific project conditions. Clearly label as being the Hot Work Procedures applicable to this contract.
	.4	Hot Work Procedures shall clearly establish worker instructions and allocate responsibilities of: .1 Worker(s),

DFO SPECIAL PROCEDURES ON Section 01 35 24 P/N C2-00517 FIRE SAFETY REQUIREMENTS Page 5 Floating Dock Construction Pugwash, NS .2 Authorized person issuing the Hot Work Permit, .3 Fire Safety Watcher, .4 Subcontractors and Contractor. .5 Brief all workers and subcontractors on Hot Work Procedures and Permit system established for project. Stringently enforce compliance. Failure to comply with the .1 established procedures may result in the issuance of a Non-Compliance Notification at Departmental Representative's discretion with possible disciplinary measures imposed as specified in Section 01 35 28. 1.9 HOT WORK PERMIT .1 Hot Work Permit to include, as a minimum, the following data: .1 Project name and project number. Building name, address and .2 specific room or area where hot work will be performed. Date when permit issued. .3 .4 Description of hot work type to be performed. Special precautions required, .5 including type of fire extinguisher needed. .6 Name and signature of person authorized to issue the permit. Name of worker (clearly .7 printed) to which the permit is being issued. Time Duration that permit is .8 valid (not to exceed 8 hours). Indicate start time and date, and completion time and date. Worker signature with date and .9 time upon hot work termination. .10 Specified time period requiring safety watch.
DFO	SPECIAL PROCEDURES ON	Section 01 35 24
P/N C2-00517	FIRE SAFETY REQUIREMENTS	Page 6
Floating Dock	Construction	
Pugwash, NS		

.11 Name and signature of designated Fire Safety Watcher, complete with time and date when safety watch terminated, certifying that surrounding area was under continual surveillance and inspection during the full watch time period specified in Permit and commenced immediately upon completion of Hot Work.

- .2 Permit to be typewritten form. Industry Standard forms shall only be used if all data specified above is included on form.
- .3 Each Hot Work Permit to be completed in full and signed as follows:

 Authorized person issuing
 Permit before hot work commences.
 Worker upon completion of Hot

 Work.

 Fire Safety Watcher upon termination of safety watch.
 Returned to Contractor's Site Superintendent for safe keeping.
- 1.10 DOCUMENTS ON SITE .1
 - Keep Hot Work Permits and Hazard assessment documentation on site for duration of Work.
 - .2 Upon request, make available to Departmental Representative or to authorized safety representative for inspection.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	HEAI R tion	LTH AND SAFETY EQUIREMENTS	Section 01 35 28 Page 1
1.1 RELATED WORK	.1	Section 01 35 2 Procedures on E Requirements.	24 - Special Fire Safety
	.2	Section 01 35 2 Procedures on I	25 - Special Lockout Requirements.
<u>1.2 SUBMITTALS</u>	.1	Submit to Depar Representative following docum updates: .1 Site Speci Plan. .2 Building H certificates ar obtained. .3 Reports or Federal and Pro and other Author jurisdiction. .4 Accident of .5 MSDS data .6 Name of Co representative health and safe site.	copies of the ments, including fic Health and Safety Permit, compliance ad other permits c directions issued by ovincial Inspectors orities having or Incident Reports. sheets. ontractor's designated to perform ety supervision on
	.2	Upon request by Representative, other documenta be produced and Federal and Pro Health and Safe specified herei	y Departmental submit reports and ation as stipulated to d maintained by ovincial Occupational ety Regulations and as in.
	.3	Submit above do with the submit specified in Se	ocuments in accordance tal procedures ection 01 33 00.
1.3 COMPLIANCE REQUIREMENTS	.1	Comply with the and Safety Act Nova Scotia, ar Health and Safe pursuant to the	e Occupational Health for the Province of nd the Occupational ety Regulations made e Act.

DFO	HEA	LTH AND SAFETY	Section 01 35 28
P/N C2-00517	F	REQUIREMENTS	Page 2
Floating Dock Construct	cion		
Pugwash, NS			
	.2	Comply with Canada II, and the Canada Safety and Health R under Part II of th Code.	Labour Code Part Occupational egulations made e Canada Labour
	.3	Observe and enforce safety measures req .1 2015 National Canada, Part 8. .2 Provincial Wor Compensation Board. .3 Municipal stat ordinances.	construction uired by: Building Code of ker's utes and
	.4	In event of conflic provisions of above most stringent prov Should a dispute ar determining the mos requirement, Depart Representative will course of action to	t between any authorities the ision will apply. ise in t stringent mental advise on the be followed.
	.5	Maintain Workers Co Coverage for durati Submit Letter of Go Departmental Repres of submitting the P Safety Plan and wit for Progress Paymen	mpensation on of Contract. ood Standing to sentative at time Project Health and th each Request
<u>1.4 RESPONSIBILITY</u>	.1	Be responsible for of persons on site, for protection of p circulating adjacen operations to exten be affected by cond	health and safety of property and ersons and public t to work t that they may suct of the Work.
	.2	Enforce compliance sub-contractors and granted access to w safety requirements	by all workers, other persons ork site with of Contract

Documents, applicable Federal, Provincial, and local statutes, DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 3 Floating Dock Construction Pugwash, NS regulations, and ordinances, and with site specific Health and Safety Plan. 1.5 SITE CONTROL AND .1 Control work site and entry points to construction areas. ACCESS Delineate and isolate .1 construction areas from other areas of site by use of appropriate means. .2 Post notices and signage at entry points and at other strategic locations identifying entrance onto site to be restricted to authorized persons only. .3 Signage must be professionally made, bilingual in both official languages or display internationally understood graphic symbols. .2 Approve and grant access to site only to workers and authorized persons. Immediately stop non-authorized .1 persons from circulating in construction areas and remove from site. .2 Provide site safety orientation to all persons before granting access. Advise of site conditions, hazards and mandatory safety rules to be observed on site. .5 Secure site at night time to extent required to protect against unauthorized entry. Provide security guard where protection cannot be achieved by other means. Ensure persons granted access to .6 site wear appropriate personal protective equipment (PPE) suitable to work and site conditions. Provide such PPE to authorized .1 persons who require access to perform inspections or other approved purposes.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	HEAI R ion	LTH AND SAFETY EQUIREMENTS	Section 01 35 28 Page 4	
1.6 PROTECTION	.1	Carry out work placing emphasis on health and safety of the Public, Facility personnel, construction workers and protection of the environment.		
	.2	Erect safety barrie signage on site to delineate work area pedestrian and vehic around and adjacent create a safe worki .1 See Section 01 minimum acceptable	ades, lights and effectively s, protect cular traffic to work, and to ng environment. 56 00 for barricades.	
	.3	Should unforeseen of related hazard or co- evident during perfo- immediately take mea- the situation and po- harm. Advise Departo Representative verbo- writing.	r peculiar safety ondition become ormance of work, asures to rectify revent damage or mental ally and in	
<u>1.7 PERMITS</u>	.1	Obtain building per compliance certific permits as specifie 10 10 before and du work. Post on site.	mit, licenses, ates and other d in Section 01 ring progress of	
	.2	Where particular per compliance certifics obtained at the required work, notify Departs Representative in with Departmental Represent approval to proceed carrying out that per	rmit or ate cannot be uired stage of mental riting and obtain entative's prior to ortion of work.	

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	HEAI R ion	LTH AND SAFETY EQUIREMENTS	Section 01 35 28 Page 5
<u>1.8 HAZARD ASSESSMENTS</u>	.1	Conduct site specif safety hazard asses commencing project of work identifying hazards resulting f conditions, weather work operations. .1 Perform on-goi addressing new risk work progresses inc subtrade or sub-con on site. .2 Also, conduct the scope of work h by Change Order and hazard or weakness and safety practice by Departmental Rep an authorized safet	fic health and sment before and during course risks and rom site conditions and ng assessments and hazards as luding when new tractor arrives assessment when as been changed when potential in current health is are identified presentative or by y representative.
	.2	Record results in w address in Health a	riting and nd Safety Plan.
	.3	Keep copy of all as site.	sessments on
1.9 PROJECT/SITE CONDITIONS	.1	The following are k project related hea environmental and s site which must be if encountered duri work: .1 Safety hazards site conditions and at adjacent operati are: .1 Fishing v harbour.	nown or potential lth, afety hazards at properly managed ng course of due to existing conduct of work onal Facility ressels using the
	.2	The following are k project related saf site: .1 Working i of water.	nown or potential ety hazards at n close proximity

Section 01 35 28 DFO HEALTH AND SAFETY P/N C2-00517 REQUIREMENTS Page 6 Floating Dock Construction Pugwash, NS .2 Use of water crafts and floating platforms. Wet and slippery .3 conditions. . 4 Inclement weather. .5 Potential structural weakness of existing structures. .6 Heavy equipment activity in the area. .7 Heavy lifting. .8 Working at heights. .9 Cutting tools and other construction power tools. .10 Overhead power/utility lines. .11 Risk of electric shock. .12 Vehicular and pedestrian traffic. .13 Confined spaces. .3 Above list shall not be construed as being complete and inclusive of potential health, and safety hazards encountered during work. Include above items into hazard assessment process. .4 Obtain from Departmental Representative, copy of MSDS Data sheets for existing hazardous products stored on site or used by Facility personnel. 1.10 HEALTH AND SAFETY .1 Attend pre-construction health and MEETINGS safety meeting conducted by Departmental Representative. Have following persons in attendance: Site Superintendent. .1 .2 Contractor's designated Health and Safety Site Supervisor. .3 Departmental Representative will advise of date, time and location.

DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 7 Floating Dock Construction Pugwash, NS .2 Conduct health and safety meetings and tool box briefings on site. Hold on a regular and pre-scheduled basis during entire work in accordance with requirements and frequency as stipulated in provincial Occupational Health and Safety Regulations. Keep workers informed of .1 potential hazards and provide safe work practices and procedures to be followed. .2 Take written minutes and post on site. 1.11 HEALTH AND SAFETY .1 Develop written site specific PLAN Project Health and Safety Plan, based on hazard assessments, prior to commencement of work. Submit copy to Departmental .1 Representative within 7 calendar days of acceptance of bid. .2 Submit updates as work progresses. Health and Safety Plan shall contain .2 three (3) parts with following information: Part 1 - Hazards: List of .1 individual health risks and safety hazards identified by hazard assessment process. Part 2 - Safety Measures: .2 Engineering controls, personal protective equipment and safe work practices used to mitigate hazards and risks listed in Part 1 of Plan. .3 Part 3a: Emergency Response: standard operating procedures, evacuation measures and emergency response in the occurrence of an accident, incident or emergency. Include response to all .1 hazards listed in Part 1 of Plan.

DFO HEALTH AND SAFETY P/N C2-00517 REQUIREMENTS Floating Dock Construction Pugwash, NS

.2 Evacuation measures to complement the Facility's existing Emergency Response and Evacuation Plan. Obtain pertinent information from Departmental Representative. List names and telephone .3 numbers of officials to contact including: .1 General Contractor and all Subcontractors. Federal and .2 Provincial Departments as stipulated by laws and regulations of authorities having jurisdiction and local emergency resource organizations, as needed base on nature of emergency. Officials from DFO .3 and site Facility Management. Departmental Representative will provide list. Part 3b - Site Communications: .1 Procedures used on site to share work related safety issues between workers, subcontractors, and General Contractor. List of critical tasks and .2 work activities, to be communicated with the Facility Manager, which has risk of affecting tenant operations, or endangering health and safety of Facility personnel and the general public. Develop list in consultation with the Departmental Representative. Prepare Health and Safety Plan in a

.4

.3 three column format, addressing the three parts specified above, as follows:

DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 9 Floating Dock Construction Pugwash, NS

> Column 1 Column 2 Column 3 Part 1 Part 2 Part 3a/3b Identified Safety Emergency Response & Measures Site Hazards Communications

- .4 Develop Plan in collaboration with subcontractors. Address work activities of all trades. Revise and update Plan as subcontractors arrive on site.
- .5 Implement and enforce compliance with requirements of Plan for full duration of work to final completion and demobilization from site.
- .6 As work progresses, review and update Plan. Address additional health risks and safety hazards identified by on-going hazard assessments.
- .7 Post copy of Plan and updates, on site.
- Submission of the Health and Safety .8 Plan and updates, to the Departmental Representative, is for review and information purposes only. Departmental Representative's receipt, review and any comments made of the Plan shall not be construed to imply approval in part, or in hold, of such Plan by Departmental Representative, and shall not be interpreted as a warranty of being complete and accurate, or as a confirmation that all health and safety requirements of the Work, have been addressed, and that it is legislative compliant. Furthermore, Departmental Representative's review of the Plan shall not relieve the Contractor of

DFO HEA P/N C2-00517 Floating Dock Construction Pugwash, NS

any of his legal obligations for Occupational Health and Safety provisions specified as part of the Work and those required by provincial legislation or those which would otherwise be applicable to the site of the work.

1.12 SAFETY SUPERVISION AND INSPECTIONS .1 Designate one person to be present on site at all times, responsible for supervising health and safety of the Work.
.1 Person to be competent in Occupational Health and Construction Safety as defined in the Provincial Occupational Health and Safety Act.

- .2 Assign responsibility, obligation and authority to such designated person to stop work as deemed necessary for reasons of health and safety.
- .3 Conduct regularly scheduled safety inspections of work site on a minimum bi-weekly basis.
 .1 Note deficiencies and remedial action taken in a log book or diary.

1.13 TRAINING

Ensure that all workers and other .1 persons granted access to site are competently trained and knowledgeable on: Safe use of tools and .1 equipment. How to wear and use personal .2 protective equipment (PPE). Safe work practices and .3 procedures to be followed in carrying out work. Site conditions and minimum . 4 safety rules to be observed on site, as given at site orientation session.

DFO	HEAL	TH AND SAFETY	Section 01 35 28
P/N C2-00517	RI	EQUIREMENTS	Page 11
Floating Dock Construct	ion		
Pugwash, NS			
1.14 MINIMUM SITE SAFETY RULES	.1	Notwithstanding the abide by federal and health and safety ru- following safety ru- considered minimum be obeyed by all per site access: .1 Wear personal per function and task of minimum requirements safety footwear and .2 Immediately rep activity or condition miss accident, inju- .3 Maintain site a condition. .4 Obey warning sa tags.	requirement to d provincial egulations, the les shall be requirements to rsons granted protective ropriate to n site; the s being hard hat, eye protection. port unsafe on at site, near- ry and damage. in tidy igns and safety
	.2	Brief workers on sig and on disciplinary taken by Department for violation or not such rules. Post ru	te safety rules measures to be al Representative n-compliance of les on site.
	.3	The following action Contractor, workers contractors will be non-conformance with safety requirements for which a Non-comp Notification will be General Contractor 1 Departmental Repress .1 Failure to fol Site safety rules sp .2 Negligence resp injury or major prop .3 Deliberate non Federal and Provinc. Regulations. .4 Falsification of Workers Compensation reports and other he related documents sp	ns or conduct by and sub- considered as h the health and of the contract pliance e issued to the by the entative: low the minimum pecified above. ulting in serious perty damage. -compliance with ial Acts and of information in n Reports, safety ealth and safety ubmitted to

DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 12 Floating Dock Construction Pugwash, NS Departmental Representative or to Authority having jurisdiction. .5 Possession of firearms on site. Possession of non-prescriptive .6 illegal drugs or alcohol. Action, or lack thereof, .7 resulting in the issuance of Warnings, Fines or Stop Work Orders from a Provincial Authority having jurisdiction. .8 Violation of other specified health and safety rules and requirements as determined by Departmental Representative. .4 See elsewhere in this section for details on Non-Compliance Notifications and resulting disciplinary measures. 1.15 ACCIDENT .1 Investigate and report the following incidents and accidents: REPORTING Those as required by Provincial .1 Occupational Safety and Health Act and Regulations. Injury requiring medical aid as .2 defined in the Canadian Dictionary of Safety Terms-1987, published by the Canadian Society of Safety Engineers (C.S.S.E)as follows: Medical Aid Injury: any .1 minor injury for which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred. Property damage in excess of .3 \$5000.00. .4 Interruption to Facility operations with potential loss to a Federal Department in excess of \$5000.00. .5 Those which require notification to Workers Compensation

DFO	HEALTH AND SAFETY Section 01 35 2		
P/N C2-0051/ Floating Dock Construct	i on	EQUIREMENTS	Page 13
Puqwash, NS	1011		
		Board or other regulas stipulated by appregulations.	latory agencies plicable law or
	.2	Send written report Representative for a	to Departmental all above cases.
1.16 TOOLS AND EQUIPMENT SAFETY	.1	Routinely check and equipment and machin operation.	maintain tools, nery for safe
	.2	Conduct checks as passive safety inspections. submit proof that cl	art of site When requested, hecks and en carried out.
	.3	Tag and immediately items found faulty of	remove from site or defective.
1.17 HAZARDOUS PRODUCTS	.1	Comply with requirer Workplace Hazardous Information System	nents of Materials (WHMIS).
	.2	Keep MSDS data sheet products delivered to site. Submit copy to Representative upon	ts for all to site. Post on Departmental receipt.
1.18 BLASTING	.1	Blasting or other us is not permitted wit written instructions Departmental Represe	se of explosives thout prior s from entative.
	.2	Do blasting operation with local and prove	ons in accordance incial codes.
1.19 POWDER ACTUATED DEVICES	.1	Use powder actuated devices only after : written permission : Representative.	fastening receipt of from Departmental

Section 01 35 28 DFO HEALTH AND SAFETY P/N C2-00517 REQUIREMENTS Page 14 Floating Dock Construction Pugwash, NS 1.20 CONFINED SPACES .1 Carry out work in confined spaces in compliance with: Provincial Occupational Safety .1 and Health Regulations; and .2 Canada Occupational Safety and Health Regulations (COSH) made under the Canada Labour Code - Part II. Conduct hazard assessment and .2 address in Safety Plan before entering confined space. .3 Provide and maintain equipment and PPE as required for the safety and emergency evacuation of persons entering confined spaced. .4 Provide training to persons who will be entering and to those persons who will be assisting in the confined space entry process. Training to be specialized instructions beyond (basic confined space entry information) as required to suit type and conditions of confined space. .5 Safety for Inspectors: .1 Upon request, provide PPE and training to Departmental Representative and to other authorized persons, for the purpose of entering confined space to conduct inspections. Be responsible for the efficacy .2 of the equipment and safety of such persons during their entry and occupancy in the confined space. Post on site safety documentation as 1.21 POSTING OF .1 stipulated by Authorities having DOCUMENTS jurisdiction and as specified herein. Place in a common visible

location.

DFO P/N C2-00517 Floating Dock Constru Pugwash, NS	HEA ction	ALTH AND SAFETY REQUIREMENTS	Section 01 35 28 Page 15
1.22 SITE RECORDS	.1	Maintain on site health and safety reports specified part of the work authorities havin	a copy of all y documentation and d to be produced as and received from ng jurisdiction.
	.2	Upon request, mal Departmental Rep authorized safety for review. Prov directed by Depa Representative.	ke available to resentative, or y representative, ide copy when rtmental
1.23 NON-COMPLIANCE AND DISCIPLINARY MEASURES	.1	Immediately addre health and safety non-compliance is	ess and correct y violations and ssues.
	.2	Negligence or far occupational heat provisions specif Documents and of laws and regulat disciplinary meas Departmental Repu the General Contr	ilure to follow Ith and safety fied in the Contract those of applicable ions could result in sures taken by the resentative against ractor.
	.3	DFO uses a system Notifications and Measures on proje .1 A non-complet is issued to the by the Department whenever there is non-compliance of health and safety of those of Prove regulations by an subcontractor or whom the Contract access to the wor .2 Non-compliant are progressive is	n of Non-Compliance d Disciplinary ects as follows: iance notification General Contractor, tal Representative, s a violation or f the project's y requirements and incial and Federal hy worker, other person to tor has granted rk site. hee notifications in nature resulting

in disciplinary measures imposed depending on the frequency, nature and severity of the infraction. DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 16 Floating Dock Construction Pugwash, NS .3 Disciplinary measures could include: Removal of the offending .1 person or party from site; .2 Financial penalties in the form of progress payment reduction or holdback assessments made against the Contract and; Taking the Work Out of .3 Contractor's Hands in accordance with the General Conditions. .4 Departmental Representative will make final decision as to what constitutes a violation and when to issue a Non-compliance Notification. .5 Non-compliance Notifications issued by Departmental Representative shall not be construed as to overrule or disregard warnings, orders and fines levied against Contractor by a regulatory agency having jurisdiction. Each non-compliance notification .6 issued is given a numerical rating based on a three level numbering system. Each level is progressive in nature to reflect: The seriousness of the .1 infraction as viewed by the Departmental Representative. The degree of disciplinary .2 action which will be taken by the Departmental Representative. .7 Numerical ratings are as follows: Non-compliance Notification-.1 Level No.1 Rating: Situation: occurrence of a .1 first time infraction by a person or party on site.

DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 17 Floating Dock Construction Pugwash, NS .2 Action: verbal warning to General Contractor, documented in Departmental files and copy sent to the General Contractor. Non-compliance Notification-.2 Level No.2 Rating: .1 Situation: .1 The second occurrence of a previous infraction by the same person or party on site or; .2 Accumulation of several level-1 notifications for different infractions by the same person or party on site or; .3 Non-action on the part of the Contractor or subcontractor to rectify non-compliance infractions previously identified in one or several level-1 notifications or; .4 Violation or nonobservance of a Federal or Provincial safety Law or Regulation by subcontractor or Contractor or; .5 Negligence by a person or party resulting in injury or major property damage. .2 Action: written notice to General Contractor complete with an order for immediate remedial action to be taken. Depending on the severity of the offense, the order may include request for the immediate removal of the offending person or party from site. .3 Non-compliance Notification-Level No.3 Rating:

DFO HEALTH AND SAFETY Section 01 35 28 P/N C2-00517 REQUIREMENTS Page 18 Floating Dock Construction Pugwash, NS Situation: .1 .1 Continued and repeated non-compliance with health and safety requirements by the General Contractor or by subcontractor(s) or; .2 The occurrence of a serious accident on site resulting in serious bodily injury or death. Action: .2 .1 Formal letter issued to General Contractor with an order to "Immediately Stop Work" until so notified to proceed. Review of all non-.2 compliance and/or accident occurrences in the project with possible investigation by DFO. Based on outcome of .3 the review/investigation, Work could be suspended or taken out of the Contractor's hands in accordance with the General Conditions. The term "serious .3 accident" used herein shall have the same meaning as defined in the Canadian Dictionary of Safety Terms -1987 issue from the Canadian Society of Safety Engineers C.S.S.E). Decision on which rating level to be .8

.8 Decision on which rating level to be placed on any given Non-Compliance Notification will be determined solely by Departmental Representative. DFO HEALTH AND SAFETY P/N C2-00517 REQUIREMENTS Floating Dock Construction Pugwash, NS

.9	Further details on the disciplinary
	system will be provided at the pre-
	construction Health and Safety
	meeting after Contract award.

- .10 Be responsible to fully brief workers and subcontractors on the operation and importance of this system.
- 1.24 DIVING OPERATIONS .1 All diving work to comply fully with the requirements of CSA Z275.2-11, "Occupational Safety Code for Diving, Operations", CSA Z275.4-12, "Competency Standards for Diving Hyperbaric Chamber, and Remotely Operated Vehicle Operations" and CSA Z180.1-13, "Compressed Breathing Air and Systems."
 - .2 Dive personnel must meet the minimum competency requirements of the CSA Z275.4-12 and all divers must possess a valid Category 1 Diving Certificate or an Unrestricted Surface-supplied Certificate.
 - .3 Diving in free-swim mode is not permitted at the work site.
 - .4 Divers must have a current less than one year validated medical examination certificate(s) from a licensed Diving Physician in Nova Scotia who is knowledgeable and competent in diving and hyperbaric medicine, for all dives.

ENVIRONMENTAL PROTECTION Section 01 35 44 DFO P/N C2-00517 PROCEDURES Page 1 Floating Dock Construction Puqwash, NS Canada Shipping Act, 2001, amended 1.1 References .1 2013-12-01; Transport Canada .2 Canadian Coast Guard Regulations, Fisheries and Oceans Canada .3 Canadian Environmental Protection Act, 1999, amended 2014-03-28; Environment and Climate Change Canada .4 Canadian Navigable Waters Act, 2019-08-28; Transport Canada .5 Fisheries Act, 1985, amended 2019-06-21; Fisheries and Oceans Canada Guidelines for the Use of .6 Explosives in or Near Canadian Fisheries Waters, 1998; Fisheries and Oceans Canada .7 Impact Assessment Act, 2019-08-28; Environment and Climate Change Canada Migratory Birds Convention Act, .8 1994, amended 2010-12-10; Environment and Climate Change Canada Nova Scotia - Environment Act .9 Species at Risk Act, 2002, amended .10 2013-03-08; Environment and Climate Change Canada and Fisheries and Oceans Canada .11 The Federal Policy on Wetland Conservation, 1991; Environment and Climate Change Canada .12 Transportation of Dangerous Goods Act, 1992, amended 2009-06-16; Transport Canada

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS

.13 Workplace Hazardous Materials Information System; Health Canada. 1.2 Definitions Archaeological resources: all .1 tangible evidence of human activity that is of historical, cultural or scientific interest. Examples include features, structures, archaeological objects or remains at or from an archaeological site, or an object recorded as an isolated archaeological find. .2 Buffer zone: a vegetated land that protects watercourses from adjacent land uses. It refers to the land adjacent to watercourses, such as streams, rivers, lakes, ponds, oceans, and wetlands, including the floodplain and the transitional lands between the watercourse and the drier upland areas. Deleterious substance: (a) any .3 substance that, if added to any water, would degrade or alter or form part of a process of degradation or alteration of the quality of that water so that it is rendered or is likely to be rendered deleterious to fish or fish habitat or to the use by man of fish that frequent that water, or (b) any water that contains a substance in such quantity or concentration, or that has been so treated, processed or changed, by heat or other means, from a natural state that it would, if added to any other water, degrade or alter or form part of a process of degradation or alteration of the quality of that water so that it is rendered or is likely to be rendered deleterious to fish or fish habitat or to the use by man of fish that frequent that water.

PROCEDURES

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 3 Floating Dock Construction Pugwash, NS

	4	Fish habitat: spawning grounds and any other areas, including nursery, rearing, food supply and migration areas, on which fish depend directly or indirectly in order to carry out their life processes.
	5	Hazardous material: product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.
	6	Invasive or alien species: refers to a species or subspecies introduced outside its normal distribution whose establishment and spread threaten ecosystems, habitats or species with economic or environmental harm.
	7	Navigable water: a canal and any other body of water created or altered as a result of the construction of any work.
	8	Surface watercourse: refers to the bed and shore of a river, stream, lake, creek, pond, marsh, estuary or salt-water body that contains water for at least part of each year.
. 9	9	Wetlands: land where the water table is at, near or above the surface or which is saturated for a long enough period to promote such features as wet-altered soils and water tolerant vegetation. Wetlands include organic wetlands or "peatlands," and mineral

excess water but produce little or no peat.

wetlands that are influenced by

 DFO
 ENVIRONMENTAL PROTECTION
 Section 01 35 44

 P/N C2-00517
 PROCEDURES
 Page 4

 Floating Dock Construction
 Pugwash, NS
 1.3 Transportation
 .1 Transport hazardous materials and hazardous waste in compliance with the Transportation of Dangerous Goods Act.

 .2
 All vessels and barges used in the work must comply with all Canada Shipping Act requirements for

		Goods Act.
	2	All vessels and barges used in the work must comply with all <i>Canada</i> <i>Shipping Act</i> requirements for inspection, which includes certification of the vessel and adequate training and appropriate certificate of competency for the operators and codes and standards of practice for shipping.
-	3	Vessels are to be permitted safe access through the worksite at all times, and assisted as necessary.
	4	All materials and equipment used in construction must be marked in accordance with the Collision Regulations of the <i>Canada Shipping</i> <i>Act, 2001</i> when located on the waterway.
	5	Work activities must comply with all / any conditions of the <i>Canadian</i> <i>Navigable Waters Act</i> issued by Transport Canada
	6	Maintain trucks clean and free of excessive mud, dirt, dredged material and other foreign matter.
	_	

- .7 All trucks to have watertight seals in their boxes to prevent leakage during loading and transporting dredge material.
- .8 Secure contents against free board spillage when excavating, loading and hauling material, including dredged material. Do not overload trucks when hauling material and avoid potential release of contents,

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 5 Floating Dock Construction Pugwash, NS

> and of any foreign matter onto highways, roads and access routes used for the work. Immediately clean any ground spills and soils to extent as directed by authority having jurisdiction

<u>1.4 Work Site Access</u> .1 Contractor shall install silt curtain at the extent of the dredging works at the start of the project and leave in place during full duration of the project. Contractor to continually monitor and address required repairs and/or repositioning as required.

> .2 It will be the Contractor's responsibility to gain access to all areas of the work site, including dredge areas. Temporary in-water access roads or causeways will require approval from Departmental Representative.

.3 Dredge material will be disposed of within containment berm onsite as shown on the drawings.

- .4 Prior to commencement of work, advise and obtain approval from the Departmental Representative of the existing roads and temporary routes / roads proposed to be used to access work areas and to haul material to and from the site, including roads to the dredge material disposal site.
- .5 Contractor to use public roadways and established access routes whenever possible and must provide appropriate signage and traffic control personnel as required.
- .6 Contractor must ensure that public and private road surfaces remain

DFO P/N C2-00 Floating Pugwash,)517 Dock NS	Constr	ENVIRON	IMENTAL PROTECTION PROCEDURES	Section 01 35 44 Page 6
				free from dredge sp etc. throughout the activities.	poils, clay, mud, e hauling
			.7	Any tools, equipment temporary structure thereof used or main purpose of building work in navigable of remain in place aft of the project.	nt, vehicles, es or parts intained for the g or placing a water are not to ter the completion
			.8	Work activities mus / any conditions of Navigable Waters Ad by Transport Canada	st comply with all f the Canadian ct approval issued a.
1.5 Oper Machiner	ation Y	n of	.1	Ensure that machine site in a clean con maintained free of invasive species an	ery arrives on ndition and is fluid leaks, nd noxious weeds.
			.2	Whenever possible, on land above the l on ice, or from a s a manner that minin to the banks and be body.	operate machinery high water mark, floating barge in mizes disturbance ed of a water
			.3	Wash, refuel and se and store fuel and for the machinery a to prevent any dele substances from en	ervice machinery other materials in such a way as eterious tering the water.
			. 4	Do not perform clea down within a 30-ma of a wetland, wate: identified environ	aning and wash etre buffer zone rcourse or other mentally sensitive

area.

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 7 Floating Dock Construction Pugwash, NS

1.6 Containment and Spill Management	.1	Comply with Federal (CEPA Storage Tank Systems for Petroleum Products and Allied Petroleum Products Regulations) and provincial regulations, codes, standards and guidelines for the storage of fuel and petroleum products on site.
	.2	In the event of a petroleum spill and release into the environment, stop work and immediately notify the Departmental Representative and the Canadian Coast Guard 24-Hour Environment Emergencies Report System (1-800-565-1633). Contain spill and perform clean-up in accordance with all regulations and procedures stipulated by authority having jurisdiction.
	.3	Do not dump petroleum products or any other deleterious substances on ground or in the water.
	.4	Be diligent and take all necessary precautions to avoid spills and contamination of the soil and water (both surface and subsurface) when handling petroleum products on the site and during fuelling and servicing of vehicles and equipment.
	.5	Maintain on site appropriate emergency spill response equipment consisting of at least one 250-litre (55 gallon) overpack spill kit for containment and clean-up of spills.
	.6	Maintain vehicles and equipment in good working order to prevent leaks on site. Hoses, couplings and tanks are to be inspected on a regular basis to prevent fractures and breaks.

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 8 Floating Dock Construction Pugwash, NS

	.7	All equipment to be used in or over the marine environment is to be free from leaks or coatings of hydrocarbon-based fluids and/or lubricants harmful to the environment. Hoses and tanks are to be inspected on a regular basis to prevent fractures and breaks.
	.8	Materials such as paint, primers, blasting abrasives, rust solvents, degreasers, grout, or other chemicals are not to enter the watercourse.
	.9	Ensure that building material used in a watercourse has been handled and treated in a manner to prevent the release or leaching of substances into the water that may be deleterious to fish.
	.10	If heavy machinery is being operated from a barge, on-site crews must have emergency spill clean-up equipment, adequate for the activity involved, on the barge. Spill equipment will include, as a minimum, at least one 250 L (i.e. 55 gallon) overpak spill kit containing items to prevent a spill from spreading; absorbent booms, pillows, and mats; rubber gloves; and plastic disposal bags. Take appropriate measures to contain and clean up any spills and all releases into the marine environment must be promptly reported to the 24- Hour Environment Emergencies Reporting System (1-800-565-1633).
1.7 Hazardous Material Handling	.1	Store and handle hazardous materials in accordance with applicable federal and provincial regulations, codes, standards and guidelines. Store in

location that will prevent spillage

into the environment.

DFO ENVIRO P/N C2-00517 Floating Dock Construction Pugwash, NS

	.2	Label containers to Workplace Hazardous Materials Information System (WHMIS) requirements and keep MSDS data sheets on site for all hazardous materials.
	.3	Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when stored.
	.4	Store and handle flammable and combustible materials in accordance with National Fire Code of Canada.
	.5	Workers in contact with hazardous materials must be provided with, and use regulated Personal Protective Equipment (PPE) and must have the necessary training to know how to handle the different hazardous materials in accordance with applicable health and safety and environmental regulations.
1.8 Disposal of <u>Wastes</u>	.1	Do not bury construction and demolition-related debris (e.g., concrete, creosote timbers, steel, impacted soil, etc.) or other waste materials on site.
	.2	Dispose and recycle construction and demolition-related debris and waste materials in accordance with provincial waste management regulations and the project waste

ENVIRONMENTAL PROTECTION

PROCEDURES

.3 Do not dispose of hazardous wastes (e.g., paints, batteries, cleaners, acids, etc.) including volatile materials (e.g., solvents, mineral spirits, aerosol cans, etc.) and petroleum products on the ground or into waterways, storm or sanitary

Section 01 74 21.

management requirements specified in

Section 01 35 44

Page 9

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 10 Floating Dock Construction Pugwash, NS

> sewers or in waste landfill sites. Dispose of hazardous wastes in accordance with applicable federal and provincial, regulations, codes, standards and guidelines.

- .6 Install approved floating silt boom around the complete perimeter of the dredging area as per Section 02 41 16. Conduct daily clean-up of floating or sinking construction materials, litter, and other debris arising from the work site to ensure protection of the marine environment. Any construction debris/ material that enters the marine environment must be removed immediately and be disposed of in a provincially approved manner.
- .5 Concrete waste:
 - .1 Perform dumping of residual material and truck cleaning operations off site or as directed by the Departmental Representative.
 - .2 Do not perform washing and cleaning of concrete vehicles within 30 meters of a wetland, watercourse or other identified environmentally sensitive area.
 - .3 Immediately clean any accidental release of concrete on site prior to solidification.
 - .4 Follow environmental regulations and good practices as approved by the provincial Departments of the Environment and other authorities having jurisdiction.
- 1.9 Water Quality .1 Contractor is responsible to develop and implement an Erosion and Sediment Control Plan for the work site that will minimize the risk of entry or

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 11 Floating Dock Construction Pugwash, NS

> re-suspension of sediment in a water body during all phases of the work. Erosion and sediment control measures should be maintained until all disturbed ground has been permanently stabilized, suspended sediment has resettled to the bed of the water body or settling basin and runoff water is clear

- .2 The Plan is to be submitted as per Section 01 33 00, for review by the Departmental Representative and should, where applicable, include:
 - .1 Effective sediment control measures (e.g. silt fencing, check dams, etc.) as an initial step in the construction sequence.
 - Measures for managing water .2 flowing onto the site, as well as water being pumped / diverted from the site such that sediment is filtered out prior to entering a water body (e.g., pumping / diversion of water to a vegetated area, construction of a settling pond or other filtration system). The water can be pumped into a settling pond or filter bag to ensure that the concentration of sediment is below regulated discharged criteria before it reaches a water body.
 - .3 Measures for containing and stabilizing waste material (e.g., dredged material, construction waste and materials, commercial logging waste, uprooted or cut aquatic plants, accumulated debris, etc.) above the high water mark of nearby water bodies to prevent re-entry.

DFO		ENVIRO	NMENTAL PROTECTION Section 01 35 44		
P/N C2-00	0517		PROC	EDURES	Page 12
Floating	Dock	Construction			
Pugwash,	NS				
			.4	Regular inspec	tion and
				reporting deta	ils for sediment
				control measur	es to ensure they
				are functionin	g properly.
			.5	Repair methodo	logy for erosion
				and sediment c	ontrol measures
				and structures	if damage
					II damage
			6	Demoural method	alogy of pop
			• 0	hiodogradable	orogy of non-
				sodimont contr	ol materials once
				site has been	atabilized Upon
				complotion of	scapilized. opon
				control measur	as hust he
				removed in a w	av so as to
				nrevent the es	cape of settled
				sediments.	cape of Sector
			.7	Methodology fo	r monitoring
			-	weather, speci	fically rainfall
				and storms and	altering work
				plans and cont	ingency measures
				as a result of	inclement
				weather.	
		.3	Where	e work may affec	ct water quality,
			sched	lule work in coo	peration with the
		Harbo	our Authority as	directed by	
		Depar	tmental Represe	entative to	
		minimize interference and impact			
			harbc	our users.	
		.4	Where	e work may affec	ct the water
			quali	ty adjacent to	water intake
		lines	used by lobste	er holding	
		facil	ities, fish pro	cessing	
			facil	ities or other	harbour users,
			sched	ule work in coo	peration with the
			Harbo	our Authority, f	acility owners
			and a	is airected by L	epartmental
			Kepre	sentative to mi	nimize
			inter	rerence and imp	act to narbour

users.

.5 All material used for infills must be clean and free from excessive fines, organics, debris and non-toxic (i.e.,

Section 01 35 44 DFO ENVIRONMENTAL PROTECTION P/N C2-00517 PROCEDURES Page 13 Floating Dock Construction Pugwash, NS free of fuel, oil, grease and/or any other contaminants), non-ore bearing and from a provincially approved, non-water source. For dredging operations, conduct work .6 in such a manner to limit turbidity and minimize sediment resuspension in the water to an absolute minimum at all times: .1 Maintain appropriate production speed and momentum of the excavation equipment. Make adjustments as required and as approved by Departmental Representative. .2 Strategically position

- excavation equipment and trucks to minimize over the water swings of dredged material whenever possible.
- .3 Avoid overfilling of the dredge bucket.
- .4 Minimize wash downs of equipment and wharf deck.
- .5 Restrict the volume of material dredged to the areas and depths in the contract, unless otherwise directed by the Departmental Representative.
- .6 No bottom stockpiling, dragging or side casting of material on the ocean floor is permitted during dredging operations.
- .7 To prevent water contamination by preservative treated wood:
 - .1 Wood treated with Chromate Copper Arsenate (CCA) or Ammoniac Copper Zinc Arsenate (ACZA) must be Canadian Standards Association (CSA) or

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 14 Floating Dock Construction Pugwash, NS

. 8

American Wood Preserver Association (AWPA) approved. . 2 Preservative treated lumber and timber, whether plant or field treated, shall be cured for a minimum of 30 days from date of the treatment application before their installation in areas which will be in contact with the water. .3 Do not field cut or bore treated timber and lumber over the surface of a watercourse or wetland. .4 Do not allow sawdust or shavings from field cutting and boring of treated timber and lumber to get washed or blown into a watercourse or wetland. .5 Take extra precautions to prevent dripping of product when using liquid applied preservative products over the surface of a watercourse. Do not use timber and lumber .6 treated with creosote, pentachlorophenol or other petroleum-based products for timber that will be in contact with the water. To prevent water contamination during concrete placement: Concrete placement should stop .1 in moderate to heavy rain [2.6-7.6 mm/hr or more] to prevent leaching contaminants into aquatic environment. Forms will have sealed corners .2 to prevent leakage. .3 Any accidental release of concrete will be removed prior

to solidification.

Section 01 35 44 DFO ENVIRONMENTAL PROTECTION P/N C2-00517 PROCEDURES Page 15 Floating Dock Construction Pugwash, NS

Restrictions

- Work will cease until the spill .4 is contained and the source of the leak can be identified. .5 Contractor must notify the Departmental Representative of all accidental releases of concrete into fish bearing waters and contact applicable federal and provincial regulators immediately. 1.10 Socioeconomic .1 Abide by municipal and provincial regulations for any restrictions on work performed during the night time and with flood lighting of the site. Obtain applicable permits. Work equipment and machinery must be .2 adequately equipped with mufflers to reduce noise on site to lowest possible level. Maintain mufflers in good operating condition at all times.
 - Place flood lights in opposite .3 direction of adjacent residential and business areas. Use LED lights instead of other types of lights, where possible. LED light fixtures are less prone to light trespass (i.e., are better at directing light where it needs to be, and do not bleed light into the surrounding area).
 - Contractor to coordinate with the .4 local Harbour Authority prior to commencement of the project activities such that the schedule with the least possible conflicts will be implemented.
- 1.11 Fish and Fish .1 Monitor and assess weather forecast on a daily basis to determine the Habitat Protection risk of extreme weather. Avoid work

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 16 Floating Dock Construction Pugwash, NS

		during periods for which Environment and Climate Change Canada has issued rainfall, storm surge or other weather warnings for the work area.
	.2	Ensure that all in-water activities, or associated in-water structures, do not interfere with fish passage, constrict the channel width, or reduce flows.
	.3	The release of deleterious substances into the watercourse is strictly prohibited. In the event of a release of a deleterious substance, stop work, contain sediment-laden water or other deleterious substances and prevent their further migration into the watercourse. Immediately report any spills or releases of sewage, oil, fuel or other deleterious material, whether near or directly into a water body.
1.12 Invasive Species	.1	Be aware of the risk for contamination of the fish habitat at the site as a result of invasive (or alien species) being introduced into the marine environment.
	.2	To minimize the possibility of fish habitat contamination and the spread of aquatic invasive species, all construction equipment that will be immersed into the water of a watercourse, or has the possibility of coming into contact with such water during the course of the work, must be cleaned and washed to ensure that they are free of marine growth and invasive species prior to mobilization to the site.

.1 Equipment shall include boats, barges, scows, cranes, excavators, haul trucks, pumps,
DFOENVIRONMENTAL PROTECTIONSection 01 35 44P/N C2-00517PROCEDURESPage 17Floating Dock ConstructionFloating Dock ConstructionFloating Dock Construction

Pugwash, NS

pipe lines and other all miscellaneous tools and equipment previously used in a marine environment. Cleaning and washing of equipment .3 shall be performed immediately upon their arrival at the site and before use in or over the water body. Conduct cleaning and washing .4 operations as follows: Scrape and remove heavy .1 accumulation of mud and dispose appropriately. .2 Wash all surfaces of equipment by use of a pressurized fresh water supply. .3 Immediately follow with application of a heavy sprayed coating of undiluted vinegar or other environmentally approved cleaning agent to thoroughly remove all plant matter, animals and sediments. Check and remove all plant, .4 animal and sediment matter from all bilges and filters.

- .5 Drain standing water from equipment and let fully dry before use.
- .6 Upon removal from the water, drain standing water from equipment and let fully dry before removal off the site.
- .5 Record of Assurance Logbook:
 - .1 Maintain an on-going log of past and present usage and washdowns of all equipment to illustrate mitigation measures undertaken against fish habitat contamination by alien species.

DFO			ENVIRO	NMENTA	AL PRC	TECTI	ON Sec	ction 0	1 35 44
P/N C2-00517				PROCE	EDURES	5	Pac	re 18	
Floating Dock Co		Constr	uction)	
Puqwash,	NS								
				.2 W 1	Vrite Ogboo 1 D e u W	data i k to i ate ar quipme sed ir etlanc	in a har include nd locat ent was n a wate d;	d cove the fo ion wh previo rcours	r bound llowing: ere usly e or
				•	2 1 3 D 9 4 C	ype of ates of iece of leanir gent(s	work p of wash of equip ng metho s) used.	down forment; d and	ea. or each cleaning
			.3	Keep I update reques Depart review	Record ed fro st, su tmenta w.	d of A om pro ubmit al Rep	ssurance ject to logbook presentat	e Logbo projeo to tive fo	ook st. Upon or
			.4	The De the r: inspec includ are f: invas: mobil:	epartr ight f ction ding l ree of ive sp izatio	mental to req of th hulls, f mari pecies on to	Represe uest a e equipr to ensu ne grow prior the site	entativ video ment, ure tha th and to e.	ve has at they
1.13 Bir <u>Habitat</u>	d and	l Bird	.1	Become by the (MBCA) of mic and th and in	e know e Mig:) in : grato: heir y n the	wledge ratory regard ry bir young vicin	able with Birds (s to the ds, the encounted ity.	th and Convent e prote ir eggs ered or	abide tion Act ection s, nests n site
			.2	Minim: site a entire	ize d: and ac e cour	isturb djacen rse of	ance to t areas the Wor	all bi during rk.	rds on g the
			.3	Do not seabin when a wharve	t app rds, v ancho es or	roach waterf ring e ferry	concent: owl and quipment ing supp	rations shorek t, acce plies.	3 of Dirds Essing
			.4	During flood nearby	g nigh light y bird	nt tim ts in d nest	e work, opposite ing hab:	positi e direc itat.	lon ction of

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 19 Floating Dock Construction Pugwash, NS

	.5	Do not use beaches, dunes and other natural previously undisturbed areas of the site to conduct work unless specifically approved by the Departmental Representative.
	.6	<pre>Should nests of migratory birds in wetlands be encountered during work, immediately notify Departmental Representative for directives to be followed1 Do not disturb nest site and neighbouring vegetation until nesting is completed2 Minimize work immediately adjacent to such areas until nesting is completed3 Protect these areas by following recommendations of Canadian Wildlife Service.</pre>
	.7	All machinery must be well muffled. If necessary, trucks may be required to avoid the use of engine brakes along specific sections of the route.
1.14 Species at Risk and Marine Mammals	.1	A safety zone for leatherback sea turtles and marine mammals must be established at the work site. The safety zone shall consist of a circle with a radius of at least 500 meters as measured from the center of the work site.
	.2	Maintain periodic visual surveys for leatherback sea turtles and marine mammals within the safety zone.
	.3	If leatherback sea turtles or marine mammals are observed within the safety zone while in-water activities are underway, all in-water activities must cease until the animals leave the safety zone and are not observed within the safety zone for a minimum

period of 30 minutes.

ENVIRONMENTAL PROTECTION Section 01 35 44 DFO P/N C2-00517 PROCEDURES Page 20 Floating Dock Construction Pugwash, NS .4 Work may start or restart if marine mammals are not observed within the safety zone within the 30-minute period. Keep airborne dust and dirt resulting 1.15 Air Quality .1 from the work on site to an absolute minimum. .2 Dust suppression by the application of water must be employed, when required. Apply dust control measures to roads, parking lots and work The Departmental areas. Representative shall determine locations where water is to be applied, the amount of water to be applied, and the times at which it shall be applied. Waste oil or any other petroleum products must not to be used for dust control under any circumstances. .3 Spray surfaces with water or other environmentally approved product. Use purposely suited equipment or machinery and apply in sufficient quantity and frequency to provide effective result and continued dust control during the entire course of the work. Fires and burning of rubbish on site 1.16 Fires .1 is not permitted. All construction personnel are 1.17 Archaeological .1 responsible for reporting any unusual materials unearthed during construction to the construction supervisor. If the find is believed

to be an archaeological resource, the

immediately stop work in the vicinity

Construction Supervisor will

of the find and notify the Departmental Representative.

DFO ENVIRONMENTAL PROTECTION Section 01 35 44 P/N C2-00517 PROCEDURES Page 21 Floating Dock Construction Pugwash, NS

.2	If an archaeological and / or
	historically significant item is
	discovered during the work
	activities, work in the area will be
	stopped immediately and the
	Departmental Representative will be
	contacted as well as the provincial
	Archaeological Services unit.
	a) Nova Scotia - NS Department of

- a) Nova Scotla NS Department of Communities, Culture and Heritage, Special Places Program, telephone: (902) 424-6475.
- .3 Work can only resume in the vicinity of the find when authorized by the Departmental Representative and Construction Supervisor, after approval has been granted by the Nova Scotia Department of Communities, Culture and Heritage.
- .4 In the event of the discovery of human remains of evidence of burials, excavation work will immediately cease and nearest law enforcement agency must be contacted immediately by the Departmental Representative and/or the Construction Supervisor.

DFO P/N C2-00517	OU	TESTING AND ALITY CONTROL	Section 01 45 00 Page 1		
Floating Dock Construc Pugwash, NS	tion				
1.1 SECTION INCLUDES	.1	Inspection and test administrative and requirements.	ing, enforcement		
	.2	Tests and mix desig	jns.		
	.3	Mock-ups.			
	.4	Mill tests.			
	.5	Equipment and syste balance.	em adjust and		
1.2 RELATED SECTIONS	.1	Section 01 33 00 - Procedures.	Submittal		
	.2	Section 01 78 00 - Submittals.	Closeout		
1.3 INSPECTION	.1	Facilitate Departme Representative's ac part of Work is bei locations other tha site, make preparat access to such Work in progress.	ental ccess to Work. If ing fabricated at an construction tions to allow whenever it is		
	.2	Give timely notice inspection of Work special tests, insp approvals by Depart Representative or k authorities having	requesting designated for pections or mental by inspection jurisdiction.		
	.3	If Contractor cover be covered Work des special tests, insp approvals before su uncover Work until inspections or test and satisfactorily until such time as Representative give	s or permits to signated for pections or uch is made, particular s have been fully completed and Departmental es permission to		

Section 01 45 00 DFO TESTING AND P/N C2-00517 QUALITY CONTROL Page 2 Floating Dock Construction Pugwash, NS proceed. Pay costs to uncover and make good such Work. In accordance with the General .4 Conditions, Departmental Representative may order any part of Work to be examined if Work is suspected to be not in accordance with Contract Documents. 1.4 INDEPENDENT .1 Departmental Representative will INSPECTION AGENCIES engage and pay for service of Independent Inspection and Testing Agencies for purpose of inspecting and testing portions of Work except for the following which remain part of Contractor's responsibilities: Inspection and testing required .1 by laws, ordinances, rules, regulations or orders of public authorities. . 2 Inspection and testing performed exclusively for Contractor's convenience. Testing, adjustment and .3 balancing of conveying systems, mechanical and electrical equipment and systems. .4 Mill tests and certificates of compliance. .5 Tests as specified within various sections designated to be carried out by Contractor under the supervision of Departmental Representative. Additional tests specified in .6 Clause 1.4.2. .2 Where tests or inspections by designated Testing Agency reveal work not in accordance with contract requirements, Contractor shall pay

costs for additional tests or inspections as Departmental

DFO		TESTING AND	Section 01 45 00
P/N C2-00517	QU	ALITY CONTROL	Page 3
Floating Dock Construct	ion		2
Puqwash, NS			
		Representative may acceptability of com	require to verify rrected work.
	.3	Employment of inspect agencies by Departme Representative does responsibility to per accordance with Cont	ction and testing ental not relax erform Work in tract Documents.
1.5 ACCESS TO WORK	.1	Furnish labour and a provide access to th inspected and tested	facility to he work being d.
	.2	Co-operate to facil: inspections and test	itate such ts.
	.3	Make good work dist inspections and test	urbed by ts.
<u>1.6 PROCEDURES</u>	.1	Notify Departmental sufficiently in adva is ready for tests, Departmental Represe attendance arrangeme Agency. When directe Departmental Represe such Agency directly	Representative ance of when work in order for entative to make ents with Testing ed by entative, notify Y.
	.2	Submit representative materials specified Deliver in required Testing Agency. Subm reasonable promptness orderly sequence so delay in Work.	ve samples of to be tested. quantities to mit with ss and in an as not to cause
	.3	Provide labour and a obtain and handle sa Provide sufficient a Testing Agency's exa store equipment and	facilities to amples on site. space on site for clusive use to cure test

samples.

Section 01 45 00 DFO TESTING AND P/N C2-00517 QUALITY CONTROL Page 4 Floating Dock Construction Pugwash, NS 1.7 REJECTED WORK Remove and replace defective Work, .1 whether result of poor workmanship, use of defective or damaged products and whether incorporated in Work or not, which has been identified by Departmental Representative as failing to conform to Contract Documents. .2 Make good damages to existing or new work, including work of other Contracts, resulting from removal or replacement of defective work. 1.8 TESTING BY Provide all necessary instruments, .1 equipment and qualified personnel to CONTRACTOR perform tests designated as Contractor's responsibilities herein or elsewhere in the Contract Documents. .2 At completion of tests, turn over 2 copies of fully documented test reports to Departmental Representative. Additionally, obtain other copies in sufficient quantities to enable one complete set of test reports to be placed in each of the maintenance manuals specified in Section 01 78 00. .3 Submit mill test certificates and other certificates as specified in various sections. Furnish test results and mix designs .4 as specified in various sections. Prepare mock-ups for Work 1.9 MOCK-UPS .1 specifically requested in various trade sections. Include in each mock-up all related work components representative of final assembly.

DFO TESTING AND Section 01 45 00 P/N C2-00517 QUALITY CONTROL Page 5 Floating Dock Construction Pugwash, NS

- .2 Construct in locations acceptable to Departmental Representative.
- .3 Prepare mock-ups for Departmental Representative's review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.
- .4 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
- .5 If requested, Departmental Representative will assist in preparing a schedule fixing dates for preparation.
- .6 Remove mock-up at conclusion of Work or when directed by Departmental Representative unless approval is given to remain as part of Work.

DFO	TEMPO	Section 01 50 00	
P/N C2-00517			Page 1
Floating Dock Construc	tion		
Pugwash, NS			
1.1 ACCESS	.1	Provide and maintain to project site.	n adequate access
	.2	Maintain access roa of contract and mak resulting from Cont roads.	ds for duration e good damage ractors' use of
1.2 CONTRACTOR'S SITE OFFICE	.1	Be responsible for site office, if req electricity, heat, telephone. Locate s directed by Departm Representative.	and provide own uired, including lights and ite office as ental
1.3 DEPARTMENTAL REPRESENTATIVE'S SITE OFFICE	.1	Provide or construct office for the use Departmental Represe Site Representative must be in place pr commencement of wor	t a separate site of the entative and the . The building ior to k.
	.2	Provide heating sys 22°C inside tempera outside temperature	tem to maintain ture at -20°C •
	.3	The building will b 2400mm x 3600mm. It suitable frame cove weatherproof siding plywood or other ap The floor will be o material. It will b suitable window with glass and arranged least 0.5m ² of scree door will be fitted and 2 keys.	e approximately will have a red with a and lined with proved material. f 19mm thick e provided with h at least 1m ² of to provide at ened opening. The with a lockset
	.4	The office will be drafting chair and table having a hing top suitable for dr	equipped with a a 900mm x 1500mm ed, smooth wooden afting.

DFO		ſ	TEMPO	RARY FACILITIES	ection 01 50 00	
P/N C2-00517					Page 2	
Floating D	ock	Construct	ion			
Pugwash, N	IS					
			.5	Install electrical	lighting system	
				to provide minimum surface mounted, sh fixtures with 10% u component.	750 lux using ielded commercial pward light	
			.6	Maintain office in	clean condition.	
			.7	Arrange and pay for facsimile machine i Departmental Repres for Site Representa use. Contractor sha distance plan for D Representative's us	telephone and n the entative's Office tive's exclusive ll include long epartmental e.	
			.8	Contractor may, on Departmental Repres cellular or mobile approval to use cel phone is granted, b all services, airti network access fees fees or charges req the phone as intend manufacturer.	approval of entative, provide phone. If lular or mobile e responsible for me, license and , and all other uired to utilize ed by the	
			.9	Upon award, contrac making arrangements and facsimile immed Construction should without clear line to site.	tor shall begin for telephone iately. not begin of communication	
1.4 SANITA FACILITIES	ARY S		.1	Provide sanitary fa force in accordance regulations and ord	cilities for work with governing inances.	
			.2	Post notices and ta precautions as requ health authorities. premises in sanitar	ke such ired by local Keep area and y condition.	

DFO	TEMPO	RARY FACILITIES	Section 01 50 00			
P/N C2-00517			Page 3			
Floating Dock Construct	tion					
Pugwash, NS						
1.5 POWER	.1	Arrange, pay for an	d maintain			
		temporary electrical power supply in accordance with governing regulations and ordinances.				
	.2	Supply and install facilities for power lines and undergrout approval of local per authority.	all temporary r such as pole nd cables to ower supply			
1.6 WATER SUPPLY	.1	Arrange, pay for and temporary water supp with governing regu- ordinances.	d maintain ply in accordance lations and			
1.7 SCAFFOLDING	.1	Design, construct as scaffolding in rigio safe manner in acco CAN/CSA-S269.2-M87	nd maintain d, secure and rdance with (R2003).			
	.2	Erect scaffolding is walls. Remove when a required.	ndependent of no longer			
1.8 CONSTRUCTION SIGN AND NOTICES	.1	Contractor or subcon advertisement signbor permitted on site.	ntractor oards are not			
	.2	Only notices of safe instructions are pe	ety or rmitted on site.			
	.3	Safety and Instruct. Notices: .1 Signs and notic and instruction share official languages. shall conform to CAN (R2001).	ion Signs and ces for safety ll be in both Graphic symbols N/CSA-Z321-96			

DFO	TEMPOR	ARY FACILII	TIES	Section	01 50	00
P/N C2-00517				Page 4		
Floating Dock Construc	tion					
Pugwash, NS						
	.4 1	Maintenance	and Dis	posal of	Site	

Signs: .1 Maintain approved signs and notices in good condition for duration of project and dispose of off-site on completion of project or earlier if directed by Departmental Representative.

1.9 REMOVAL OF .1 Remove temporary facilities from site when directed by Departmental Representative.

Section 01 56 00 DFO TEMPORARY BARRIERS P/N C2-00517 AND ENCLOSURES Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL 1.1 SECTION INCLUDES .1 Barriers. .2 Traffic Controls. 1.2 INSTALLATION AND .1 Provide temporary controls in order REMOVAL to execute work expeditiously. Remove from site all such work after .2 use. 1.3 HOARDING .1 Erect temporary site enclosure using new 1.2m high snow fence wired to rolled steel "T" bar fence posts spaced at 2.4m centres. Provide one lockable truck gate. Maintain fence in good repair. 1.4 GUARD RAILS AND .1 Provide secure, rigid guard rails and barricades around open BARRICADES excavations. Provide barricades along wharf .2 structure when wheelquard is removed. .3 Provide as required by governing authorities. Provide and maintain access to 1.5 ACCESS TO SITE .1 adjacent harbour facilities. 1.6 PUBLIC TRAFFIC .1 Provide and maintain competent signal flag operators, traffic FLOW signals, barricades and flares, lights, or lanterns as required to perform work and protect the public.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	TEMP AN ion	ORARY BARRIERS D ENCLOSURES	Section 01 56 00 Page 2
1.7 FIRE ROUTES	.1	Maintain access to including overhead use by emergency re	property clearances for sponse vehicles.
1.8 PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY	.1	Protect surrounding public property fro performance of work	private and m damage during •
	.2	Be responsible for	damage incurred.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	COMMON PRODUCT Section 01 61 00 REQUIREMENTS Page 1 n
1.1 GENERAL .1	Use new material and equipment unless otherwise specified.
.2	<pre>Within 7 days of written request by Departmental Representative, submit following information for any materials and products proposed for supply: .1 name and address of manufacturer; .2 trade name, model and catalogue number; .3 performance, descriptive and test data; .4 manufacturer's installation or application instructions; .5 evidence of arrangements to procure; .6 evidence of manufacturer delivery problems or unforeseen delays.</pre>
.3	Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
. 4	Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.
.5	Permanent labels, trademarks and nameplates on products are not acceptable in prominent locations, except where required for operating instructions, or when located in mechanical or electrical rooms.

DFO	С	OMMON PRODUCT	Section 01 61 00
P/N C2-00517		REQUIREMENTS	Page 2
Floating Dock Construc	tion		
Pugwash, NS			
1.2 PRODUCT QUALITY AND REFERENCED STANDARDS	.1	Contractor shall be responsible for sub technical data and reports to confirm or system proposed contract requiremen standards.	solely mitting relevant independent test whether a product for use meets its and specified
	.2	Final decision as t product or system m requirements rest s Departmental Repres accordance with the Conditions.	o whether a leets contract olely with the entative in General
1.3 ACCEPTABLE MATERIALS AND ALTERNATIVES	.1	Acceptable Material specified include t trade marks or manu supplier's name as material descriptio only use one of the incorporation into	s: When materials rade names or facturer's or part of the on, select and names listed for the Work.
	.2	Alternative Materia alternative materia or manufacturer's n must be done during period following pr indicated in the In Bidders.	ls: Submission of ls to trade names ames specified the bidding ocedures structions to
	.3	Substitutions: After bid, substitution of material will be de change to the Work with the General Co Contract.	r acceptance of of a specified alt with as a in accordance onditions of the
1.4 MANUFACTURERS INSTRUCTIONS	.1	Unless otherwise sp with manufacturer's instructions for ma installation method	ecified, comply latest printed terials and ls to be used. Do

not rely on labels or enclosure

DFO P/N C2-00517 Floating Dock Const Pugwash, NS	C	COMMON PRODUCT REQUIREMENTS	Section 01 61 00 Page 3
		provided with p written instruc manufacturers.	products. Obtain tions directly from
	.2	Notify Departme in writing of a these specifica manufacturers i Departmental Re designate which followed.	ental Representative my conflict between tions and enstructions, so that presentative will document is to be
<u>1.5 AVAILABILITY</u>	.1	Immediately not Representative unforeseen or u delivery proble Provide support Clause 1.1.2 ab	ify Departmental in writing of manticipated material ms by manufacturer. documentation as per pove.
1.6 WORKMANSHIP	.1	Ensure quality standard, execu experienced and respective duti employed.	of work is of highest ted by workers I skilled in es for which they are
	.2	Remove unsuitab workers from si General Conditi	ole or incompetent te as stipulated in ons.
	.3	Ensure cooperat laying out work and continuous at all times.	ion of workers in Maintain efficient supervision on site
	. 4	Coordinate work subcontractors.	between trades and
	.5	Coordinate place sleeves and acc	ement of openings, essories.
1.7 FASTENINGS - GENERAL	.1	Provide metal f accessories in and finish as b	astenings and same texture, colour base metal in which

DFO	COMMON PRODUCT Section 01 61 00
P/N C2-00517	REQUIREMENTS Page 4
Floating Dock Constructio	n J
Puqwash, NS	
	they occur. Prevent electrolytic action between dissimilar metals. Use non-corrosive fasteners, anchors and spacers for securing exterior work and in humid areas.
.2	Space anchors within limits of load bearing or shear capacity and ensure that they provide positive permanent anchorage. Wood or organic material plugs not acceptable.
.3	Keep exposed fastenings to minimum, space evenly and lay out neatly.
. 4	Fastenings which cause spalling or cracking of material to which anchorage is made, are not acceptable.
. 5	Do not use explosive actuated fastening devices unless approved by Departmental Representative. See Section 01 35 28 on Health and Safety in this regard.
1.8 FASTENINGS1 EQUIPMENT	Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.
. 2	Use heavy hexagon heads, semi- finished unless otherwise specified.
. 3	Bolts may not project more than one diameter beyond nuts.
. 4	Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur and, use resilient washers with stainless steel.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	C	COMMON PRODUCT Section 01 61 00 REQUIREMENTS Page 5
1.9 STORAGE, HANDLING AND PROTECTION	.1	Deliver, handle and store materials in manner to prevent deterioration and soiling and in accordance with manufacturer's instructions when applicable. Provide same degree of protection to materials supplied by Canada.
	.2	Store packaged or bundled materials in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in Work. Provide additional cover where manufacturer's packaging is insufficient to provide adequate protection.
	.3	Store products subject to damage from weather in weatherproof enclosures.
	• 4	Store cementitious products clear of earth or concrete floors, and away from walls.
	.5	Keep sand, when used for grout or mortar materials, clean and dry. Store sand on wooden platforms and cover with waterproof tarpaulins during inclement weather.
	.6	Store sheet materials and lumber on flat, solid supports and keep clear of ground. Slope to shed moisture.
	.7	Store and mix paints in heated and ventilated room. Remove oily rags and other combustible debris from site daily. Take every precaution necessary to prevent spontaneous combustion.
	.8	Immediately remove damaged or rejected materials from site.

DFO C P/N C2-00517 Floating Dock Construction Pugwash, NS

.9 Touch-up damaged factory finished surfaces to Departmental Representative's satisfaction. Use touch-up materials to match original. Do not paint over name plates.

1.10 CONSTRUCTION EQUIPMENT AND PLANT

- ON .1 On request, prove to the <u>ANT</u> satisfaction of Departmental Representative that the construction equipment and plant are adequate to manufacture, transport, place and finish work to quality and production rates specified. If inadequate, replace or provide additional equipment or plant as directed.
 - .2 Maintain construction equipment and plant in good operating order. Prevent oil and other contaminant leaks. Should any contaminant leak onto ground or into the water, take immediate and appropriate measures to contain, cleanup and dispose in an environmentally responsible manner.

DFO P/N C2-0051 Floating Do	17 ock	Construct	ion	CLEANING	Section 01 74 11 Page 1
ruywashi, Na	5				
<u>PART 1 - GE</u>	ENER	AL			
1.1 GENERAI	<u>L</u>		.1	Conduct cleaning and operations to complete ordinances and anti-	d disposal y with local -pollution laws.
			.2	Store volatile waster metal containers, as premises at end of	e in covered nd remove from each working day.
			.3	Prevent accumulation create hazardous com	n of wastes which nditions.
			.4	Provide adequate ver use of volatile or a substances.	ntilation during noxious
1.2 MATERIA	ALS		.1	Use only cleaning manufacturer.	aterials facturer of ed, and as ning material
1.3 CLEANIN CONSTRUCTIO	NG E ON	DURING	.1	Maintain project groperties in a tid from accumulations and debris. Clean a basis.	ounds and public y condition, free of waste material reas on a daily
			.2	Provide on-site gard for collection of wa and debris.	bage containers aste materials
			.3	Remove waste materia from site on a dail	als and debris y basis.
1.4 FINAL C	CLEA	NING	.1	In preparation for . Work perform final	acceptance of the cleaning.
			.2	Inspect finishes, f equipment. Ensure sp workmanship and oper	itments and pecified ration.

P/N C2-00517 Page 2	CLEANING Section 01 74 11
Electing Deck Construction	Page 2
Floating Dock Construction	struction
Pugwash, NS	

.3 Broom clean exterior paved and concrete surfaces; rake clean other surfaces of grounds.

CONSTRUCTION/DEMOLITION Section 01 74 21 DFO P/N C2-00517 WASTE MANAGEMENT AND DISPOSAL Page 1 Floating Dock Construction Pugwash, NS 1.1 RELATED SECTIONS Section 01 35 44 - Environment .1 Procedures. Section 03 30 00 - Cast-in-Place .2 Concrete. 1.2 WASTE MANAGEMENT .1 Prior to commencement of work, prepare Waste Management Workplan. PLAN .2 Workplan to include: .1 Waste audit. .2 Waste reduction practices. .3 Material source separation process. .4 Procedures for sending recyclables to recycling facilities. Procedures for sending non-.5 salvageable items and waste to approved waste processing facility or landfill site. Training and supervising .6 workforce on waste management at site. Workplan to incorporate waste .3 management requirements specified herein and in other sections of the Specifications. Develop Workplan in collaboration .4 with all subcontractors to ensure all waste management issues and opportunities are addressed. .5 Implement and manage all aspects of Waste Management Workplan for duration of work. Revise Plan as work progresses .6 addressing new opportunities for diversion of waste from landfill.

DFO CONS	STRUCTION/DEMOLITION Section 01 74 21
P/N C2-00517 WASTE N	MANAGEMENT AND DISPOSAL Page 2
Floating Dock Construction	on
Pugwash, NS	
<u>1.3 WASTE AUDIT</u> .3	<pre>1 At project start-up, conduct waste audit of: .1 Site conditions identifying salvageable and non-salvageable items and waste resulting from demolition and removal work. .2 Projected waste resulting from product packaging and from material leftover after installation work.</pre>
.2	2 Develop written list. Record type, composition and quantity of various salvageable items and waste anticipated, reasons for waste generation and operational factors which contribute to waste.
1.4 WASTE REDUCTION	1 Based on waste audit, develop waste reduction program.
. :	2 Structure program to prioritize actions, with waste reduction as first priority, followed by salvage and recycling effort, then disposal as solid waste.
	3 Identify materials and equipment to be: .1 Protected and turned over to Departmental Representative when indicated. .2 Salvaged for resale by Contractor. .3 Sent to recycling facility. .4 Sent to waste processing/landfill site for their recycling effort. .5 Disposed of in approved landfill site.
. '	4 Reduce construction waste during installation work. Undertake practices which will minimize waste and optimize full use of new materials on site, such as:

CONSTRUCTION/DEMOLITION Section 01 74 21 DFO P/N C2-00517 WASTE MANAGEMENT AND DISPOSAL Page 3 Floating Dock Construction Pugwash, NS Use of a central cutting area .1 to allow for easy access to offcuts; .2 Use of off-cuts for blocking and bridging elsewhere. Use of effective and .3 strategically placed facilities on site for storage and staging of left-over or partially cut materials to allow for easy incorporation into work whenever possible avoiding unnecessary waste. .5 Develop other strategies and innovative procedures to reduce waste such as minimizing the extent of packaging used for delivery of materials to site, etc. 1.5 MATERIAL SOURCE Develop and implement material .1 source separation process at SEPARATION PROCESS commencement of work as part of mobilization and waste management at site. . 2 Provide on-site facilities to collect, handle and store anticipated quantities of reusable, salvageable and recyclable materials. .1 Use suitable containers for individual collection of items based on intended purpose. .2 Locate to facilitate deposit but without hindering daily operations of existing building tenants. .3 Clearly mark containers and stockpiles as to purpose and use. Perform demolition and removal of .3 existing structure components and equipment following a systematic deconstruction process.

CONSTRUCTION/DEMOLITION Section 01 74 21 DFO P/N C2-00517 WASTE MANAGEMENT AND DISPOSAL Page 4 Floating Dock Construction Pugwash, NS .1 Separate materials and equipment at source, carefully dismantling, labelling and stockpiling alike items for the following purposes: Reinstallation into the . 1 work where indicated. .2 Salvaging reusable items not needed in project which Contractor may sell to other parties. Sale of such items not permitted on site. .3 Sending as many items as possible to locally available recycling facility. .4 Segregating remaining waste and debris into various individual waste categories for disposal in a "non-mixed state" as recommended by waste processing/landfill sites. Isolate product packaging and .4 delivery containers from general waste stream. Send to recycling facility or return to supplier/manufacturer. .5 Send leftover material resulting from installation work for recycling whenever possible. .6 Establish methods whereby hazardous and toxic waste materials, and their containers, encountered or used in the course work are properly isolated, stored on site and disposed in accordance with applicable laws and regulations from authorities having jurisdiction. Isolate and store existing materials .7 and equipment identified for reincorporation into the Work. Protect against damage.

DFO P/N C2-00517 WAS	CONSTR TE MAN	UCTION/DEMOLITION Section 01 74 21 AGEMENT AND DISPOSAL Page 5
Floating Dock Constru Pugwash, NS	ction	
1.6 WORKER TRAINING AND SUPERVISION	.1	Provide adequate training to workforce, through meetings and demonstrations, to emphasize purpose and worker responsibilities in carrying out the Waste Management Plan.
	.2	Waste Management Coordinator: designate full-time person on site, experienced in waste management and having knowledge of the purpose and content of Waste Management Plan to: .1 Oversee and supervise waste management during work. .2 Provide instructions and directions to all workers and subcontractors on waste reduction, source separation and disposal practices.
	.3	Post a copy of Plan in a prominent location on site for review by workers.
1.7 CERTIFICATION OF MATERIAL DIVERSION	.1	Submit to Departmental Representative, copies of certified weigh bills from authorized waste processing sites and sale receipts from recycling/reuse facilities confirming receipt of building materials and quantity of waste diverted from landfill.
	.2	Submit data at pre-determined project milestones as determined by Departmental Representative.
	.3	Compare actual quantities diverted from landfill with projections made during waste audit.
1.8 DISPOSAL REQUIREMENTS	.1	Burying or burning of rubbish and waste materials is prohibited.

DFO

CONSTRUCTION/DEMOLITION Section 01 74 21 P/N C2-00517 WASTE MANAGEMENT AND DISPOSAL Page 6 Floating Dock Construction Pugwash, NS

.2	Disposal of waste, volatile materials, mineral spirits, oil, paint, paint thinner or unused preservative material into waterways, storm, or sanitary sewers is prohibited.
.3	Do not dispose of preservative treated wood through incineration.
.4	Do not dispose of preservative treated wood with other materials destined for recycling or reuse.
.5	Dispose of treated wood, end pieces, wood scraps and sawdust at a sanitary landfill.
.6	Dispose of waste only at approved waste processing facility or landfill sites approved by authority having jurisdiction.
.7	Contact the authority having jurisdiction prior to commencement of work, to determine what, if any, demolition and construction waste materials have been banned from disposal in landfills and at transfer stations. Take appropriate action to isolate such banned materials at site of work and dispose in strict accordance with provincial and municipal regulations.
.8	Transport waste intended for landfill in separated condition, following rules and recommendations of Landfill Operator in support of their effort to divert, recycle and reduce amount of solid waste placed in landfill.

.9 Collect, bundle and transport salvaged materials to be recycled in DFO CONSTRUCTION/DEMOLITION Section 01 74 21 P/N C2-00517 WASTE MANAGEMENT AND DISPOSAL Page 7 Floating Dock Construction Pugwash, NS

> separated categories and condition as directed by recycling facility. Ship materials only to approved recycling facilities.

.10 Sale of salvaged items by Contractor to other parties not permitted on site.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	CLOSE	EOUT SUBMITTALS Section 01 78 00 Page 1
1.1 SECTION INCLUDES	.1	<pre>Project Record Documents as follows: .1 As-built drawings; .2 As-built specifications;</pre>
	.2	Reviewed shop drawings.
1.2 PROJECT RECORD DOCUMENTS	.1	Departmental Representative will provide two white print sets of contract drawings and two copies of Specifications Manual specifically for "as-built" purposes.
	.2	Maintain at site one set of the contract drawings and specifications to record actual as-built site conditions.
	.3	Maintain up-to-date, real time as- built drawings and specifications in good condition and make available for inspection by the Departmental Representative at any time during construction.
	. 4	<pre>As-Built Drawings: .1 Record changes in red ink on the prints. Mark only on one set of prints and at completion of project and prior to final inspection, neatly transfer notations to second set (also by use of red ink). Submit both sets to Departmental Representative. All drawings of both sets shall be stamped "As-Built Drawings" and be signed and dated by Contractor. .2 Show all modifications, substitutions and deviations from what is shown on the contract drawings or in specifications. .3 Record following information: .1 Horizontal and vertical location of various elements in relation to Chart Datum.</pre>

DFO CLOSEOUT SUBMITTALS P/N C2-00517 Floating Dock Construction Pugwash, NS

.2 Field changes of dimension and detail. All design elevations, .3 sections, and details dimensioned and marked-up to consistently report finished installation conditions. . 4 Any details produced in the course of the contract by the Departmental Representative to supplement or to change existing design drawings must also be marked-up and dimensioned to reflect final as-built conditions and appended to the as-built drawing document. All change orders issued .5 over the course of the contract must be documented on the finished as-built documents, accurately and consistently depicting the changed condition as it applies to all affected drawing details. .5 As-built Specifications: legibly mark in red each item to record actual construction, including: .1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly items substituted from that specified. .2 Changes made by Addenda and Change Orders. Mark up both copies of .3 specifications; stamp "as-built", sign and date similarly to drawings as per above clause. Maintain As-built documents current .6 as the contract progresses.

> Departmental Representative will conduct reviews and inspections of the documents on a regular basis.

DFO CLOSEOUT SUBMITTALS Section 01 78 00 P/N C2-00517 Page 3 Floating Dock Construction Pugwash, NS

> Frequency of reviews will be subject to Departmental Representative's discretion. Failure to maintain asbuilts current and complete to satisfaction of the Departmental Representative shall be subject to financial penalties in the form of progress payment reductions and holdback assessments.

1.3 REVIEWED SHOP DRAWINGS .1 Compile 2 full sets of all reviewed shop drawings.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

<u>1.1 DESCRIPTION</u>	.1	This section specifies requirements for demolishing and removing wholly or in part various items designated to be removed or partially removed.
	.2	Demolition and removal will consist of, but not necessarily be limited to, the following: .1 Partial demolition of the existing armour stone revetment and corestone berm to facilitate installation of the new retaining wall. Armourstone to be salvaged on site as directed by the Departmental Representative.
1.2 GENERAL REQUIREMENTS	.1	A Notice to Shipping is to be issued prior to commencement and upon completion of work.
	.2	During construction, any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
	.3	Upon completion of the project, a written Notice to Mariners must be issued.
1.3 PROTECTION	.1	Protect existing objects designated to remain. In event of damage, immediately replace or make repairs to approval of and at no additional cost to Canada.
	.2	Place a floating boom around entire demolition site to prevent loss of any materials.
	.3	Remove all floating debris from

water on a routine and timely basis.

DFO SITEWORK, DEMOLITION, Section 02 41 16 P/N C2-00517 AND REMOVAL Page 2 Floating Dock Construction Pugwash, NS

> .4 Removal of floating debris from water shall not be carried out utilizing designated safety boat. Contractor shall use separate vessel for debris cleaning, leaving the designated safety boat available for emergency operations at all times.

PART 2 - PRODUCTS

NOT APPLICABLE

3.1 EXECUTION

- PART 3 EXECUTION
- .1 Inspect site and verify with Departmental Representative objects designated for removal.
 - .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.

3.2 REMOVAL

- .1 Remove in their entirety all materials and objects specified for removal.
- .2 Do not disturb adjacent work designated to remain in place. Take extreme caution when excavating adjacent to the existing approach slab.
- 3.3 DISPOSAL OF MATERIAL
- .1 All demolished materials, except materials designated to be reused, will become property of contractor and will be removed from site and disposed of to satisfaction of Departmental Representative and in accordance with environmental guidelines. It is the sole responsibility of the contractor to dispose of all demolished materials
| DFO | SITEWORK, DEMOLITION, | Section 02 41 16 |
|---------------------------------|-----------------------|------------------|
| P/N C2-00517 | AND REMOVAL | Page 3 |
| Floating Dock Co
Pugwash, NS | onstruction | |
| | | |

at an approved disposal site. Ensure that disposal site is approved and willing to accommodate any materials disposed of from work site.

.2 Contractor shall obtain and pay for all necessary permits and disposal fees for use of an approved waste disposal site.

3.4 RESTORATION

- .1 Upon completion of work, remove debris, trim surfaces and leave work site in clean condition.
- .2 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

DFO CONCRETE FORMING Section 03 10 00 P/N C2-00517 AND ACCESSORIES Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL 1.1 RELATED SECTIONS .1 Section 03 20 00 - Concrete Reinforcing. Section 03 30 00 - Cast-in-Place .2 Concrete. .3 Section 07 92 10 - Joint Sealing. .1 Canadian Standards Association (CSA) 1.2 REFERENCES CAN/CSA-A23.1 latest edition, .1 Concrete Materials and Methods of Concrete Construction. CAN/CSA-086 latest edition), .2 Engineering Design in Wood (Limit States Design). .3 CSA 0121 latest edition, Douglas Fir Plywood. .4 CSA 0151 CAC latest edition, Canadian Softwood Plywood. .5 CSA 0153 latest edition, Poplar Plywood. .6 CAN3-0188.0 latest edition, Standard Test Methods for Mat-Formed Wood Particleboards and Waferboard. CSA 0437 Series latest edition, . 7 Standards for OSB and Waferboard. .8 CSA S269.1 latest edition, Falsework for Construction Purposes. .9 CAN/CSA-S269.3 latest edition, Concrete Formwork. 1.3 SHOP DRAWINGS .1 Submit shop drawings for formwork and falsework in accordance with Section 01 33 00 - Submittal Procedures. Indicate method and schedule of .2 construction, shoring, stripping and re-shoring procedures, materials, arrangement of joints, special architectural exposed finishes,

Section 03 10 00 DFO CONCRETE FORMING P/N C2-00517 AND ACCESSORIES Page 2 Floating Dock Construction Pugwash, NS ties, liners, and locations of temporary embedded parts. Comply with CSA S269.1, for falsework drawings Comply with CAN/CSA-S269.3 for formwork drawings. .3 Indicate formwork design data, such as permissible rate of concrete placement, and temperature of concrete, in forms. .4 Indicate sequence of erection and removal of formwork/falsework as directed by Departmental Representative. .5 Each shop drawing submission shall bear stamp and signature of qualified Professional Engineer registered or licensed in Province of Nova Scotia, Canada. 1.4 WASTE MANAGEMENT Separate and recycle waste materials .1 in accordance with Section 01 74 21 AND DISPOSAL - Construction/Demolition Waste Management and Disposal and the Waste Reduction Workplan. .2 Place materials defined as hazardous or toxic waste in designated containers. .3 Ensure emptied containers are sealed and stored safely for disposal away from children. .4 Use sealers, form release and stripping agents that are non-toxic, biodegradable and have zero or low VOC's.

DFO CON P/N C2-00517 AN Floating Dock Construction Pugwash, NS Section 03 10 00 Page 3

PART 2 - PRODUCTS

2.1 MATERIALS

.1 Formwork materials: .1 Use formwork materials to CAN/CSA-A23.1.

- .2 Form ties: .1 Removable or snap-off metal ties, fixed or adjustable length, free of devices leaving holes larger than 25mm diameter in concrete surface.
- .3 Form release agent: non-toxic, chemically active release agents containing compounds that react with free lime present in concrete to provide water insoluble soaps, preventing set of film of concrete in contact with form.
- .4 Falsework materials: to CSA-S269.1. .1 Materials required to bear grade marks, or be accompanied with certificates, test reports or other proof of conformity.
- .5 Premoulded joint fillers: .1 Bituminous impregnated fibreboard to ASTM D1751.
- .6 Bond Breaker: .1 Impermeable tube formed of polyvinylchloride, rubber or similar material to the approval of the Departmental Representative. Internal diameter equal to dowels.
- .7 Sealant: to Section 07 92 10 Joint Sealing.

DFO CONCRETE FORMING P/N C2-00517 AND ACCESSORIES Floating Dock Construction Pugwash, NS

PART	3	_	EXECUTION

- 3.1 FABRICATION AND ERECTION
- .1 Verify lines, levels and centres before proceeding with formwork/falsework and ensure dimensions agree with drawings.
- .2 Obtain Departmental Representative's approval for use of earth forms framing openings not indicated on drawings.
- .3 Hand trim sides and bottoms and remove loose earth from earth forms before placing concrete.
- .4 Fabricate and erect falsework in accordance with CSA S269.1.
- .5 Fabricate and erect formwork in accordance with CAN/CSA-S269.3 to produce finished concrete conforming to shape, dimensions, locations and levels indicated within tolerances required by CAN/CSA-A23.1.
- .6 Align form joints and make watertight. Keep form joints to minimum.
- .7 Use 25mm chamfer strips on external corners and/or 25mm fillets at interior corners, joints, unless specified otherwise.
- .8 Form chases, slots, openings, drips, recesses, expansion and control joints as indicated.
- .9 Build in anchors, sleeves, and other inserts required to accommodate Work specified in other sections. Assure that all anchors and inserts will not protrude beyond surfaces designated to receive applied finishes, including painting.

DFO P/N C2-00517 Floating Dock Constr	COI AN uction	NCRETE FORMING Section 03 10 00 D ACCESSORIES Page 5
Pugwash, NS		
	.10	Clean formwork in accordance with CAN/CSA-A23.1, before placing concrete.
3.2 REMOVAL AND RESHORING	.1	<pre>Leave formwork in place for following minimum periods of time after placing concrete. .1 7 days for walls and sides of beams. .2 7 days for columns. .3 5 days for beam soffits, slabs, decks and other structural members, or 3 days when replaced immediately with adequate shoring to standard specified for falsework. .4 5 days for footings and abutments.</pre>
	.2	Remove formwork when concrete has reached 75% of its design strength or minimum period noted above, whichever comes later, and replace immediately with adequate reshoring.
	.3	Provide all necessary reshoring of members where early removal of forms may be required or where members may be subjected to additional loads during construction as required.
	.4	Space reshoring in each principal direction at not more than 3000 mm apart.
	. 5	Re-use formwork and falsework subject to requirements of CAN/CSA- A23.1.
3.3 JOINT FILLERS	.1	Locate and form expansion joints as indicated. Install joint filler in all joints.

DFO	CONCRETE FORMING	Section 03 10 00
P/N C2-00517	AND ACCESSORIES	Page 6
Floating Dock	Construction	
Pugwash, NS		

.2 Use 13mm thick joint filler to separate slab-on-grade and extend joint filler from bottom of slab to within 25mm of finished slab surface unless indicated otherwise.

3.4 JOINT SEALANT

.1 Fill expansion and control joints with sealer as per manufacturer instructions.

DFO CONCRETE REINFORCING Section 03 20 00 P/N C2-00517 Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL 1.1 RELATED SECTIONS .1 Section 03 10 00 - Concrete Forming and Accessories. Section 03 30 00 - Cast-in-Place .2 Concrete. 1.2 REFERENCES American Concrete Institute (ACI) .1 ACI 315R latest edition, Manual .1 of Engineering and Placing Drawings for Reinforced Concrete Structure. American National Standards .2 Institute/American Concrete Institute (ANSI/ACI) ANSI/ACI 315 latest edition, .1 Details and Detailing of Concrete Reinforcement. .3 Canadian Standards Association (CSA) .1 CAN/CSA-A23.1 latest edition, Concrete Materials and Methods of Concrete Construction. .2 CSA-A23.3 latest edition, Design of Concrete Structures for Buildings. . 3 CSA G30.3 latest edition, Cold Drawn Steel Wire for Concrete Reinforcement. .4 CSA G30.5 latest edition, Welded Steel Wire Fabric for Concrete Reinforcement. .5 CSA G30.14 latest edition, Deformed Steel Wire for Concrete Reinforcement. .6 CSA G30.15 latest edition, Welded Deformed Steel Wire Fabric for Concrete Reinforcement. .7 CAN/CSA-G30.18 latest edition, Billet-Steel Bars for Concrete Reinforcement. .8 CAN/CSA-G40.21 latest edition, Structural Quality Steels.

DFO	CONCR	ETE REINFORCING	Section 03 20 00
P/N C2-00517	0011011		Page 2
Floating Dock Construct	ction		
Pugwash, NS			
		.9 CSA W186 lates Welding of Reinford Reinforced Concrete	st edition, cing Bars in e Construction.
1.3 SHOP DRAWINGS	.1	Submit shop drawing placing of reinford accordance with Sec Submittal Procedure	gs including cement in ction 01 33 00 - es.
	.2	Indicate on shop dr bending details, li of reinforcement, s locations of reinfor mechanical splices Departmental Repres identifying code ma correct placement w to structural drawi sizes, spacings and chairs, spacers and reinforcement drawi with Reinforcing St Standard Practice - Steel Institute of 315 and ACI 315R, M Engineering and Pla Reinforced Concrete	cawings, bar sts, quantities sizes, spacings, orcement and if approved by sentative, with arks to permit without reference ings. Indicate a locations of a hangers. Prepare ings in accordance ceel Manual of by Reinforcing Canada. ANSI/ACI Manual of acing Drawings for e Structure.
1.4 WASTE MANAGEMENT AND DISPOSAL	.1	Separate and recycl in accordance with - Construction/Demo Management and Disp Waste Reduction Wor	e waste materials Section 01 74 21 Dittion Waste Dosal and the Ckplan.

Floating Dock Construction

PART 2 - PRODUCTS

P/N C2-00517

DFO

2.1 MATERIALS	.1	Substitute different size bars only
		if permitted in writing by
		Departmental Representative.

- .2 Reinforcing steel: billet steel, grade 400, deformed bars to CAN/CSA-G30.18, unless indicated otherwise.
- .3 Reinforcing steel: weldable low alloy steel deformed bars to CAN/CSA-30.18.
- .4 Cold-drawn annealed steel wire ties: to CSA G30.3.
- .5 Welded steel wire fabric: to CSA G30.5. Provide in flat sheets only.
- .6 Chairs, bolsters, bar supports, spacers: to CAN/CSA-A23.1.
- .7 Mechanical splices: subject to approval of Departmental Representative.

2.2 FABRICATION

- .1 Fabricate reinforcing steel in accordance with CAN/CSA-A23.1, ANSI/ACI 315, and Reinforcing Steel Manual of Standard Practice by the Reinforcing Steel Institute of Canada. ACI 315R, Manual of Engineering and Placing Drawings for Reinforced Concrete Structures unless indicated otherwise.
 - .2 Obtain Departmental Representative's approval for locations of reinforcement splices other than those shown on placing drawings.

DFO	CONCR	ETE REINFORCING	Section 03 20 00
P/N C2-00517			Page 4
Floating Dock Construct	tion		
Pugwash, NS			
	.3	Upon approval of Dep Representative, well in accordance with	partmental d reinforcement CSA W186.
	.4	Ship bundles of bar clearly identified with bar bending de	reinforcement, in accordance tails and lists.
2.3 SOURCE QUALITY CONTROL	.1	Provide Departmenta with certified copy report of reinforci: physical and chemic minimum 2 weeks pri- reinforcing work.	l Representative of mill test ng steel, showing al analysis, or to commencing
	.2	Upon request inform Representative of p material to be supp	Departmental roposed source of lied.
PART 3 - EXECUTION			
3.1 FIELD BENDING	.1	Do not field bend of reinforcement except or authorized by Dep Representative.	r field weld t where indicated partmental
	.2	When field bending bend without heat, and steady pressure	is authorized, applying a slow •
	.3	Replace bars which splits.	develop cracks or
3.2 PLACING REINFORCEMENT	.1	Place reinforcing s on reviewed placing accordance with CAN	teel as indicated drawings and in /CSA-A23.1.
	.2	Use approved type c the reinforcing stee grade.	hairs to locate el at the proper

.3 Tie reinforcement where spacing in each direction is:

DFO P/N C2-00517 Floating Dock Constru Pugwash, NS	CONCF ction	ETE	REINFORCING	Section 03 20 00 Page 5
		.1 alt .2 int	Less than 300m ernate intersect 300mm or more: ersection.	m: tie at ions. tie at each
	.4	Pri Dep app pla	or to placing co artmental Repres roval of reinfor cement.	oncrete, obtain sentative's scing material and
	.5	Ens mai	ure cover to rei ntained during c	nforcement is concrete pour.
3.3 CLEANING	.1	Cle con	an reinforcing b crete to CAN/CSA	pefore placing A-A23.1.

DFO CAST D P/N C2-00517 Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

<u>1.1 DESCRIPTION</u> .1 This section specifies requirements for supply, placing, finishing, protecting and curing cast-in-place concrete for abutments.

1.2 RELATED SECTIONS

- .1 Section 03 10 00 Concrete Forming and Accessories.
- .2 Section 03 20 00 Concrete Reinforcing.

American Society for Testing and 1.3 REFERENCES .1 Materials (ASTM) ASTM C109/C109M latest edition, .1 Test Method for Compressive Strength of Hydraulic Cement Mortars (Using 2 in. or 50mm Cube Specimens). ASTM C260 latest edition, .2 Specification for Air-Entraining Admixtures for Concrete. ASTM C494/C494M latest edition, .3 Specification for Chemical Admixtures for Concrete.

> .2 Canadian General Standards Board (CGSB)
>
> .1 CAN/CGSB-51.34 latest edition, Vapour Barrier, Polyethylene Sheet for Use in Building Construction.
>
>
> .3 Canadian Standards Association (CSA)
>
> .1 CAN/CSA-A3000 latest edition.

.2 CAN/CSA-A23.1 latest edition, Concrete Materials and Methods of Concrete Construction.

.3 CAN/CSA-A23.2 latest edition, Methods of Test for Concrete.

DFO P/N C2-00517 Floating Dock Const	CAST :	IN PLACE CONCRETE Section 03 30 (Page 2
1.4 CERTIFICATES	.1	Submit certificates in accordance with Section 01 33 00 - Submittal Procedures.
	.2	<pre>Minimum 2 weeks prior to starting concrete work submit to Department Representative manufacturer's test data and certification by qualifie independent inspection and testing laboratory that following material will meet specified requirements: .1 Portland cement. .2 Blended hydraulic cement. .3 Supplementary cementing materials. .4 Grout. .5 Admixtures. .6 Aggregates. .7 Water. .8 Joint filler. .9 Joint Sealant.</pre>
	.3	Provide certification sealed by a professional engineer registered to practice in the Province of Nova Scotia, that mix proportions selected will produce concrete of quality, yield and strength as specified in concrete mixes, and will comply with CAN/CSA-A23.1.
	. 4	Provide certification that plant, equipment, and materials to be use in concrete comply with requiremen of CAN/CSA-A23.1.
1.5 STORAGE OF MATERIALS	.1	Store materials to prevent contamination or deterioration.
	.2	Provide adequate storage facilitie for materials to ensure a continuo supply of these materials during batching operations.

DFO P/N C2-00517 Floating Dock Constru Pugwash, NS	CAST I	IN PLACE CONCRETE Section 03 30 00 Page 3
	.3	Store cement in weathertight facility.
1.6 QUALITY ASSURANCE	.1	<pre>Minimum 2 weeks prior to starting concrete work, submit proposed quality control procedures to Departmental Representative for the following items: .1 Cold weather concrete. .2 Curing. .3 Finishes. .4 Formwork removal. .5 Joints.</pre>
1.7 WASTE MANAGEMENT AND DISPOSAL	.1	Use trigger operated spray nozzles for water hoses.
	.2	Designate a cleaning area for tools to limit water use and runoff.
	.3	Carefully coordinate the specified concrete work with weather conditions.
	.4	Ensure emptied containers are sealed and stored safely for disposal away from children.
	.5	Prevent plasticizers, water-reducing agents and air-entraining agents from entering drinking water supplies or streams. Using appropriate safety precautions, collect liquid or solidify liquid with an inert, noncombustible material and remove for disposal. Dispose of all waste in accordance with applicable local, provincial and national regulations.
	.6	Choose least harmful, appropriate cleaning method which will perform adequately.

PART 2 - PRODUCTS

2.1 MATERIALS

P/N C2-00517

Pugwash, NS

DFO

- .1 Cement as required to produce concrete with specified exposure class.
- .2 Supplementary cementing materials: to CAN/CSA-A3001.
- .3 Cementitious hydraulic slag: to CAN/CSA-A3001.
- .4 Water: to CAN/CSA-A23.1.
- .5 Aggregates: to CAN/CSA-A23.1. Coarse aggregates to be normal density.
- .6 Air entraining admixture: to ASTM C260.
- Chemical admixtures: to ASTM .7 C494/C494M. Departmental Representative to approve accelerating or set retarding admixtures during cold and hot weather placing.
- .8 Concrete retarders: to ASTM C494/C494M. Do not allow moisture of any kind to come in contact with the retarder film.
- .9 Curing compound: curing compounds are not to be used.
- .10 Premoulded joint fillers: Sponge rubber: to ASTM D1752, .1 Type I, flexible grade.

2.2 MIXES

Proportion concrete in accordance .1 with CAN/CSA-A23.1, Clause 4.3.

DFO CAST IN PLACE CONCRETE Section 03 30 00 P/N C2-00517 Page 5 Floating Dock Construction Pugwash, NS .2 Proportion concrete to comply with Alternate 1, Table 2 in CAN/CSA-A23.1 and following requirements: .1 Cement: Type GUb or otherwise .1 required to produce concrete with specified exposure class. Minimum compressive strength: .2 35 MPa at 28 days. .3 Class of exposure: C1. Minimum cement content: 385 .4 kg/m^3 of concrete. 20 mm nominal size coarse .5 aggregate. Air content 5% to 8%. .6 .7 Density of air-dry concrete in range of 2240 kg/m³ to 2400 kg/m³. .8 Slump at time and point of Discharge 50mm to 100mm. .3 When the Contractor wishes to purchase concrete from a ready mix concrete supplier, submit a letter from the supplier certifying the following: .1 That plant and equipment is certified and all materials to be used in the concrete comply with the requirements of CAN/CSA-A23.1. .2 That the mix proportions selected will produce concrete of the specified quality and yield. Indicate mix proportions and sources of all materials. That the strengths will comply .3 with the strengths specified herein. When the Contractor wishes to mix .4 concrete on site, identify the source of aggregates and submit samples of fine and coarse aggregates to a testing laboratory for testing and trial mixes in order to determine a suitable mix design.

The testing laboratory, at

DFO	CAST	ΙN	PLACE	CONCRETE	Section 03	3 30	00
P/N C2-00517					Page 6		
Floating Dock Constru	ction						
Pugwash, NS							

Contractor's cost, will test the trial mix for slump, air content, density and strength. The results of these tests will be submitted to the Departmental Representative to be reviewed for compliance with the specification. This review must be completed before permission to place concrete is given. .1 The sand, gravel, water and air entraining agent should be mixed prior to the addition of cement and water reducer. Weigh aggregates, cement, water and .5 admixture when batching. No alternative methods of measuring will be permitted. Do not use calcium chloride. .6 PART 3 - EXECUTION 3.1 PREPARATION .1 Obtain Departmental Representative's approval before placing concrete. Provide 24 hour notice prior to placing of concrete.

- .2 Pumping of concrete is permitted only after approval of equipment and mix.
- .3 Ensure reinforcement and inserts are not disturbed during concrete placement.
- .4 Prior to placing of concrete obtain Departmental Representative's approval of proposed method for protection of concrete during placing and curing in adverse weather.

DFO	CAST	IN PLACE CONCRETE Section 03 30 00
P/N C2-00517		Page 7
Floating Dock Constru	iction	5
Pugwash, NS		
	.5	Maintain accurate records of poured concrete items to indicate date, location of pour, quality, air temperature and test samples taken.
	.6	Do not place load upon new concrete until authorized by Departmental Representative.
3.2 CONSTRUCTION	.1	Comply with additional requirements of CAN/CSA-A23.1, Clause 4.1.1.5, for concrete exposed to seawater environments.
	.2	Minimum concrete cover over reinforcing steel bars to be 75 mm.
	.3	Place concrete in hot weather to CAN/CSA-A23.1.
	.4	Place concrete in cold weather to CAN/CSA-A23.1.
	.5	Keep concrete surfaces moist continually during protection stage.
	.6	Place, consolidate, finish, cure and protect concrete to CAN/CSA-A23.1.
	. 7	Do not commence placing concrete until Departmental Representative has inspected and approved forms, foundations, reinforcing steel, joints, conveying, spreading, consolidation and finishing equipment and curing and protective methods.
3.3 FORMWORK	.1	Install and strip formwork to

.1 Install and strip formwork to CAN/CSA-A23.1 and Section 03 10 00.

DFO P/N C2-00517 Floating Dock Constru Pugwash NS	CAST I ction	N PLACE CONCRETE	Section 03 30 00 Page 8
3.4 INSERTS	.1	Position and secure formwork to maintai grades.	anchor bolts in n line and
3.5 PLACING CONCRETE	.1	Place and consolida CAN/CSA-A23.1.	te concrete to
	.2	Do not place concre- frozen material.	te on or against
	.3	Place concrete cont joint to joint.	inuously from
	.4	Place concrete in a normal to the centre of placing to that a finished before bega set.	uniform heading, eline. Limit rate which can be inning of initial
3.6 STRIKE OFF AND CONSOLIDATION	.1	High speed internal shall be used to con- concrete during place compaction of the set done by beam-type v screed as approved be Representative. A set approximately 65mm of be maintained at the during consolidation	poker vibrators nsolidate the cing. Final urfaces shall be ibratory air by Departmental urcharge of of concrete will e screed face n.
	.2	Strikeoff and consol completed before exe to the surface.	lidation must be cess water bleeds
	.3	Ensure that the con- conforms to the ele- slopes as shown on - that satisfactory di- result.	crete deck vations and the drawings so rainage will
3.7 FINISHING	.1	Only ACI certified of approved concrete fine be utilized in finis concrete works. All	or other pre- inishers are to shing all work is to be

finished to CAN/CSA-A23.1, and as specified below.

- Strike off the surface with a .2 straight edge.
- .3 The surface shall be true and accurate to a maximum tolerance of 1mm in 500mm.
- 3.8 PROTECTION AND CURING

DFO

- Cure to CAN/CSA-A23.1. .1
- .2 Cure concrete by protecting it against loss of moisture, rapid temperature change and mechanical injury for at least 7 days after placement. After finishing operations have been completed, the entire surface of the newly placed concrete shall be covered by whatever curing medium is applicable to local conditions and approved by the Departmental Representative. The edges of concrete slabs exposed by removal of forms shall be protected with continuous curing treatment equal to the method selected for curing the slab and curb surfaces. Cure to CAN/CSA-A23.1. Have the equipment needed for adequate curing at hand and ready to install before actual concrete placement begins.
- When air temperature is at or below .3 5°C or when there is a probability of its falling to that limit within 24 hours of placing (as forecast by the nearest official meteorological office) cold weather protection as per CAN/CSA-A23.1 will be provided and the following:

Housing - Protect concrete by a .1 windproof shelter of canvas or other material to allow free circulation

Section 03 30 00 DFO CAST IN PLACE CONCRETE Page 10 P/N C2-00517 Floating Dock Construction Pugwash, NS of inside air around fresh touch formwork and provide sufficient space for removal of formwork for finishing. Supply approved heating equipment capable of keeping inside air at a constant temperature sufficiently high to maintain concrete at following curing temperatures. .1 For initial 3 days at a temperature of not less than 15°C nor more than 27°C at surface. .2 Maintain concrete at 10°C for an extra 4 days plus the initial 3 days. Departmental Representative will 3.9 TESTING .1 appoint a concrete testing company to test all work under this section of specification as per CAN/CSA-A23.1. .2 Cost of compressive strength tests shall be paid for by the Departmental Representative. Testing company shall issue reports .3 to Departmental Representative on quality of test cylinders. Notify Departmental Representative .4 at least 7 days prior to start of placing concrete. Provide for testing purposes an adequate quantity of approved test cylinders. At least 1 set of 3 cylinders each .5 shall be taken from 25m³ or fraction thereof of each day's pour, whichever is less. 1 cylinder shall

be tested at 7 days and other 2

tested at 28 days.

DFO	CAST	IN	PLACE	CONCRETE		Section	03 3	30	00
P/N C2-00517						Page 11			
Floating Dock (Construction								
Pugwash, NS									
	.6	С	rate d	cylinders	and	deliver	to	the	9

- testing laboratory within 48 hours after casting in accordance with CAN/CSA-A23.1. Contractor will pay for crating and delivery of cylinders to the laboratory.
- .7 If strength tests of test cylinder for any portion of the work falls below the specified compressive strength at 28 days, the Departmental Representative reserves the right to determine the acceptability of the concrete by performing additional field testing as outlined in CAN/CSA-A23.1.
- .8 If concrete does not conform to drawings or specifications, take measures as directed to correct the deficiency. All costs of correctional measures will be at the expense of the Contractor.

Section 05 50 00 DFO METAL FABRICATIONS P/N C2-00517 Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL .1 Section 01 33 00 - Submittal 1.1 RELATED SECTIONS Procedures. Section 03 30 00 - Cast-in-Place .2 Concrete. 1.2 REFERENCES .1 American Society for Testing and Materials International, (ASTM) ASTM A 53/A53M-latest edition, .1 Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Steamless. .2 ASTM A 269-latest edition, Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service. .2 Canadian General Standards Board (CGSB) .1 CAN/CGSB-1.181-latest edition, Ready-Mixed, Organic Zinc-Rich Coating. .3 Canadian Standards Association (CSA International) CAN/CSA-G40.20/G40.21-latest .1 edition, General Requirements for Rolled or Welded Structural Quality Steel. .2 CAN/CSA-G164-latest edition, Hot Dip Galvanizing of Irregularly Shaped Articles. .3 CAN/CSA-S16.1-latest edition, Limit States Design of Steel Structures. .4 CSA W48-latest edition, Filler Metals and Allied Materials for Metal Arc Welding (Developed in cooperation with the Canadian Welding Bureau). .5 CSA W59-latest edition, Welded Steel Construction (Metal Arc Welding).

DFO	METAI	L FABRICATIONS	Section 05 50 00
P/N C2-00517			Page 2
Floating Dock Construct	tion		
Pugwash, NS			
<u>1.3 SUBMITTALS</u>	.1	Product Data: .1 Submit manufactor product literature, a and data sheet in acc Section 01 33 00 - So Procedures. .2 Submit two copie - Material Safety Data accordance with Sects Submittal Procedures	urer's printed specifications cordance with ubmittal es of WHMIS MSDS ta Sheets in ion 01 33 00 - . Indicate VOC's:
	2	.1 For finishe primers and pair	es, coatings, nts.
	• 2	.1 Submit shop draw accordance with Sect: Submittal Procedures .2 Indicate materia thicknesses, finishes joints, method of and of anchors, supports, details, and accesso:	wings in ion 01 33 00 - als, core s, connections, chorage, number , reinforcement, ries.
1.4 QUALITY ASSURANCE	.1	Test Reports: Certif: showing compliance wi performance characte: physical properties.	ied test reports ith specified ristics and
	.2	Certificates: Product signed by manufacture materials comply with performance charactes criteria and physical	t certificates er certifying n specified ristics and l requirements.
1.5 DELIVERY, STORAGE, AND HANDLING	.1	Packing, Shipping, Ha Unloading: .1 Deliver, store, protect materials in Section 01 61 00 - Co Requirements.	andling and handle and accordance with ommon Product
	.2	Storage and Protection .1 Cover exposed st surfaces with pressur- heavy protection pape	on: tainless steel re sensitive er or apply

Section 05 50 00 DFO METAL FABRICATIONS P/N C2-00517 Page 3 Floating Dock Construction Pugwash, NS strippable plastic coating, before shipping to job site. .2 Leave protective covering in place until final cleaning of building. Provide instructions for removal of protective covering. PART 2 - PRODUCTS Steel shapes: CSA G40.21, Grade 350W 2.1 MATERIALS .1 or better; hollow structural sections: CSA G40.21, Grade 350W Class C; plates: to CSA G40.21, Grade 300W or better, All galvanized finish. Welding materials: to CSA W59. .2 .3 Welding electrodes: to CSA W48 Series. Bolts and anchor bolts: to ASTM A325. .4 Fabricate work square, true, straight 2.2 FABRICATION .1 and accurate to required size, with joints closely fitted and properly secured. .2 Use self-tapping shake-proof flat headed screws on items requiring assembly by screws or as indicated. Where possible, fit and shop assemble .3 work, ready for erection. Ensure exposed welds are continuous .4 for length of each joint. File or grind exposed welds smooth and flush. Galvanizing: hot dipped galvanizing 2.3 FINISHES .1 with zinc coating 600g/m² to CAN/CSA-G164. All steel used shall be hot

dipped galvanized.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	META: ion	L FABRICATIONS	Section 05 50 00 Page 4
	.2	Shop coat primer: to	CAN/CGSB-1.40.
	.3	Zinc primer: zinc ric CAN/CGSB-1.181.	ch, ready mix to
2.4 STEEL STRONGARM	.1	Sizes and shapes as i	Indicated.
PART 3 - EXECUTION			
3.1 ERECTION	.1	Do welding work in ac CSA W59 unless specif	cordance with fied otherwise.
	.2	Erect metalwork squar straight, and true, a fitted, with tight jo intersections.	re, plumb, accurately pints and
	.3	Exposed fastening dev finish and be compate material through whice	vices to match ible with ch they pass.
	• 4	Make field connection CAN/CSA-S16.1, or well	ns with bolts to Ld.
	.5	Hand items over for or concrete or building appropriate trades to setting templates.	casting into into masonry to ogether with
	.6	Touch-up rivets, fiel and burnt or scratche completion of erection	ld welds, bolts ed surfaces after on with primer.
	.7	Touch-up galvanized s zinc rich primer when field welding.	surfaces with re burned by
3.2 CLEANING	.1	Perform cleaning after to remove construction accumulated environme	er installation on and ental dirt.
	.2	Upon completion of in remove surplus mater: tools and equipment b	nstallation, ials, rubbish, parriers.

DFO P/N C2-00517 Floating Dock Construction	ALUMINUM GANGWAY Section 05 51 00 Page 1
Pugwasn, NS	
PART 1 - GENERAL	
1.1 RELATED SECTIONS .1	Section 01 33 00 - Submittal Procedures.
<u>1.2 REFERENCES</u> .1	Latest edition of CAN3-S157 Strength Design in Aluminum.
.2	Latest edition of AWS D1.2 Structural Welding Code - Aluminum.
.3	Canadian Standards Association (CSA International) .1 Latest edition of CAN/CSA-S6 Canadian Highway Bridge Design Code. .2 Latest edition of CSA W47.2 Certification of Companies for Fusion Welding of Aluminum. .3 Latest edition of CSA W59.2 Welded Aluminum Construction.
. 4	Latest edition of The Aluminum Association - Aluminum Design Manual.
.5	Latest edition of AASHTO - LRFD Guide Specifications for the Design of Pedestrian Bridges.
<u>1.3 SUBMITTALS</u> .1	Shop Drawings .1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures. All shop drawings shall be stamped by a Professional Engineer licensed to practice in the province of Nova Scotia.
.2	Company and Welder Certifications and Welding Procedures .1 Submit proof of company W47.2 certification at with shop drawings. .2 Submit welder performance qualification within a minimum of two weeks prior to starting welding.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	ALUMINUM GANGWAY Section 05 51 00 Page 2
1.4 DELIVERY, STORAGE, .1 AND HANDLING	<pre>Packing, Shipping, Handling and Unloading: .1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 - Common Product Requirements. .2 Protect gangway from damage until completion of the work. Any damage to the gangway shall be repaired by the Contractor.</pre>
PART 2 - PRODUCTS	
2.1 MATERIALS .1	Gangway shall be constructed of aluminum structural shapes, tubing, plates and bars of CSA aluminum alloy number GS11N (Alcan alloy 6061-T6) or have an equivalent yield strength of 240 MPa in the pre-welded condition and 110 MPa in the heat affected zone.
.2	Aluminum sawtooth grating for gangway walking surface shall be capable of spanning 1.2 m under an unfactored live load of 4.8 kPa. Submit load tables for proposed grating.
.3	Bolts connecting gangway to strongarm to Section 05 50 00 - Metal Fabrications.
2.2 FABRICATION .1	Fabricate work square, true, straight and accurate to required size, with joints closely fitted and properly secured.
.2	Do aluminum welding work in accordance with the lastest edition of CSA W59.2 or AWS D1.2.
.3	Companies and individuals doing welding shall be certified under the

latest edition of CSA W47.2.

DFO	ALUMINUM G	GANGWAY	Section	05	51	00
P/N C2-00517			Page 3			
Floating Dock Construction						
Pugwash, NS						
. 4	Welds exp continuou acceptanc	posed to view us and meet t ce criteria c	y shall k the visua of CSA WS	be al 59.2	2.	

.5 Welding electrodes shall be in conformance with ANSI/AWS Standard A5.10, alloy type 5356 and shall be certified by the Canadian Welding Bureau (CWB).

PART 3 - EXECUTION

3.1 ERECTION

.1 Erect gangway and connections to steel strongarms in accordance with the design drawings and approved shop drawings. Provide neoprene isolation gaskets between aluminum and steel connection points.

WOOD TREATMENT P/N C2-00517 Floating Dock Construction Pugwash, NS

PART 1 - GENERAL

DFO

.1 American Wood-Preservers' 1.1 REFERENCES Association (AWPA) Latest edition of AWPA M2, .1 Standard Inspection of Treated Wood Products. .2 Latest edition of AWPA M4, Standard for the Care of Preservative-Treated Wood Products. Canadian Standards Association (CSA) .2 . 1 Latest edition of CSA 080

Series, Wood Preservation. Latest edition of CSA 080.201, .2 Standard for Hydrocarbon Solvents for Preservatives. This Standard covers hydrocarbon solvents for preparing solutions of preservatives. This is not stand alone specification .3 Latest edition of CSA 0322, Procedure for Certification of Pressure-Treated Wood Materials for Use in Preserved Wood Foundations.

1.2 QUALITY ASSURANCE Testing of products treated with .1 preservative by pressure impregnation will be carried out by the manufacturer's testing laboratory to AWPA M2, and revisions specified in CSA 080 Series, Supplementary Requirements to AWPA М2.

> Inspection and testing of timber .2 materials will be carried out by the manufacturer.

1.3 CERTIFICATES AND .1 Submit certificates and assay ASSAY RETENTION retention results in accordance with Section 01 33 00 - Submittal RESULTS Procedures.

Section 06 05 73 DFO WOOD TREATMENT P/N C2-00517 Page 2 Floating Dock Construction Pugwash, NS .2 For products treated with preservative by pressure impregnation submit following information certified by authorized signing officer of treatment plant: Information listed in AWPA M2 .1 and revisions specified in CSA 080 Series, Supplementary Requirement to AWPA M2 applicable to specified treatment. .2 Moisture content after drying following treatment with water-borne preservative. .3 Assay retentions results representing each treated batch of supplied timber. Acceptable types of paint, .4 stain, and clear finishes that may be used over treated materials to be finished after treatment. 1.4 WASTE MANAGEMENT Do not dispose of preservative .1 treated wood through incineration. AND DISPOSAL .2 Do not dispose of preservative treated wood with other materials destined for recycling or reuse. .3 Dispose of treated wood, end pieces, wood scraps and sawdust at sanitary landfill approved by Departmental Representative. Dispose of unused wood preservative .4 material at official hazardous material collections site approved by Departmental Representative. .5 Do not dispose of unused preservative material into sewer system, into streams, lakes, onto ground or in other location where

they will pose health or environmental hazard.

Section 06 05 73 DFO WOOD TREATMENT P/N C2-00517 Page 3 Floating Dock Construction Pugwash, NS PART 2 - PRODUCTS Preservative: to CSA-080 Series. 2.1 MATERIALS .1 .2 Solvent: to CSA-080.201. Treat to CSA 080, commodity standard 2.2 PRESERVATIVE .1 080.18, Table 1 and its referenced TREATMENTS standards, with the following minimum assay retentions: CCA ACA Species kg/m3 kq/m3 Dimension Timber -Coast Douglas Fir 24 24 -Western/Eastern Hemlock 24 24 -Hemlock, Douglas Fir (Wheelguard, Wheelguard 10 10 Blocking) -Birch or Maple Treat to Refusal Note: Birch or maple must be air dried for six (6) months in weather protected environment or kiln dried.

PART 3 - EXECUTION

- 3.1 FIELD TREATMENT .1 Handle pressure treated material in a manner that will avoid damage which may expose untreated material. Rejection of any damaged material may result and replacement will be at the Contractor's expense.
 - .2 Fill all bored bolt holes with preservative immediately after boring. Use a pressurized container with hose to apply preservative, or some alternate method acceptable to the Departmental Representative.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	tion	WOOD TREATMENT	Section 06 05 73 Page 4
	.3	Fill all unused bored spike holes with tigh treated wooden plugs.	d holes and nt fitting
3.2 CUTTING	.1	Field cuts, if author receive three (3) lik the applicable preser to dry wood on each a	rized, are to beral coats of rvative applied application.
3.3 FIELD QUALITY	.1	Timber which contain exposing untreated we wane, or timbers which fastened in the work structurally sound ar	rot, splits ood, excessive ch cannot be so as to be ce unacceptable.
	.2	The Departmental Repr reserves the right to field testing of trea penetration and reter preservative. Timber requirements of the s may be rejected for u contract.	resentative carry out ated timber for ntion of not meeting the specification use under the

DFO EXCAVATION, TRENCHING, Section 31 23 10 P/N C2-00517 AND BACKFILLING Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL .1 Section 01 35 43 - Environmental 1.1 RELATED SECTIONS Procedures. American Society for Testing and 1.2 REFERENCES .1 Materials (ASTM) ASTM C117 latest edition, .1 Standard Test Method for Material Finer Than 0.075mm (No.200) Sieve in Mineral Aggregates by Washing. .2 ASTM C136 latest edition, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates. ASTM D422 latest edition, .3 Standard Test Method for Particle-Size Analysis of Soils. .4 ASTM D698 latest edition, Standard Test Methods for Laboratory Compaction Characteristics of Soil Using Standard Effort (12,400 ft lbs/ft^{3}) (600kN-m/m³). .5 ASTM D4318 latest edition, Standard Test Methods for Liquid Limit, Plastic Limit, and Plasticity Index of Soils. .2 Canadian General Standards Board (CGSB) .1 CAN/CGSB-8.1 latest edition, Sieves, Testing, Woven Wire, Inch Series. .2 CAN/CGSB-8.2 latest edition, Sieves, Testing, Woven Wire, Metric. Canadian Standards Association (CSA) .3 .1 CAN/CSA-A23.1 latest edition, Concrete Materials and Methods of Concrete Construction. .1 Excavation classes: two classes of 1.3 DEFINITIONS excavation will be recognized; common excavation and rock excavation.

DFO	EXCAVATION, TRENCHIN	NG, Section 31 23 10
P/N C2-00517	AND BACKFILLING	Page 2
Floating Dock Co	nstruction	
Pugwash, NS		

	.1 Rock : any solid material in excess of 0.25m ³ and which cannot be removed by means of heavy duty mechanical excavating equipment with 0.95 to 1.15m ³ bucket. Frozen material not classified as rock. .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation.
.2	Waste material: excavated material unsuitable for use in Work or surplus to requirements.
.3	Borrow material: material obtained from locations outside area to be graded, and required for construction of fill areas or for other portions of Work.
. 4	Unsuitable materials: .1 Weak and compressible materials under excavated areas. .2 Frost susceptible materials under excavated areas. .3 Frost susceptible materials: .1 Fine grained soils with plasticity index less than 10 when tested to ASTM D4318, and gradation within limits specified when tested to ASTM D422 and ASTM C136: Sieve sizes to CAN/CGSB-8.1. .2 Table <u>Sieve Designation % Passing</u> 2.00mm 100 0.10mm 45 - 100 0.02mm 10 - 80 <u>0.005mm 0 - 45</u> .3 Coarse grained soils containing more than 20% by mass passing 0.075mm sieve.

.5 Unshrinkable fill: very weak mixture of Portland cement, concrete
DFO EXCAVATION, TRENCHING, Section 31 23 10 P/N C2-00517 AND BACKFILLING Page 3 Floating Dock Construction Pugwash, NS aggregates and water that resists

settlement when placed in utility trenches, and capable of being readily excavated.

PART 2 - PRODUCTS

2.1 MATERIALS

.1 Type 1 and Type 2 Fill: crushed and screened rock or gravel. Material shall consist of hard and durable stone particles. Gradation shall be dense, well graded and within limits specified when tested to ASTM C 136 and as follows: .1 Type 1:

Sieve Size, μmPercent Passing20 00010014 00050-855 00020-501605-12803-8

.2 Type 2

Sie	ve Size, µ	m	Percent	Passing
80	000		100	
56	000		70-100	
28	000		50-80	
14	000		35-65	
5	000		20-50	
	160		3-10	
	80		0-7	

.2 Type 1 and Type 2 Fill shall have a fractured particle content of 50% per one face (minimum). The fractured particles shall have at least one well defined fresh face resulting from fracture, with the face comprising no less than 20% of the particle surface area. Particles with smooth faces and rounded edges, or with only small chips removed, are not considered fractured.

Section 31 23 10 DFO EXCAVATION, TRENCHING, P/N C2-00517 AND BACKFILLING Page 4 Floating Dock Construction Pugwash, NS PART 3 - EXECUTION 3.1 SITE PREPARATION .1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated. Excavate to lines, grades, 3.2 EXCAVATION .1 elevations and dimensions as indicated. .2 Excavation must not interfere with bearing capacity of adjacent foundations. Dispose of surplus and unsuitable .3 excavated material in approved location off site. .4 Do not obstruct flow of surface drainage. Earth bottoms of excavations to be .5 undisturbed soil, level, free from loose, soft or organic matter. Notify Departmental Representative .6 when bottom of excavation is reached. .7 Obtain Departmental Representative's approval of completed excavation. 3.3 FILL TYPES AND Use fill of types as indicated. .1 COMPACTION .2 Only Type 1 and Type 2 fill material approved by Departmental Representative will be placed. Material will be placed uniformly across full cross-section in layers not exceeding 150mm loose depth.

.3 Use suitable earth moving and surface grading equipment to place

DFO	EXCAVA	TION, TRENCHING, Section 31 23 10
P/N C2-00517	ANI	BACKFILLING Page 5
Floating Dock Co Pugwash, NS	onstruction	
		and spread fill in continuous and uniform horizontal layers.
	. 4	Compact Type 1 and Type 2 fill after each 150mm lift (maximum).
	.5	Place type 1 and type 2 fill after sub-base surface is inspected and approved by Departmental Representative.
	.6	<pre>Placing: .1 Construct Type 1 and Type 2 fill to depth and grade in area indicated. .2 Ensure no frozen material is placed. .3 Place material only on clean unfrozen surface, free from snow and ice. .4 The contractor shall place all Type 1 and Type 2 fill in such a manner as to prevent contamination by other materials and to prevent segregation. If, in the opinion of the Departmental Representative, the methods and techniques used by the Contractor cannot overcome contamination or segregation, then the Departmental Representative may direct a modification in these methods which may require the use of an approved spreader box or other acceptable device. .5 All Type 1 and Type 2 fill shall be placed in uniform layers such that the thickness of the compacted layer does not exceed 50mm. .6 Prior to closing down operations for each working day, all granular materials shall be bladed and compacted to the specified density. .7 The materials shall be sprayed with water when and as directed by</pre>

DFO	EXCAVATION, TR	ENCHING, Sect	ion 31 23 10
P/N C2-00517	AND BACKFII	LING Page	6
Floating Dock Co	onstruction		
Pugwash, NS			

	the Departmental Representative, either to aid compaction or reduce dust nuisance or both. When water is added to aid compaction, it shall be applied immediately ahead of the compacting unit. .8 Each layer of Type 1 and Type 2 fill shall be bladed shaped and compacted as necessary to produce the required profile and cross- section. The finished surface shall not deviate at any place on a 3 m straight edge by more than 10mm. The upper layer shall be maintained to these tolerances and to the specified density until compaction of the contract. This may require keeping the moisture content at the appropriate value during periods of dry weather in addition to regarding and re-compacting as frequently as may be deemed necessary by the Departmental Representative.
.7	Shape each layer to smooth contour and compact to specified density before succeeding layer is placed.
.8	Compaction Equipment: .1 Compaction equipment to be capable of obtaining required material densities.
.9	Compacting: .1 All Type 1 and Type 2 fill shall be compacted to not less than 100% of the maximum Standard Proctor Dry Density ASTM D698-07el Method D. .2 Compaction operations shall be carried out as closely as possible behind the placing and spreading operation. At the end of each working day, all materials placed shall have been compacted to the

specified density. .3 Each layer of material shall be DFO

P/N C2-00517

Pugwash, NS graded and compacted as specified before the next layer is placed. Where necessary to obtain the .4 required compaction, the contractor shall apply sufficient water by means of an approved distributor. .1 Do not proceed with backfilling 3.4 BACKFILLING operations until Departmental Representative has inspected and approved installations. .2 Areas to be backfilled to be free from debris, snow, ice, water and frozen ground. .3 Do not use backfill material which is frozen or contains ice, snow or debris. .4 Place backfill material in uniform layers not exceeding 150mm compacted thickness up to grades indicated. Compact each layer before placing succeeding layer. .5 Backfilling around installations. Place bedding and surround .1 material as specified elsewhere. Do not backfill around or over .2 cast-in-place concrete within 24 hours after placing of concrete. Place layers simultaneously on .3 both sides of installed Work to equalize loading. Difference not to exceed 1.0m. Upon completion of Work, remove 3.5 RESTORATION .1

waste materials and debris, trim slopes, and correct defects as directed by Departmental Representative.

DFO	EXCAVATION,	TRENCHING,	Section 31 23 10	
P/N C2-00517	AND BACKF	TILLING	Page 8	
Floating Dock Constru Pugwash, NS	ction			

- .2 Clean and reinstate areas affected by Work as directed by Departmental Representative.
- .3 Restore site to its normal state prior to excavation.

Section 31 23 26 DFO ROCK FILL P/N C2-00517 Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL This section specifies the 1.1 DESCRIPTION .1 requirements for the supplying, producing, placing, and compaction of Levelling Course in the areas as indicated, as well as the reinstatement of corestone berm material. ASTM C 117 latest edition, Test 1.2 REFERENCES .1 method for material finer than 0.075 mm sieve in mineral aggregates by washing. .2 ASTM C 131 latest edition. Test method for resistance to degradation of small size coarse aggregate by abrasion and impact in the Los Angeles machine. ASTM C 136-6 latest edition, Method .3 for sieve analysis of fine and coarse aggregates, CAN/CGSB-8.2 latest edition, Sieves testing, woven wire, metric. 1.3 DELIVERY, STORAGE .1 Deliver and stockpile aggregates as directed by Departmental AND HANDLING Representative. PART 2 - PRODUCTS

2.1 LEVELING COURSE .1 Leveling course will consist of clean, hard, durable crushed gravel or stone, free from shale clay, friable materials, organic matter and other deleterious substances and graded within the following limits when tested to ASTM C136-84 and ASTM C117-87 and giving a smooth curve without sharp breaks when plotted on a semi-log chart.

DFO	ROCK FILL	Section 31 23 26
P/N C2-00517		Page 2
Floating Dock Constructio	n	
Pugwasii, NS		
	ASTM Sieve	e % Passing
	Designatio	on Leveling Course
	28mm	-100
	25.4mm	-
	19.0mm	90-100
	10mm	0-40
	5mm	0-10
	Physical Requ	irements for:
	 Los Ange Maximum) 35 	eles Abrasion* (Loss % ASTM C131-89 35, C535-89
	 Percent Ci 	cushed (% Minimum) 50
	 Plasticity 	/ Index ASTM D4318-84 0
	• Petrograph 23-2-M90	nic Number (max) ASTM CSA 150
PART 3 - EXECUTION		
3.1 PLACING ROCK FILL .1	Only rock Department placed. M uniformly in layers depth.	fill material approved by cal Representative will be Material will be placed across full cross-section not exceeding 300mm loose
.2	Rock Fill underwater manner to (i.e., enc acceptable	materials placed s should be placed in a minimize segregation. d dumping will not be e).
.3	Above wate	er level, use suitable

- .3 Above water level, use suitable earth moving and surface grading equipment to place and spread backfill in continuous and uniform horizontal layers.
- .4 Above water level, compact rock fill after each 300 mm lift with a 10 tonne (minimum) steel drum vibratory roller making a minimum of 6 passes. Compaction within 2 m of a

DFO P/N C2-00517 Floating Dock Constructio Pugwash, NS	ROCK FILL n	Section 31 23 26 Page 3
	structural mem should be perf rolling only.	ber or wharf face ormed by static
3.2 LEVELING COURSE .1	Place leveling indicated on d	course to thickness rawings.
. 2	Do not place l the rock mattr by the Departm	eveling course until ess has been accepted ent Representative.
.3	Level top surf grade.	ace to specified
. 4	Contractor to sections with m intervals in top of the lev installation o Surface of lev within 40 mm o on drawings.	provide plan and cross elevation shots at 1.5 each direction on the reling course prior to f the precast footing. reling course to be f elevation indicated
<u>3.3 PROTECTION</u> .1	Maintain finis conforming to succeeding mat until acceptan Representative	hed base in condition this section until erial is applied or ce by Departmental
3.4 CO-OPERATION AND .1 ASSISTANCE TO DEPARTMENTAL PEDDESENTATIVE	Co-operate wit Representative and provide as	h Departmental on inspection of work sistance requested.
.2	On request of Representative boats, equipme materials form part of excava reasonably nec supervise work	Departmental , furnish use of such ent, labour and ling ordinary and usual ting plant as may be lessary to inspect and

Section 31 32 21 DFO GEOTEXTILES P/N C2-00517 Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL 1.1 SECTION INCLUDES .1 Materials and installation of polymeric geotextiles used in breakwaters, retaining wall structures, filtration, drainage structures and roadbeds, purpose of which is to: Separate and prevent mixing of .1 granular materials of different grading. .2 Act as hydraulic filters permitting passage of water while retaining soil strength of granular structure. Section 01 33 00 - Submittal 1.2 RELATED WORK .1 Procedures. Section 01 74 21 -.2 Construction/Demolition Waste Management and Disposal. .3 Section 31 23 10 - Excavating, Trenching and Backfilling. Section 31 23 26 - Rock Fill. .4 ASTM International 1.3 REFERENCES .1 .1 ASTM A123/A123M latest edition, Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products. ASTM D4491 latest edition, .2 Standard Test Methods for Water Permeability of Geotextiles by Permittivity. ASTM D4595 latest edition, .3 Standard Test Method for Tensile Properties of

Geotextiles by the Wide- Width

Strip Method.

DFO GEOTEXTILES Section 31 32 21 P/N C2-00517 Page 2 Floating Dock Construction Pugwash, NS .4 ASTM D4716 latest edition,

.2

.3

Standard Test Method for Determining the (In-Plane) Flow Rate Per Unit Width and Hydraulic Transmissivity of a Geosynthetic Using a Constant Head. ASTM D4751 latest edition, .5 Standard Test Method for Determining Apparent Opening Size of a Geotextile. Canadian General Standards Board (CGSB) CAN/CGSB-4.2 No. 11.2, .1 Textile Test Methods - Bursting Strength - Ball Burst Test (Extension of September 1989). CAN/CGSB-148.1, Methods of .2 Testing Geotextiles and Complete Geomembranes. .1 No.2, Methods of Testing Geosynthetics - Mass per Unit Area. .2 No.3, Methods of Testing Geosynthetics - Thickness of Geotextiles. No.6.1, Methods of Testing .3 Geotextiles and Geomembranes -Bursting Strength of Geotextiles Under No Compressive Load. No.7.3, Methods of Testing .4 Geotextiles and Geomembranes -Grab Tensile Test for Geotextiles. .5 No. 10, Methods of Testing Geosynthetics - Geotextiles -Filtration Opening Size. CSA International

.1 CSA G40.20/G40.21 latest edition, General Requirements for Rolled or Welded Structural Quality Steel/Structural Quality Steel.

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	tion	GEOTEXTILES	Section 31 32 21 Page 3
1.4 SAMPLES	.1	Submit samples in Section 01 33 00 - Procedures.	accordance with Submittal
	.2	Submit to Departme Representative the at least 2 weeks p work. .1 Methods of jo	ental e following samples prior to commencing pining.
1.5 MILL CERTIFICATES	.1	Submit to Departme Representative a c data and certifica weeks prior to sta	ental copy of mill test at least 2 art of work.
1.6 DELIVERY AND STORAGE	.1	During delivery an geotextiles from d ultraviolet rays, mud, dirt, dust, d	nd storage, protect lirect sunlight, excessive heat, lebris and rodents.
1.7 WASTE MANAGEMENT AND DISPOSAL	.1	Separate waste mat and recycling in a Section 01 74 21 - Construction/Demol Management And Dis	cerials for reuse accordance with tition Waste sposal.
	.2	Remove from site a packaging material recycling faciliti	and dispose of all s at appropriate es.
	.3	Collect and separa paper, plastic, po corrugated cardboa material, in appro bins, for recyclin with Waste Managem	te for disposal olystyrene, ard, and packaging opriate on-site ag in accordance ment Plan.
	.4	Fold up metal band place in designate recycling.	ling, flatten and ed area for

Section 31 32 21 DFO GEOTEXTILES P/N C2-00517 Page 4 Floating Dock Construction Pugwash, NS PART 2 - PRODUCTS 2.1 MATERIAL .1 Geotextile: woven or non-woven synthetic fibre fabric, supplied in rolls. .1 Width: 3.5m minimum. .2 Length: 50m minimum. .3 Composed of: minimum 85% by mass of polyester with inhibitors added to base plastic to resist deterioration by ultra-violet and heat exposure. .2 Physical properties: Thickness: to CAN/CGSB-148.1, .1 No.3, minimum 2.5mm. .2 Mass per unit area: to CAN/CGSB-148.1, No. 2, minimum $400q/m^{2}$. Tensile strength and elongation .3 (in any principal direction): to ASTM D4595. Tensile strength: minimum .1 1200 N, wet condition. .2 Elongation at break: 50 to 100 percent. Seam strength: equal to or .3 greater than tensile strength of fabric. .4 Mullen burst strength: to CAN/CGSB-4.2, method 11.1, minimum 3100 kPa. .3 Hydraulic properties: Apparent opening size (AOS): to .1 ASTM D4751, 50 to 150 micrometres. .2 Permittivity: to ASTM D4491, 0.25 cm per second. Securing pins and washers: to .4 CAN/CSA-G40.21, Grade 300W, hotdipped galvanized with minimum zinc coating of 600 g/m^2 to CAN/CSA G164.

GEOTEXTILES

DFO G P/N C2-00517 Floating Dock Construction Pugwash, NS

PART 3 - EXECUTION

3.1	INSTALLATION	.1	Place	geot	text	tile	materia	1	as
			indica	ated	on	the	drawing	s.	

- .2 Place geotextile material by unrolling onto graded surface in orientation, manner and locations indicated and retain in position with securing pins and washers.
- .3 Place geotextile material on sloping surfaces in one continuous length from toe of slope to upper extent of geotextile.
- .4 Place geotextile material smooth and free of tension stress, folds, wrinkles and creases.
- .5 Overlap each successive strip of geotextile 600 mm over previously laid strip.
- .6 Protect installed geotextile material from displacement, damage or deterioration before, during and after placement of material layers.
- .7 After installation, cover with overlying layer within 4 hours of placement.
- .8 Replace damaged or deteriorated geotextile to approval of Departmental Representative.
- .9 Place and compact rock fill in accordance with Section 31 23 26 Rock Fill.

.1 Remove construction debris from Project site and dispose of debris in an environmentally responsible and legal manner.

3.2 CLEANING

DFO GEOTEXTILES Section 31 32 21 P/N C2-00517 Page 6 Floating Dock Construction Pugwash, NS

<u>3.3 PROTECTION</u> .1 Vehicular traffic not permitted directly on geotextile.

Section 31 53 16 DFO STRUCTURAL TIMBER P/N C2-00517 Page 1 Floating Dock Construction Pugwash, NS PART 1 - GENERAL .1 This section specifies requirements 1.1 DESCRIPTION for supply and installation of structural timber as follows: Supply and installation of .1 treated dimension timber floating docks, and associated painting, hardware and galvanizing. .1 Section 06 05 73 - Wood Treatment. 1.2 RELATED WORK .2 Section 05 50 00 - Metal Fabrications. American Society for Testing and 1.3 REFERENCES .1 Materials (ASTM International) ASTM A3125, Specification for .1 Steel Bolts, 120,000 PSI Tensile. American Wood-Preserver's .2 Association (AWPA) .1 Latest edition of AWPA M4, Standard for the Care of Preservation - Treated Wood Products. .3 Canadian Standards Association (CSA International) .1 Latest edition of CSA B111, Wire Nails, Spikes and Staples. Latest edition of CAN/CSA-.2 G40.21, General Requirements for Rolled or Welded Structural Quality Steel/Structural Steel. .3 Latest edition of CAN/CSA G164, Hot Dip Galvanizing of Irregularly Shaped Articles. . 4 Latest edition of CAN/CSA-080 Series, Wood Preservation.

DFO P/N C2-00517	STRUCTURAL TIMBER Section 31 53 16 Page 2
Floating Dock Construction Pugwash, NS	1
.4	Canadian Wood Council .1 Wood Design Manual.
. 5	National Lumber Grades Authority (NLGA) .1 Latest edition of Standard Grading Rules for Canadian Lumber.
<u>1.4 DIMENSIONS</u> .1	Check existing site dimensions and report discrepancies to Departmental Representative before commencing work.
<u>1.5 PROTECTION</u> .1	Avoid dropping, bruising or breaking of wood fibres.
.2	Avoid breaking surfaces of treated timber.
.3	Do not damage surfaces of treated timber by boring holes or driving nails or spikes into them to support temporary material or staging.
. 4	Treat cuts, breaks or abrasions on surfaces of treated timber with 3 brush coats of preservative to CSA 080.
.5	Treat bolt holes, cutoffs and field cuts in accordance with CSA 080.
1.6 DELIVERY AND .1 STORAGE	Store timber horizontally, evenly supported and open piled permit circulation when stored for prolonged period.
.2	When handling long timber, provide support at sufficient number of points, properly located to prevent damage due to excessive bending.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	STRUCTURAL TIMBER Section 31 53 16 Page 3
.3	Handle treated timber with hemp, manila or sisal rope slings or other approved means of support that will not damage surface.
. 4	Do not use sharp pointed tools to handle treated timber. Any timber so handled will be rejected and be replaced at Contractor's expense.
<u>1.7 SUBMITTALS</u> .1	Submit shop drawings for buoyancy compartment shells and foam filler.
PART 2 - PRODUCTS	
2.1 TIMBER MATERIALS .1	Timber: Use timber graded and stamped in accordance with applicable grading rules and standards of associations or agencies approved to grade lumber by Canadian Lumber Standards Administration Board of CSA.
.2	Species .1 Wheelguard, wheelguard blocks, floating dock and cribwork timbers: Hemlock or Douglas Fir (CCA or ACA treated).
.3	Grade: No. 1 Structural Grade
. 4	Grading Authority: NLGA
.5	Preservative Treatment: Treat to CSA 080, for coastal waters and Section 06 05 73. Timbers will be treated in the lengths required. Unnecessary field cutting will not be permitted.
. 6	Primer: Alkyd undercoat, exterior oil wood primer, similar to Pittsburgh 6-9.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	STRUCTURAL TIMBER Section 31 53 16 Page 4
.7	Paint: Alkyd/Oil Resin paint similar to Pittsburgh Paints "Safety Yellow" Product ID 7-808. Paint to conform to latest edition of CAN/CGSB-1.61.
.8	Plywood: pressure treated douglas fir plywood to latest edition of CSA 0141.
2.2 MISCELLANEOUS .1 STEEL AND FASTENINGS	Miscellaneous Steel: All steel and fastenings to be CSA G40.21, Grade 300W, galvanized.
.2	Nails and Spikes: to CSA B111.
.3	Machine Bolts and Nuts: to ASTM A325. All machine bolts and nuts to be galvanized.
. 4	Drift Bolts: to G40.21 from round stock button head and diamond or wedge point. All drift bolts to be galvanized.
.5	<pre>Washers: .1 Round Plate Washers: for 16mm machine bolts will be 76mm diameter by 6.4mm thick, for 19mm machine bolts will be 79mm diameter by 7.9mm thick and have a hole diameter of 18mm and 21mm diameter respectively. Washers to conform to G40.21. All washers to be galvanized. .2 Plain Washers: to CSA B19.1, Class 2. All washers to be galvanized. .3 Square washers are not permitted.</pre>
.6	Galvanizing: will conform to CSA G164 "Hot Dip Galvanizing of Irregularly Shaped Articles." Unless otherwise specified, minimum weight of zinc coating will be as stated in

DFO P/N C2-00517	STRUCTURAL TIMBER Section 31 53 16 Page 5
Floating Dock Constructic Pugwash, NS	n
	Table 1 of this standard. Fabricator is to adhere to recommendations of CSA G164.
. 7	Welding in accordance with CSA Standards. The welders will be qualified to the appropriate classification as stated in CSA W47.1 "Certification of Companies for Fusion Welding of Steel Structures." Conform welding to all appropriate requirements and recommendations of CSA Standard W59 "Welded Steel Construction" (metal arc welding).
2.3 BUOYANCY .1 COMPARTMENTS	Buoyancy compartment shells to be manufactured from linear virgin polyethylene resin containing UV ray inhibitors and carbon black pigment to protect against ultra-violet deterioration. Shells shall be rotationally molded for seamless, one piece construction with a 3.2 mm wall thickness.
.2	Buoyancy compartment shells to be filled with urethane foam with a maximum density of 32 kg/m3.
PART 3 - EXECUTION	
3.1 FLOATING DOCK .1 TIMBER	Install floating dock timbers and all other floating dock components as indicated on drawings.
.2	Dress timber decking on bottom side to ensure uniform thickness and level walking surface.

DFO P/N C2-00517 Floating Dock Construction	STRUCTURAL TIMBER Section 31 53 16 Page 6
Pugwash, NS	
<u>3.2 PAINTING</u> .1	Paint wheelguard and wheelguard blocking as directed by the Departmental Representative.
.2	Use one (1) coat of exterior oil wood primer and two (2) coats of alkyd/oil resin paint as specified. Paint materials for each coat to be product of a single manufacturer as specified. Ensure previous coat of primer or paint is dry before second coat is applied.
<u>3.3 BOLT SIZING</u> .1	Drift Bolts: Drift bolts used in the work will have a length equal to thickness of timbers being fastened less 50mm unless otherwise specified. Holes for drift bolts will be bored 2mm smaller diameter than size of steel used and for full length of bolts.
.2	Machine Bolts: Machine bolts used in work will have a length equal to thickness of timbers being fastened plus thickness of washers plus 40mm. Where bolts are countersunk, the length will be as above less depth of countersinking. Machine bolts will be threaded for 64mm. Holes will be drilled same diameter as bolt.
.3	Lag Screws: All lag screws used in the work will have a length equal to thickness of timbers being fastened less 50mm and depth of countersinking. Holes for lag screws to be drilled same diameter as shank portion of screw and to inside

of screw and for full length. All lag screws will be countersunk,

thread diameter for threaded portion

DFO	STRUCTURAL	TIMBER	Section	31	53	16
P/N C2-00517			Page 7			
Floating Dock Construction						
Pugwash, NS						
	screwed,	not driven	in place,	, an	nd	
	will have	one (1) st	andard wa	ıshe	er	
	under the	head.				

- .4 Countersink drift bolts and/or lag screws in ladders to the extent that the minimum distance from face of timber to head of bolt is 12mm.
- .5 Bolting of timbers without properly drilled bolt holes will not be accepted.

DFO	DREDG	ING Section 35 20 23
P/N C2-00517		Page 1
Floating Dock Construction		
Pugwash, NS		
<u> PART 1 - GENERAL</u>		
1.1 REFERENCES .1	Defini	tions:
	.1 A h w a b	verage of Instantaneous Plan: ydrographic survey plan in hich average sounding in an ppropriate group of matrix locks is plotted.
	.2 B a e n	ox Cut: excavating channel rea with vertical side slopes nd allowing side slope of xcavation collapse to a atural equilibrium slope.
	.3 C r t 1	lass A Material: solid rock equiring drilling and blasting o loosen, and boulders or rock ragments of individual volumes .5 m3 or more.
	.4 C s c h i 1	lass B Material: loose or hale rock, silt, sand, quick and, mud, shingle, gravel, lay, sand, gumbo, boulders, ardpan and debris of ndividual volumes less than .5 m3.
	.5 C e s r N	hart Datum: permanently stablished plane from which oundings or tide heights are eferenced, usually Lowest ormal Tide (LNT).
	.6 C e c s	leared Area: area of xcavating accepted as omplying with plans and pecifications.
	.7 C T	o-ordinates: 1 U.T.M.: Universal ransverse Mercator projection. 2 M.T.M.: Modified ransverse Mercator projection. 3 U.T.M. or M.T.M. Co- rdinates: plane rectangular o-ordinates used in grid ystem in which grid network is pplied to U.T.M. or M.T.M. rojection. Horizontal control nformation as indicated.

DFO	DREI	OGING Section 35 20 23
P/N C2-00517		Page 2
Floating Dock Construction		5
Pugwash, NS		
	0	
	.8	Debris: pieces of wood, wire
		rope, scrap steel, pieces of
		concrete and other waste
		materials.
	.9	Excavating: excavating,
		transporting and disposing of
		underwater materials.
	.10	Estimated Quantity:
		.1 Volume of material
		calculated to be above sub-
		grade and within specified side
		slopes unless otherwise
		specified.
		.2 Areas in square metres of
		material calculated
		horizontally to exist above
		grade and within excavation
		limits, unless otherwise
		specified.
	.11	Grade: plane above which
		material is to be excavated.
	.12	Hydraulic Excavating Plant:
	•	equipment that uses the
		movement of water to excavate
		and transport underwater
		materials such as cutter
		suction excavator, suction
		excavator or trailing suction
		hopper excavator
	13	Instantaneous Mode: mode of
	• ± 5	operation of hydrographic
		survey equipment where enly
		sounding observed at
		prodotorminod distance interval
		is retained in memory
	1 /	Is recarned in memory.
	• 1 4	heast of Millimum Fidil:
		nyurographic survey plan in
		which least sounding in
		grouping of matrix blocks is
		prottea.
	.15	Lowest Normal Tide (LNT): plane
		so low that tide will seldom
		fall below it.

P/N C2-00517 Floating Dock Construction Pugwash, NS .16 Matrix Block: each excavated area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection	DFO			DRED	GING	Section 35 20 23
 Floating Dock Construction Pugwash, NS .16 Matrix Block: each excavated area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection 	P/N C2-00	1517		21.22	02110	Page 3
 Plagwash, NS .16 Matrix Block: each excavated area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (UTM) or Condinates plane 	Electing		Constantion			rage 5
 I.16 Matrix Block: each excavated area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. I.17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. I.18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. I.19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations. I.20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. I.21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. I.22 Sub-grade: plane parallel to and 300 mm below grade. I.31 Nirverse Mercator Projection (UTM) or Modified Transverse Merca	Floating	DOCK	Construction			
 .16 Matrix Block: each excavated area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to ave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m 3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .31 Mire Suber Sub and S	i ugwasii,	110				
 area is presented as number of 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. 17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .31 Wirth of the substance of the substance of the projection (UTM) or Modified Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (UTM) creates: plane 				.16	Matrix Block:	each excavated
 1.2 x 10 m long blocks. Dependent on position of sounding, block may have 0 to 4 soundings contained within it. 1.1 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. 1.8 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. 1.9 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations. 20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. 21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. 22 Sub-grade: plane parallel to and 300 mm below grade. 23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 				• ± •	area is presen	ted as number of
 Dependent on position of sounding, block may have 0 to 4 soundings contained within it. 17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. 18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. 19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. 20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. 21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. 22 Sub-grade: plane parallel to and 300 mm below grade. 23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					$1 2 \times 10 \text{ m}$ lon	a blocks
 bependent on position of sounding, block may have 0 to 4 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (WTM) Co-ordinates: plane 						g DIOCKS.
 sounding, block may have 0 to 4 soundings contained within it. 17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 						
 soundings contained within it. .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					sounding, bloc	k may nave U to 4
 .17 Mechanical Excavation Plant: equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 				4 5	soundings cont	ained within it.
<pre>equipment comprising of the following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				• 1 /	Mechanical Exc	avation Plant:
<pre>following: clamshell, dragline, dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					equipment comp	rising of the
<pre>dipper or backhoe excavate with dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					following: cla	mshell, dragline,
 dump scows. .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					dipper or back	hoe excavate with
 .18 Mechanical Sweep: clearing excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					dump scows.	
<pre>excavated areas to grade depth using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				.18	Mechanical Swe	ep: clearing
<pre>using a mechanical device suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					excavated area	s to grade depth
<pre>suspended from barge. .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					using a mechan	ical device
 .19 Minimum Mode: mode of operation of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (MTM) Co-ordinates: plane 					suspended from	barge.
<pre>of hydrographic survey equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				.19	Minimum Mode:	mode of operation
<pre>equipment where minimum sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					of hydrographi	c survey
 sounding over length of travel between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. 20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. 21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					equipment wher	e minimum
between position updates will be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					sounding over	length of travel
<pre>be retained in memory. Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					between positi	on updates will
Soundings taken in this mode may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					be retained in	memory.
<pre>may be shallower than actual bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					Soundings take	n in this mode
 bottom elevations due to variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					mav be shallow	er than actual
 variations in water depths due to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					bottom elevati	ons due to
 to wave action. .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					variations in	water depths due
 .20 Obstructions: material other than class A, having individual volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					to wave action	
<pre>that there is a state of the the class A, having individual volumes of 1.5 m3 or more21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical22 Sub-grade: plane parallel to and 300 mm below grade23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				.20	Obstructions:	material other
 volumes of 1.5 m3 or more. .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					than class A.	having individual
 .21 Side slope: inclined surface or plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane 					volumes of 1.5	m3 or more.
<pre>plane from subgrade at side limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				.21	Side slope: in	clined surface or
<pre>limit of excavation area to intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>				•	plane from sub	grade at side
<pre>intersect original ground line outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane</pre>					limit of excav	ation area to
outside of side limit and to be expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					intersect orig	inal ground line
expressed as ratio of horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					outside of sid	e limit and to be
horizontal to vertical. .22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					expressed as r	atio of
.22 Sub-grade: plane parallel to and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane					horizontal to	vertical
and 300 mm below grade. .23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane				22	Sub-grade · pla	ne parallel to
.23 Universal Transverse Mercator Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane				•==	and 300 mm bel	ow grade
Projection (UTM) or Modified Transverse Mercator Projection (MTM) Co-ordinates: plane				.23	Universal Tran	sverse Mercator
Transverse Mercator Projection (MTM) Co-ordinates: plane					Projection (IIT	M) or Modified
(MTM) Co-ordinates: plane					Transverse Mer	cator Projection
					(MTM) Co-ordin	ates: plane
rectangular coordinates used in					rectangular co	ordinates used in
arid system in which arid					arid system in	which grid
network is applied to UTM or					network is ann	lied to UTM or
MTM, projection, Horizontal					MTM. projectio	n. Horizontal

DFO	DFO		GING	Section 35 20 23	
P/N C2-00517				Page 4	
Floating Dock Construction					
Pugwash, NS					
			control inform	mation as	
			indicated.		
	.2	Refe	rence Standard	s:	
		.1	Justice Canada	a L'izri	
			.1 Canada Si	nipping Act -	
			c.1416).		
1.2 ADMINISTRATIVE	.1	Co-oi	rdination:		
REQUIREMENTS		.1	Location:		
			.1 Work comp	prises	
			excavating/dr	edging of area in	
			to allow for l	hew lloating docks	
		. 2	Erosion and Se	edimentation	
		• =	Control Plan:	0.11.101100.0101	
			.1 Prepare a	and submit and	
			erosion and se	edimentation	
			control plan	for review in	
			accordance wi	th Section UI 35	
			43-Enivironme Section 1 9	for the	
			containment of	f suspended	
			sediment when	conducting work	
			in water.	2	
	.2	Navio	gation co-ordin	nation:	
		.1	Perform Work :	in accordance with	
			not obstruct r	Regulation during	
			progress of W	ork.	
		.2	Observe vessel	l movements and	
			fishery activ	ities in area	
			affected by early affected by early affected by early affected by a second seco	xcavating	
			operations in	cluding movement	
		2	of vessels at	adjacent wharves.	
		. 3	that will not	interfore with	
			fishing operat	tions. marina	
			operations, co	onstruction	
			activities at	wharf sites, or	
			access to what	rves by land or	
			water.		

0 23
2
_

4 Departmental Representative will not be responsible for loss of time, equipment, material or any other cost related to interference with moored vessels in harbour or due to other Contractor's operations.

- .5 Keep Watchkeeper Operations Centre, District Manager, Canadian Coast Guard (CCG), Fisheries and Oceans, informed of excavation operations in order that necessary Notices to Mariners will be issued.
- .6 Make arrangements with CCG to relocate and replace buoys for execution of work. Advise nearest Coast Guard Base of any requirements to relocate channel markers/buoys within excavation area.
- .7 Arrange operations to minimize interference with recreational boaters using harbour.
- .8 Maintain a minimum 10 m clear width of channel for passage of recreational boaters at all times. Provide and locate necessary buoys to indicate temporary channel for passage.
- .3 Scheduling:
 - .1 Submit to Departmental Representative within 2 weeks after award of Contract, schedule of work including time periods during which each operation involved in Work will be undertaken. At time of submission of schedule, meet with Departmental Representative to review schedule.

DFO	DRED	GING Section 35 20 23
P/N C2-00517		Page 6
Floating Dock Construction		
Pugwash, NS		
	.2	Adhere to schedule and take immediate action to correct any slippage by effectively altering existing excavating operations or mobilizing other equipment. Notify Departmental Representative of corrective action to be taken.
1.3 ACTION AND .1 INFORMATIONAL SUBMITTALS	Subm: Sect: Proce	it in accordance with ion 01 33 00 - Submittal edures.
<u>1.4 QUALITY ASSURANCE</u> .1	Regul appro .1	<pre>latory agency sustainability ovals: Comply with municipal, provincial and national codes and regulations relating to project. Mark floating equipment with lights in accordance Collision Regulations and Notice to Mariners. .1 Maintain VHF marine radio (Channel 16) on board floating equipment.</pre>
.2	Float	ting plant: Dredges or other floating plants to be employed on this Work, to be of Canadian registry, make or manufacture, or, must receive certificate of qualification from Industry Canada, Aerospace, Defence and Marine Branch and this certificate to accompany Tender submission. Requests for certification in format of attached questionnaire to be directed to Director Aerospace, Defense and

Marine Branch, Industry Sector,

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS

> Industry Canada, 235 Queen Street, 7th Floor, East Tower, Ottawa, Ontario, K1A OH5, and to be received there not less than 14 days prior to bid closing.

1.5 SITE CONDITIONS .1 Contractor to visit and inspect work site and become thoroughly familiar with extent and nature of Work and conditions affecting Work before tendering.

- .2 Material to be excavated consists of Class B material.
- .3 Existing borehole information of the upland area is included in Appendix B.
- .4 Results of most recent soundings completed in 2017 are shown on drawings. Data is available for bidding purposes. Data may differ from present site conditions. Take this into consideration when submitting bid.
- .5 Take necessary steps to become fully familiar with potential inclement weather and sea conditions in this area.
- .6 Survey requirements:
 - .1 Provide, at own expense, survey vessel, equipment and crew to set up and maintain control for location of excavation limits and to sound areas immediately after excavating to verify that grade depth has been attained. Areas are to be sounded to provide sounding printout display of at least UTM 5 x 5m grid to approval of Departmental Representative.

DFO		DREDGING	Section 35 20 23
P/N C2-00517			Page 8
Floating Dock Construct	ion		20.90 0
Puowash NS			
rugwash, NS			
1.6 EXCAVATION SEQUENCE	.1	Supply Departmental with plan of excava stages.	Representative ting sequence and
1.7 EXCAVATING PLANT	.1	Excavating plant use mechanical type of capacity and in goo condition to satisf Work within time sc accordance with spe	ed for work to be sufficient d operating actory complete hedule and in cifications.
<u> PART 2 - PRODUCTS</u>			
2.1 EXCAVATING EQUIPMENT	.1	Contractor to detern equipment necessary material specified excavated material containment berm on	mine required to excavate and to dispose of in the adjacent site.
PART 3 - EXECUTION			
3.1 EXAMINATION	.1	Verification of loc. .1 Work comprises excavating/drea areas as indica	ation: dging of ated on drawings
	.2	Surveys and accepta: .1 Contractor to necessary to r material withi areas which is above grade. .2 All elevations minimum mode w areas of excav confirmed to have dredged depth drawings before considered comp	nce of work: re-excavate as emove all n excavation found to be obtained in ithin specified ating must be ave reached the indicated on the e area will be pleted.
3.2 LAYOUT OF WORK	.1	Immediately upon en purpose of beginnin project, locate ref	tering site for g work on this erence points and

take proper action necessary to

prevent their disturbance.

DFO DREDGING Section 35 20 23 P/N C2-00517 Page 9 Floating Dock Construction Pugwash, NS

> .2 Contractor will be responsible to establish horizontal control consisting of a baseline, coordinate system with reference control monuments and vertical control consisting of water level gauge and benchmark to define Work and disposal area.

- .3 Maintain established horizontal and vertical control and lay out work from these established references. Be responsible for accuracy of work relative to established references. Provide and maintain electronic position fixing and distance measuring equipment as required for accurate excavation control. Provide at own expense, survey vessel, equipment and crew to set up and maintain control for location of excavation limits.
- .4 Contractor's electronic positioning system must be made accessible to Departmental Representative or their representative upon request. It must provide a continuous automatic update of position in all weather conditions. Minimum accuracy of positioning to be ±1 metre. An online graphics display of position and hard copy capability is required. Positioning system is subject to Departmental Representative's approval.
- .5 Install and maintain tide boards in vicinity of worksite in order that proper depth of excavation can be determined. Locate tide boards so as to be clearly visible.
- .6 Establish and maintain additional on-land temporary targets, markers and buoys for location and definition of designated excavation

DFO		DREDGING	Section 35 20 23
P/N C2-00517			Page 10
Floating Dock	Construction		2
Pugwash, NS			
		area limits as completion of w	required. Remove on work.
3.3 EXCAVATI	<u>.1</u>	Mark floating e in accordance w Regulations and (Channel 16) ra	equipment with lights with Collision d maintain VHF adio watch on board.
	.2	Place and maint and lights requ areas.	tain buoys, markers uired to define work
	.3	Lay out Work for base lines esta Departmental Re responsible for relative to est and baseline. In electronic post distance measure transits and su normally require excavating cont	rom bench marks and ablished by epresentative. Be r accuracy of Work tablished bench marks Provide and maintain ition fixing and ring equipment, laser uch other equipment as red for accurate trol.
	. 4	Areas to be exercised to the formation of the formation o	cavated are to be vertical bench marks ion of excavation as
	.5	Establish and r in order that p excavation can tide boards so visible.	maintain tide boards proper depth of be determined. Locate as to be clearly
	. 6	Establish and r targets for loc of designated e limits. Targets control of exca locating sound: on completion o	maintain on-land cation and definition excavation area s to be suitable for avating operations and ings. Remove targets of Work.
	.7	Excavate to lir	nits as indicated on

drawings.

DFO P/N C2-00517		DREDGING Section 35 20 23 Page 11
Floating Dock Construc Pugwash, NS	tion	
	.8	Excavation side slopes as noted on drawings.
	.9	Remove materials above specified grade depths, within limits indicated. Material removed from below subgrade depth or outside specified area or side slope is not part of Work. Do not over excavate. Average over excavating not to exceed 0.3 metres.
	.10	Remove spillage or shoaling which occurs as result of Work at no expense to Departmental Representative.
	.11	Remove material cast-over on surrounding area and dispose of it as excavated material. Do not cast- over material unless authorized in writing by Departmental Representative.
	.12	Remove infilling in excavation area which occurs prior to acceptance by Departmental Representative.
	.13	Immediately notify Departmental Representative upon encountering object which might be classified as obstruction. By-pass object after clearly marking its location and continue Work.
3.4 SOUNDING SURVEYS	.1	Contract drawings are based on latest soundings taken in August 2017. Estimated quantity shown on Unit Price Table are based on this survey.
3.5 DISPOSAL OF EXCAVATED MATERIAL	.1	Dispose of excavated material by depositing in the containment berm onsite, as shown on the drawings.

DFO		DREDGING Se	ction 35 20 23
P/N C2-00517		Pa	ge 12
Floating Dock Construct	ion		
Pugwash, NS			
	.2	Deposit excavated mate throughout entire disp not concentrate in one	erial evenly posal site. Do e area.
	.3	Limits of disposal to site prior to start of Restrict disposal act those areas indicated.	be verified on f work. ivities to
	.4	Grade disposal site as	designated.
	.5	Maintain dyke roadways area in a clean manner duration of contract. caused by Contractor's no additional cost. Re to original condition completion of work.	and transfer throughout Repair damages operation at estore surfaces upon
3.6 DISPOSAL OF DEBRIS	.1	Do not dispose of debr lakes or streams.	ris in open
	.2	Dispose of debris at a disposal site.	approved land
3.7 EXCAVATING IN VICINITY OF STRUCTURES	.1	Do not excavate materia areas lying within 2 m existing structure, ex- slope areas, unless of on drawing or unless a writing by Departmenta Representative.	al from basin netres of cluding side therwise shown authorized in al
3.8 SWEEPING AND ACCEPTANCE OF WORK	.1	On completion of excav Contractor will conduct of Departmental Represe mechanical sweep of ex- to confirm that grade achieved. Provide deta system including horization vertical control method days after contract av	vating ct in presence sentative a kcavated areas depth has been ails of sweep zontal and ods within 15 ward.

.2 Sweeping equipment to consist of heavy steel beam suspended from a

DFO		DRED	GING	Section 35 20 23
P/N C2-00517				Page 13
Floating Dock Construc	tion			
Pugwash, NS				
		barge capak calik	e at required ble of adjust pration.	depth. Beam to be ment and
	.3	Provi to De comme of si	de a minimum epartmental R encement of m te.	of 48 hours notice epresentative for echanical sweeping
3.9 RE-EXCAVATING	.1	Re-ex verif sound appro Repre	cavate unsat: Ty depths wit ding or mecha oval of Depar esentative.	isfactory work and h additional nical sweeping to tmental
3.10 SITE QUALIYY CONTROL	.1	Site .1 .2 .3 .4 .5	test and insp Co-operate with Representation Work and pro- requested. Upon request Representation such boats, and material and usual paper plant as may necessary to supervise Wo Provide appro- transport Des Representation Inspectors to dredging site Sweep excavators completion of confirm that been achieved Sweeping equators of heavy stee from scow at depth. Beam adjustment at approved by	pections: ith Departmental ve on inspection of vide assistance of Departmental ve, furnish use of equipment, labour s forming ordinary rt of excavating be reasonably inspect and rk. oved duty boat to partmental ve and PWGSC o and from the e. ted areas on f dredging to grade depth has d. ipment to consist el beam suspended required grade to be capable of nd calibration and Departmental

DFO		DRED	GING	Section 35 20 23
P/N C2-00517				Page 14
Floating Dock	Construction			5
Pugwash NS	001100110001011			
	.2	Non-o.1	conforming w If, as resu Work, addit of depths b sweeping be additional be paid by Re-excavate and verify additional to approval Representat	work: alt of incomplete tional verification by sounding or ecomes necessary, costs involved shall Contractor. e unsatisfactory Work depths with sounding or sweeping l of Departmental tive.
3.11 CLEANING	.1	Progr acco: Clear .1	cess Cleanir dance with ning. Leave Work each day.	ng: clean in Section 01 74 11 - area clean at end of
	.2	Final remove tools with	Cleaning: ve surplus r and equipr Section 01	upon completion materials, rubbish, ment in accordance 74 11 - Cleaning.
		Waste mate: acco: Const Manao .1 .2 .3	e Management cials for re- cdance with cruction/Der gement and H Remove recy bins from s materials a facility. Contaminate disposed of disposal fa Metals, woo materials i excavating diverted ap facilities	2: separate waste ecycling in Section 01 74 21 - molition Waste Disposal. ycling containers and site and dispose of at appropriate ed sediments must be f in confined acility. od and recyclable removed during the activities must be opropriate recycling
Section 35 31 19 DFO REVETMENT P/N C2-00517 Page 1 Floating Dock Construction Puqwash, NS PART 1 - GENERAL Section 01 33 00 - Submittal 1.1 RELATED .1 Procedures. REQUIREMENTS Section 31 32 21 - Geotextiles. .2 American Association of State 1.2 REFERENCES .1 Highway and Transportation Officials (AASHTO) / Standard Specifications for Transportation Materials and Methods of Sampling and Testing, 25th Edition, 2005. AASHTO M 288 latest edition, .1 Geotextile Specification for Highway Applications. .2 American Society for Testing and Materials International (ASTM) .1 ASTM C117 latest edition, Standard Test Method for Material Finer Than 0.075 mm (No. 200) Sieve in Mineral Aggregates by Washing. .2 ASTM C127 latest edition, Standard Test Method for Density, Relative Density (Specific Gravity), and Absorption of Coarse Aggregate. ASTM C535 latest edition, .3 Standard Test Method for Resistance to Degradation of Large Size Coarse Aggregate by Abrasion and Impact in the Los Angeles Machine. .4 ASTM C136 latest edition, Standard Test Method for Sieve Analysis of Fine and Coarse Aggregates. ASTM D698 latest edition, .5 Standard Test Methods for Laboratory Compaction Characteristics of Soil Using

DFO P/N C2-00517 Floating Dock Construct Pugwash, NS	ion	REVETMENT	Section 35 31 19 Page 2
		Standard E: lbf/f3 (600	ffort (12,400 ft- 0kN-m/m3)).
	.3	Canadian General (CGSB) .1 CAN/CGSB-8 Sieves, Tes Inch Series .2 CAN/CGSB-8 Sieves, Tes Metric.	l Standards Board .1 latest edition, sting, Woven Wire, s. .2 latest edition, sting, Woven Wire,
1.3 DELIVERY, STORAGE AND HANDLING	.1	Deliver, store a in accordance wi - Common Product	and handle materials ith Section 01 61 00 t Requirements.
	.2	Replace defective materials with r	ve or damaged new.
PART 2 - PRODUCTS			
2.1 MATERIALS	.1	No new materials this project. The to salvage and mexisting armour facilitate instance	s are required for his section applies reinstatement of the stone material to allation of the new ing wall.
PART 3 - EXECUTION			
3.1 CONSTRUCTION	.1	The Contractor s reinstate armoun system as indica Contract Documen	shall remove and r stone protection ated in the nts.

.2 The Contractor shall verify the existing grades and shall notify the Departmental Representative if reshaping is required.

DFO P/N C2-00 Floating Pugwash,)517 Dock NS	Construction	REVE	TMENT	Section 35 31 19 Page 3
		.3	The grad mate Area debr obje of t .1	Contractor shal es and Slopes o rial to ensure is cleared of is, snow, ice a ctionable mater he Work. The armour sto shall be place with the const retaining wall retaining wall protected as s placement as p	<pre>l maintain the f the underlying that the Work all driftwood, nd all other ials in the area ne protection d in conjunction ruction of the , so that the is fully oon after ractical.</pre>
		.4	Cont visu .1	rol of the grad al examination. Any difference between the De Representative Contractor sha testing in acc D5519. The Contractor the Equipment, and the labour undertake the	ation shall be by in opinion partment and the ll be resolved by ordance with ASTM shall provide a sorting site required to testing required.
		.5	The armo the abut .1	Contractor shal ur stone protec underlying mate ting Structures The Contractor responsible at expense to rep damage to the	l place the tion such that rials and any are not damaged. shall be his/her own air any such Work.
		. 6	The for to r of w weat	Contractor shal any Work or mat epair damage wh ater level vari her conditions.	l be responsible erials required ich is a result ations, waves or

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	REVETMENT	Section 35 31 19 Page 4
3.2 ARMOUR STONE .1	Place armour stone and dimensions as :	to lines, grades indicated.
.2	Reinstate armour st courses to total la matching existing o	tone in two ayer thickness conditions.
.3	Armour stone protect placed such that easily stable, secure and rocks below and the be controlled to easily uniform and continu- results. .1 The Contractor that during plarger rocks as throughout the stone protects .2 The Contractor individual roc manner that the shall be bound to as great an nature of the	ction shall be ach rock is supported by e placement shall nsure that a uous cover r shall ensure lacement the shall be dispersed e entire armour ion mass. r shall place the ck in such a ne whole structure d and consolidated n extent as the rock will allow.
.4	No pushing or dump stone protection s during placement.	ing of armour hall be permitted
.5	Any remaining armound not required at the retaining wall is site as directed by Representative.	ar stone material e new concrete to be salvaged on y the Departmental
<u>3.4 TOLERANCES</u> .1	Completed component within following to and grades as indic .1 Armour: plus o	t layer to be olerances of lines cated: or minus 100 mm.

DFO P/N C2-00517 Floating Dock Construction Pugwash, NS	REVETMENT Section 35 31 19 Page 5
<u>3.5 CLEANING</u> .1	Progress Cleaning: clean in accordance with Section 01 74 11 - Cleaning. .1 Leave Work area clean at end of each day.
.2	Final Cleaning: upon completion remove surplus materials, rubbish, tools and equipment in accordance with Section 01 74 11 - Cleaning.