Fisheries and Oceans Canada Section 00 01 10

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

List of Contents

Page 1

Section No.	Title	Pages
Division 00	Procurement and Contracting Requirements	
00 01 10	List of Contents	1
00 21 10	List of Drawings	1
Division 01	General Requirements	
01 10 10	General Instructions	10
01 15 50	Weigh Scales	2
01 29 00	Project Particulars and Measurement for Payment	2
01 33 00	Submittal Procedures	5
01 35 30	Health and Safety Requirements	16
01 35 44	Environmental Protection Procedures for Marine	
	Work	18
01 45 00	Testing Laboratory Services	2
01 51 00	Temporary Facilities	3
01 61 00	Material and Equipment	3
01 71 00	Project Record Documents	1
01 74 00	Cleaning	1
Division 31	Earthworks	
31 11 00	Sitework, Demolition and Removals	3
31 23 10	Excavating, Trenching and Backfilling	4
31 32 21	Geotextiles	3
Division 35	Waterway and Marine Construction	
35 31 24.1	Containment Cell	9

Fisheries and Oceans Canada Section 00 21 00 Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

List of Drawings

Page 1

### List of Drawings

Drawing No.	Title
	Cover
M1	Existing Conditions and Removals
M2	Plan and Sections

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### General Instructions

Page 1

#### 1.1 Scope

.1 The work covered under this contract consists of the furnishing of all plant, labour, equipment and material for Containment Cell Construction at Little Judique Ponds, Inverness County, Nova Scotia, in strict accordance with specifications and accompanying drawings and subject to all terms and conditions of contract.

#### 1.2 Site Examination

- .1 All parties tendering should visit the site of the work prior to submission of tenders and make themselves thoroughly acquainted with site conditions, conditions of existing objects to be removed, tides, degree of exposure and all information necessary for the proper carrying out of the work covered by the drawings and this Specification.

  Submission of Tender will be deemed that Contractor is conversant with site conditions.
- .2 The Departmental Representative will give no consideration whatsoever to any claim by the Contractor resulting from failure to have made all the necessary investigations prior to tendering.

#### 1.3 Documents Required

- .1 Maintain at job site, one copy each of following:
  - .1 Contract drawings;
  - .2 Specifications;
  - .3 Addenda;
  - .4 Reviewed shop drawings/submissions;
  - .5 Change orders;
  - .6 Other modifications to Contract;
  - .7 Field test reports;
  - .8 Copy of approved work schedule;
  - .9 Manufacturer's installation and application instructions; and
  - .10 Permits and orders

## 1.4 Work Schedule and Completion Dates

.1 Prepare and submit to the *Departmental Representative* within five (5) days of notification of Contract award, one copy

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

General Instructions

Page 2

of the construction schedule in the form of a bar chart showing the dates for commencement and completion of each major activity of the work, including the work of subcontractors; dates for submissions, review and return of shop drawings, etc.; the dates of Substantial and Final Completion. If the schedule as submitted is unacceptable in any way, submit without delay a revised schedule satisfactory to the Departmental Representative.

- .2 The Departmental Representative will notify the Contractor in writing of acceptance of the Construction Schedule. Comply with the Construction Schedule at all times. If, for any reason, the Construction Schedule is not followed, immediately notify the Departmental Representative of the change and submit a revised schedule for acceptance. Upon acceptance by the Departmental Representative, this schedule will become the Construction Schedule.
- .3 Whenever required, give further written particulars concerning this Schedule. The submission to and acceptance by the Departmental Representative of the Contractor's Construction Schedule or the furnishing of details and particulars thereto will not relieve the Contractor of any duties and responsibilities under the Contract.
- .4 The work sequence must include the concurrent construction of the new containment cell along with the demolition, removal, sorting and stockpiling of armour stone and filter stone as the construction progresses.
- .5 Schedule shall take into account the possibility of Nova Scotia Department of and Public Works annual spring weight restrictions on local roads.

Section 01 10 10 Fisheries and Oceans Canada Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155		General Instructions Page 3		
1.5	Measurement Responsibilities	.1	Notify Departmental Representations sufficiently in advance of oper permit required measurements for purposes.	rations to
1.6	Contractor's Use of Site	.1	The Contractor will not be persuse the existing wharf structus harbour for loading or offload construction equipment.	res at the
		.2	Co-operate with users of exist facilities. Should interference take directions from Department Representative.	es occur,
		.3	Do not unreasonably encumber someterials or equipment.	ite with
		. 4	Move stored products or equipmed interfere with operations of De Representative or other Contractions	epartmental
		.5	Obtain and pay for use of addit storage or work areas needed for operations.	
		.6	Comply with all regulations and authorities having jurisdiction work, whether on land or on wat	n over the
		.7	Ensure no damage occurs to exist structures as a result of operation of damage will be repaired at Contractor's expense.	ations. Any
		.8	Provide temporary barriers and signs in location where work is to areas used by public.	_
1.7	Codes and Standards	.1	Perform work in accordance with Building Code of Canada (NBC) a other code of provincial or locapplication provided that in an conflict or discrepancy, the model of the conflict or discrepancy.	and any cal ny case of

stringent requirements will apply.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### General Instructions

Page 4

- .2 Meet or exceed requirements of specified standards, codes and referenced documents. When a standard or code is outdated, the latest edition will supersede the referenced date.
- .3 Observe and enforce construction safety measures by Canadian Construction Safety Code and Construction Safety Code of Nova Scotia. In the event of conflict between any provisions of above authorities the most stringent provision will apply.

#### 1.8 Project Meetings

.1 Departmental Representative will arrange project meetings and assume responsibility for setting times and recording and distributing minutes.

#### 1.9 Setting Out of Work

- .1 Do all detail surveys necessary for the work, including locating and maintaining working points, and establishing lines and elevations. Perform all layout work, and carefully preserve benchmarks, reference points and stakes.
- .2 Provide such masts, scaffolds, batter boards, lines, straight edges, templates and other devices as may be necessary to facilitate layout, construction and inspection of the work. Whenever necessary, suspend work for such reasonable time as may be necessary to permit the Departmental Representative to check or inspect any portion of the Work. The Contractor will not be allowed any extra compensation or time for completion because of this suspension of work.
- .3 Elevations for the various grades and features of the specified works to be referenced and properly related to a benchmark, which will be approved by the Departmental Representative.
- .4 Verify all grades, lines, levels, and dimensions shown on the drawings and report any errors or inconsistencies to

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### General Instructions

Page 5

the Departmental Representative before commencing work. Establish all other grades, lines, levels required to facilitate the work.

#### 1.10 Existing Services

- .1 Where work involves breaking into or connecting to existing services, carry out work at times directed by governing authorities, with minimum of disturbance to pedestrian and vehicular traffic.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify *Departmental*\*Representative of findings.
- .3 Submit schedule to and obtain acceptance from *Departmental Representative* for any shut-down or closure of active service or facility. Adhere to approved schedule and provide notice to affected parties.
- .4 Where unknown services are encountered, immediately advise *Departmental*\*Representative and confirm findings in writing.

#### 1.11 Contract Documents

- .1 Contract Drawings:
  - .1 The drawings for the Work consist of all drawings listed in these "Plans And Specifications" and any additional drawings issued at a later date by the Departmental Representative.
  - .2 Departmental Representative may furnish additional drawings to assist in proper execution of work. These drawings will be issued for clarification only. Such drawings will have same meaning and intent as if they were included with plans referred to in Contract Documents.
  - .3 The drawings indicate the extent and general dimensions of the work. Make all necessary measurements to ensure that the result of the work is in

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

General Instructions

Page 6

- accordance with the intent.
- .4 Verify all existing conditions in field prior to proceeding with work.
- .2 Contract Specifications:
  - .1 The general requirements and technical specifications are written solely for the General Contractor. They are organized into the NMS format of separate divisions and sections.
  - .2 Specification language is of the 'Short Form type' for example, where the word "provide" occurs, interpret it to mean "the Contractor shall furnish all labour, material and equipment necessary to complete the work".
  - . 3 This Specification and accompanying drawings are intended to describe and provide for a finished project. They are intended to be complementary, and what is called for by either will be as binding as if called for by both. The Contractor shall understand that the work herein described will be complete in every detail, notwithstanding that every item necessarily involved is not particularly mentioned, and Contractor will be held to provide all labour, materials and equipment necessary for the entire completion of the work and will not avail himself of any errors or omissions.

1.12 Permits and Regulations

- .1 Fisheries and Oceans Canada will obtain all federal and provincial permits required for the in-water works associated with the new works.
- .2 Comply with all by-laws, ordinances and regulations of all authorities having jurisdiction.
- .3 Pay for any Municipal or other permits

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

~ 7	- · · · · ·
General	Instructions
Generar	TIID CT UC CTOIID

Page 7

required including any other permits required for construction methodology that is outside the limits of the new works.

.4 Submit to Departmental Representative, copy of application submissions and approval documents received for above authorities having jurisdiction.

1.13 Payment

- .1 Payment for all work under this contract to be according to the Contract.
- .2 No separate payment will be made for work specified under this section. The cost of this work is to be considered as overhead and to be included in the unit prices of the Contract.
- .3 Dimensional changes as directed by the Departmental Representative to suit existing conditions, but not resulting in additional work or materials, will not be considered as extra to the Contract.
- 1.14 Maintenance of Shipping
- .1 Liaise with the local Harbour Authority officials to coordinate activities such that any interference is minimized.
- 1.15 Cooperation &
  Assistance to
  Departmental
  Representative
- .1 Co-operate with *Departmental Representative* on inspection of work and provide assistance when requested.
- .2 Provide small motor boat with operator for Departmental Representative's use when requested.

1.16 Datum

.1 The datum referred to in this project is Chart Datum. Chart Datum is, by International Agreement, is a plane below which the tide will seldom fall. The Canadian Hydrographic Service (CHS) has adopted the plane of the lowest normal tide (L.N.T.) as Chart Datum. As the rise, fall, and range of tides varies daily, the Canadian Tide and Current Tables, as issued by the CHS, should be consulted for

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### General Instructions

Page 8

tidal predictions and other tidal information relating to the work.

- .2 Refer to drawings for existing benchmark information.
- 1.17 Contractor's Representative
- .1 Continuously maintain on the site an authorized company representative to whom communication may be addressed and who will be competent to speak for the Contractor in discussing work methods and other matters.
- 1.18 Workers
  Compensation
- .1 Contractor and all sub-contractors must be registered under the Workers Compensation Act and provide evidence of good standing.
- .2 At completion of Contract and before final payment is made, the Contractor will present to the Departmental Representative a Letter of Certification from the Workers' Compensation Board of Nova Scotia, showing that all required assessments are paid in connection with all trades.
- 1.19 Laws, Standards
  Taxes and Fees
- comply with all laws and standards governing all or any part of the work. Pay all applicable taxes and pay for all permits and certificates required in respect of the execution of the work, except those permits obtained by Fisheries and Oceans Canada. Where variances exist between the requirements of agencies governing all or any part of the work, the most restrictive will govern, but in no instance will the standards established by the drawings and this Specification, which exceed such requirements, be reduced.
- 1.20 Protection and Repair
- .1 Take appropriate measures to protect exiting infrastructure and services.
- .2 Do not operate tracked equipment on concrete or paved surfaces without suitable protection.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

. 3

Project No.: C2-00155

#### General Instructions

Page 9

- 1.21 Location of Equipment and Fixtures
- operations under this contract.

  1 Location of equipment, fixtures or any

Repair any damage resulting from

- appurtenances indicated are to be considered approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.
- .3 Submit field drawings to indicate relative position of various services and equipment when required by *Departmental*\*Representative.
- .4 Exact locations of mooring cleats and ladders shall be coordinated and confirmed with the Harbour Authority prior to commencing work related to cleats and ladder installation.
- 1.22 Notice to Shipping / Mariners
- .1 Notify the Marine Communications and Traffic Services' Centre, of Fisheries and Oceans Canada, at (709) 772-2083, ten (10) days prior to commencement and upon completion of the work, in order to allow for the issuance of Notices to Shipping/Mariners.
- .2 During construction any vessels or barges utilized must be marked in accordance with the provisions of the Canada Shipping Act Collision Regulations.
- .3 Material from the work shall not be permitted to go adrift or otherwise become a hazard or menace to navigation.
- 1.23 Inspection and Testing
- .1 The Departmental Representative may employ an Inspector and/or Testing Company to ensure work conforms with contract.

Fisheries and Oceans Canada
Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.
Project No.: C2-00155

Section 01 10 10

Page 10

## 1.24 Relics and Antiquities

.1 Protect relics, antiquities, items of historical or scientific interest such as cornerstones and contents, commemorative plaques, inscribed tablets, and similar objects found during course of work.

General Instructions

- .2 Give immediate notice to Departmental Representative and await written instructions before proceeding with work in this area.
- .3 Relics, antiquities and items of historical or scientific interest remain His Majesty's property.
- 1.25 Temporary
  Navigational
  Buoys
- .1 Maintain temporary buoys as required to mark any obstructions as construction proceeds.
- .2 The part of the buoy that shows above the surface of the water to be at least 15.25 cm wide and at least 30.5 cm high and equipped with radar reflectors.
- .3 Buoys, including buoy anchors, to be constructed and maintained in a manner and with materials that will ensure that they will remain in position after the buoys have been anchored.
- .4 Buoys to comply with the requirements set out in the section entitled "Floating Aids to Navigation (Buoys)" of TP 968, entitled Canadian Aids to Navigation System and published by the Canadian Coast Guard, as amended from time to time.
- .5 Coordinate the buoy installation with the local Harbour Authority.
- .6 Pay all costs associated with the supply, installation, maintenance and removal of temporary navigational buoys.

Fisheries and Oceans Canada

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Proj	ect No.: C2-00155		Weigh Carles	a ara 1
			Weigh Scales Pa	age 1
1.1	Requirements of Regulatory Agencies	.1	Prior to use, have weigh scales certi as meeting requirements of Statutes o Canada, Chapter 36, Weights and Measu Act, 1971 and subsequent amendments. Display certificate in a prominent position. No payment will be made fo materials weighed on non-certified sc	of ires or
1.2	<u>Equipment</u>	.1	Weigh Scales: of sufficient capacity weigh loaded vehicles in a single operation.	to
		.2	Scale House: .1 To enclose mass indicator and in which Departmental Representative representative can perform work maintain records.	re's
			.2 To be weatherproof and have minimum 750 lx of illumination, one slid window facing scale platform, on other window for cross ventilationshelf desk at least 0.6 x 1.8 m, heat to maintain inside temperat at 20°C. Entrance door not to fa onto scale platform.	ling e on, and ure
			.3 Provide sufficient number of app weigh tickets, in triplicate, wi consecutive serial numbers.	
1.3	<u>Installation</u>	.1	Provide, install and maintain scales scale house convenient to project sit location approved by Departmental Representative.	
		.2	Certified weigh scales at the quarry be acceptable in lieu of on-site weig scales.	
		.3	Ramps to be level for one truck lengt each side of scale.	h

.4 Remove ramps scales and scale house when

no longer required on site.

Fisheries and Oceans Canada Containment Cell Construction			Section 01 15 50
Little Judique Ponds, Inverness Project No.: C2-00155			County, N.S.
			Weigh Scales Page 2
1.4 <u>Op</u>	eration_	.1	Departmental Representative's representative at scales will weigh materials.
1.5 <u>Ma</u>	<u>intenance</u>	.1	Maintain scale platform and scale mechanism clean and free from gravel, asphalt, snow, ice and debris.
		.2	Maintain approach ramps in good condition free from sags and ruts.
		.3	Have scales retested and recertified if requested by Departmental Representative.
	asurement for yment	.1	Weigh scales will be measured in accordance with Section 01 29 00.
		EN	D of SECTION

Fisheries and Oceans Canada Section 01 29 00

Containment Cell Construction

Little Judique Ponds, Inverness County, NS

Project No.: C2-00155 Project Particulars and
Measurement for Payment Page 1

#### PART 1 - PROJECT PARTICULARS

#### 1.1 Description of Work

- .1 In general, the work under this contract includes but will not necessarily be limited to:
  - .1 Mobilization, demobilization and weigh scales.
  - .2 Sitework, demolition, removal, salvage, sorting, stockpiling and reinstallation of existing armourstone, filterstone to the lines and grades indicated.
  - .3 Carry out underwater excavation to accommodate new filterstone and armourstone installation.
  - .4 Load, supply, and installation of approved core stone to the lines and grades indicated.
  - .5 Supply and installation of geotextile (filter fabric).
  - .6 Load, supply and placement filter stone to the lines and grades indicated.
  - .7 Load, supply, and placement of armourstone to the lines and grades indicated.

#### Part 2 - PROJECT MEASUREMENT

#### 2.1 General

.1 This section details the measurement method to be used for payment purposes. Incidental items covered in the various sections of the Specification are to be included in the pricing of each pay item as applicable.

# 2.2 Measurement for <a href="Payment">Payment</a>

#### Division 01

.1 Mobilization and demobilization to the site will not be measured but paid Lump Sum. Include in this item, the cost to deliver materials and equipment to the site to carry out the work. Weigh scales to be included in this item.

Project No.: C2-00155

Project Particulars and
Measurement for Payment

Page 2

#### Division 31

- .2 Sitework, demolition and removals will not be measured but paid Lump Sum. Include into this item, the removal, sorting and stock piling of existing armourstone and filterstone. Also include incorporating the suitable materials into the new Work to the lines and grades indicated.
- .3 Include in this item underwater excavation and disposal in on-site containment area.

#### Division 35

- Load, supply and placement of approved core stone to lines, grades and elevations indicated on the plans will be measured per tonne incorporated into the work.
- .5 Supply and installation of geotextile (filter fabric) to areas indicated on the construction drawings will not be measured but paid Lump Sum.
- .6 Load, supply and placement of filterstone to lines and grades indicated will be measured per tonne incorporated into the work.
- .7 Load, supply and placement of armourstone to lines and grades indicated will be measured per tonne incorporated into the work.

-----END of SECTION----------

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### Submittal Procedures

Page 1

#### 1.1 General

- .1 Submit to Departmental Representative for review submittals listed, including shop drawings, samples, certificates and other data, as specified in other sections of these Specifications.
- .2 Submit with promptness and in orderly sequence so as to allow for *Departmental Representative's* review and not cause delay in Work. Failure to submit in ample time will not be considered sufficient reason for an extension of Contract time and no claim for extension by reason of such default will be allowed.
- .3 Do not proceed with work until relevant submissions are reviewed by *Departmental Representative*.
- .4 Present shop drawings, product data, samples and mock-ups in SI Metric units. Where items or information is not produced in SI Metric units, provide converted values.
- .5 Review submittals prior to submission to Departmental Representative. Ensure during review that necessary requirements have been determined and verified, required field measurements or data have been taken, and that each submittal has been checked and coordinated with requirements of Work and Contract Documents.
  - .1 Submittals not stamped, signed, dated and identified as to specific project will be returned unexamined by Departmental Representative and considered rejected.
- .6 Notify Departmental Representative, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.
- .7 Verify field measurements and affected adjacent work and coordinate.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

#### Submittal Procedures

Page 2

- .8 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submittals.
- .9 Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Departmental Representative's review.
- .10 Submittal format: PDF format by email or hardcopy paper originals (alternatively clear and fully legible photocopies of originals). Facsimiles are not acceptable, except in special circumstances preapproved by Departmental Representative. Poorly printed non-legible photocopies or facsimiles will not be accepted.
- .11 Make changes or revision to submissions which Departmental Representative may require, consistent with Contract Documents and resubmit as directed by Departmental Representative. When resubmitting, notify Departmental Representative in writing of any revisions other than those requested.
- .12 Keep one reviewed copy of each submittal document on site for duration of Work.

#### 1.2 Shop Drawings

- .1 Drawings to be originals prepared by Contractor, Subcontractor, Supplier or Distributor, which illustrate appropriate portion of work; showing fabrication, layout, setting or erection details as specified in appropriate Sections.
- .2 Identify details by reference to sheet and detail numbers shown on Contract Drawings.
- .3 Maximum sheet size 860 X 1120 mm.

#### 1.3 Product Data

.1 Certain Specification Sections specify that manufacturer's standard schematic drawings, catalogue sheets, diagrams schedules, performance charts,

Fisheries and Oceans Canada Section 01 33 00 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Page 3

illustrations and other standard descriptive data will be accepted in lieu of shop drawings.

#### 1.4 Samples

- .1 Submit samples in sizes and quantities specified.
- .2 Construct field samples and mock-ups at locations acceptable to *Departmental Representative*.
- .3 Accepted samples will become standards of workmanship and material against which, installed work will be checked on project.

#### 1.5 Miscellaneous Data

.1 Provide certificates, methodologies, designs and test results as required.

# 1.6 Coordination of Submissions

- .1 Review shop drawings, product data, samples and miscellaneous data prior to submission.
- .2 Verify:
  - .1 Field measurements;
  - .2 Field construction criteria; and
  - .3 Catalogue numbers and similar data.
- .3 Coordinate each submission with requirements of work and Contract documents. Individual submissions will not be reviewed until all related information is available.
- .4 Contractor's responsibility for errors and omissions in submission is not relieved by Departmental Representative's review of submissions.
- .5 Contractor's responsibility for deviations in submission from requirements in Contract documents is not relieved by Departmental Representative's review of submission, unless Departmental Representative gives written acceptance of specified deviations.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Submittal Procedures

Page 4

- .6 Notify Departmental Representative, in writing at time of submission, of deviations from requirements of Contract documents stating reasons for deviations.
- .7 After Departmental Representative's review, distribute copies.
- 1.7 Submission Requirements
- .1 Schedule submissions at least fourteen (14) days before dates reviewed submissions will be needed.
- .2 Submit number of copies of shop drawings, product data which Contractor requires for distribution, plus 2 copies which will be retained by Departmental Representative.
- .3 Accompany submissions with transmittal letter, in duplicate, containing:
  - .1 Date.
  - .2 Project title and number.
  - .3 Contractor's name and address.
  - .4 Identification and quantity of each shop drawing, product data and sample submitted.
  - .5 Other pertinent data.
- .4 Submissions shall include:
  - .1 Date and revision dates.
  - .2 Project title and number.
  - .3 Name and address of:
    - .1 Contractor
    - .2 Sub-Contractor
    - .3 Supplier
    - .4 Manufacturer
    - .5 Separate detailer when pertinent
  - .4 Identification of product or material.
  - .5 Relation to adjacent structure or materials.
  - .6 Field dimensions, clearly identified as such.
  - .7 Specification Section Number.
  - .8 Applicable standards, such as ASTM, CSA or CGSB numbers.
  - .9 A Contractor's stamp, initialled or signed, certifying review of

Fisheries and Oceans Canada Section 01 33 00 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Submittal Procedures

Page 5

submission, verification of field measurements and compliance with Contract documents.

## 1.8 Shop Drawings Review

. 1 The review of shop drawings by Fisheries and Oceans Canada or its authorized consultant is for the sole purpose of ascertaining conformance with the general concept. This review shall not mean that Fisheries and Oceans Canada approves the detail design inherent in the shop drawings, responsibility for which shall remain with the Contractor submitting same, and such review shall not relieve the Contractor of responsibility for errors or omissions in the shop drawings or of responsibility for meeting all requirements of the construction and contract documents. Without restricting the generality of the foregoing, the Contractor is responsible for dimensions to be confirmed and correlated at the work site, for information that pertains solely to fabrication processes or to techniques of construction and installation and for coordination of the work of all subtrades.

#### 1.9 Other Reviews

.1 As for shop drawings above, other reviews are for the sole purpose of ascertaining conformance with the general concept.

-----END of SECTION------

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Health and Safety Requirements Page 1 1.1 Related Work . 1 Refer to other Specification sections for related information. COSH: Canada Occupational Health and 1.2 Definitions . 1 Safety Regulations made under Part II of the Canada Labour Code. .2 Competent Person: means a person who is: Qualified by virtue of personal knowledge, training and experience to perform assigned work in a manner that will ensure the health and safety of persons in the workplace, . 2 Knowledgeable about the provisions of occupational health and safety statutes and regulations that apply to the Work and; Knowledgeable about potential or .3 actual danger to health or safety associated with the Work. Medical Aid Injury: any minor injury for . 3 which medical treatment was provided and the cost of which is covered by Workers' Compensation Board of the province in which the injury was incurred. PPE: Personal Protective Equipment . 4 Work Site: where used in this section . 5 shall mean areas, located at the premises where Work is undertaken, used by Contractor to perform all of the activities associated with the performance of the Work. 1.3 Submittals Submit site-specific Health and Safety . 1 Plan prior to commencement of Work. Submit within five (5) workdays of notification of Bid Acceptance. Provide 2 copies. .2 Departmental Representative will review Health and Safety Plan and provide comments. .3 Revise the Plan as appropriate and

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 2

- resubmit within five (5) workdays after receipt of comments.
- .4 Departmental Representative's review and comments made of the Plan shall not be construed as an endorsement, approval or implied warranty of any kind by Canada and does not reduce Contractor's overall responsibility for Occupational Health and Safety of the Work.
- .5 Submit revisions and updates made to the Plan during the course of Work.
- .2 Submit name of designated Health and Safety Site Representative and support documentation specified in the Safety Plan.
- .3 Submit compliance certificates and other permits obtained.
- .4 Submit copy of Letter in Good Standing from Provincial Workers Compensation Board.
  - .1 Submit update of Letter of Good Standing whenever expiration date occurs during the period of Work.
- .5 Submit copies of reports or directions issued by federal, provincial and territorial health and safety inspectors.
- .6 Submit copies of incident reports.
- .7 Submit WHMIS MSDS Material Safety Data Sheets.
- .8 Provide submittals in accordance with Section 01 33 00 Submittal Procedures.

- 1.4 Compliance Requirements
- .1 Comply with Occupational Health and Safety Act for Province of Nova Scotia, and Regulations made pursuant to the Act.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 3

- . 2 Comply with Canada Labour Code - Part II (entitled Occupational Health and Safety) and the Canada Occupational Health and Safety Regulations (COSH) as well as any other regulations made pursuant.
- Treasury Board of Canada Secretariat .3 (TBS):
  - .1 Directive on the Management of Real Property (2021).
- Canadian Standards Association (CSA): . 4
  - CSA S350-M1980 (R2003), Code of Practice for Safety in Demolition of Structures.
- . 5 Observe construction safety measures of:
  - Part 8 of National Building Code
  - Municipal by-laws and ordinances.
- . 6 In case of conflict or discrepancy between above specified requirements, the more stringent shall apply.
- . 7 Maintain Workers Compensation Coverage in good standing for duration of Contract. Provide proof of clearance through submission of Letter in Good Standing.
- . 8 Medical Surveillance: Where prescribed by legislation or regulation, obtain and maintain worker medical surveillance documentation.
- 1.5 Responsibility
- Contractor shall be responsible for health . 1 and safety of persons and safety of property on site and for protection of other employees and general public circulating adjacent to work operations to extent that they may be affected by conduct of Work.
- . 2 Comply with and enforce compliance by all workers, sub-contractors and other persons granted access to Work Site with safety requirements of Contract Documents,

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 4

applicable federal, provincial, and local by-laws, regulations, and ordinances, and with site-specific Health and Safety Plan.

## 1.6 Site Control and Access

- .1 The harbour and facility shall have ongoing operations during construction including:
  - .1 Vessel traffic navigating and berthed to harbour facilities within the harbour basin.
  - .2 Regular vehicle traffic on the access road, wharf and service area.
- .2 Control the Work and entry points to Work Site. Approve and grant access only to workers and authorized persons.

  Immediately stop and remove non-authorized persons.
  - .1 Departmental Representative will provide names of those persons authorized by Departmental Representative to enter onto Work Site and will ensure that such authorized persons have the required knowledge and training on Health and Safety pertinent to their reason for being at the site, however, Contractor remains responsible for the health and safety of authorized persons while at the Work Site.
- .3 Isolate Work Site from other areas of the premises by use of appropriate means.
  - and temporary lighting as required to effectively delineate the Work Site, stop non-authorized entry, and to protect pedestrians and vehicular traffic around and adjacent to the Work and create a safe environment.
  - .2 Post signage at entry points and other strategic locations indicating restricted access and conditions for access.
  - .3 Use professionally made signs with bilingual message in the 2 official

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 5

languages or international known graphic symbols.

- .4 Provide safety orientation session to persons granted access to Work Site.
  Advise of hazards and safety rules to be observed while on site.
- .5 Ensure persons granted site access wear appropriate PPE. Supply PPE to inspection authorities who require access to conduct tests or perform inspections.
- .6 Secure Work Site against entry when inactive or unoccupied and to protect persons against harm.

#### 1.7 Protection

- .1 Carry out work placing emphasis on health and safety of public, wharf users, site personnel and protection of the environment.
- .2 Give precedence to safety and health of persons and protection of environment over cost and schedule considerations for Work.
- .3 Provide temporary facilities for protection and safe passage of wharf users, public pedestrians and vehicular traffic around and adjacent to work site.
- .4 Should unforeseen or peculiar safetyrelated hazard or condition become evident
  during performance of Work, immediately
  take measures to rectify situation and
  prevent damage or harm. Advise

  Departmental Representative verbally and
  in writing.

#### 1.8 Filing of Notice

- .1 File Notice of Project with pertinent provincial health and safety authorities prior to beginning of Work.
- .2 Upon request, Departmental Representative will provide name and mailing address of provincial department to whom the Notice

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 6

of Project must be sent.

#### 1.9 Permits

- .1 Obtain applicable permits, licenses and compliance certificates at appropriate times and frequency as stipulated by Authorities having jurisdiction.
- .2 Post permits, licenses and compliance certificates at Work Site.
- .3 Where a particular permit or compliance certificate cannot be obtained, notify Departmental Representative in writing and obtain approval to proceed before carrying out applicable portion of work.

#### 1.10 Hazard Assessments

- .1 Perform site-specific health and safety hazard assessment of the Work and its site.
- .2 Carry out initial assessment prior to start of Work with further assessments as needed during progress of Work.
- .3 On-going hazard assessments performed during the progress of work identifying new or potential health risks and safety hazards not previously known. At a minimum, hazard assessments shall be carried out when:
  - .1 New sub-trade work, new subcontractor(s) or new workers arrive at the site to commence another portion of the work.
  - .2 The scope of work has been changed by Change Order.
  - .3 Potential hazard or weakness in current health and safety practices are identified by *Departmental Representative* or by an authorized safety representative.
- .4 Hazard assessments to be project and site specific and based on review of the Contract Documents, site conditions and weather conditions. Record results and

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Health and Safety Requirements Page 7 address in Health and Safety Plan.

- . 5 Each hazard assessment shall be made in writing. Keep documentation on site for entire duration of the Work.
- 1.11 Project/Site Conditions
- . 1 Harbour on-gong operations during construction
  - . 1 The work of this contract will take place at a commercial fishing harbor with ongoing operations from users at adjacent facilities.
- . 2 The following are known or potential project-related safety hazards at site:
  - Overhead and underground electrical lines;
  - Working over water; . 2
  - .3 Working under water;
  - .4 Vehicle traffic;
  - . 5 Pedestrian traffic;
  - .6 Vessel traffic;
  - .7 Slip and fall hazards;
  - . 8 Debris;
  - .9 Noise;
  - .10 Adverse weather;
  - Heavy equipment operation and .11 stability
- Include above items in the hazard . 3 assessment of the Work Site.
- . 4 There are no known hazardous or controlled products stored on site.
- Above items shall not be construed as . 5 being complete and inclusive of potential health and safety hazards encountered as a result of Contractor's operations.

1.12 Meetings

- Attend pre-construction health and safety . 1 meeting, convened and chaired by Departmental Representative, prior to commencement of Work, at time, date and location determined by Departmental Representative. Ensure attendance of:
  - Superintendent of Work

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 8

- .2 Designated Health & Safety Site Representative
- .3 Subcontractors
- .2 Provide site safety orientation session to all workers and other authorized persons prior to granting them access to work site. Brief persons on site conditions and on the minimum site safety rules in force at site.
- .3 Conduct regularly scheduled toolbox and safety meetings during the Work in conformance with Occupational Health and Safety regulations.
- .4 Keep workers informed of anticipated hazards, on safety practices and procedures to be followed and of other pertinent safety information related to:
  - .1 Progress of Work.
  - .2 New sub-trades arriving on site.
  - .3 Changes in site and project conditions.
- .5 Keep documents on site.
- 1.13 Health and Safety Plan
- .1 Develop written Health and Safety Plan specific to the Work. Implement, maintain, and enforce Plan for entire duration of Work and until final demobilization from site.
- .2 Health and Safety Plan shall include the following components:
  - .1 **Part 1:** List of individual health risks and safety hazards identified by hazard assessment(s).
  - .2 Part 2: List of specific measures to control or mitigate each hazard and risk identified in Part 1 of Plan. Describe the engineering controls, safe job procedures, and safe work practices and personal protective equipment to be implemented and followed when

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 9

performing work related to each identified hazard or risk.

.3 Part 3: - Emergency Measures and Communication Plan and Procedures as follows:

Emergency Measures:

- .1 On site operational procedures, evacuation measures and emergency response to be implemented in the event of an occurrence of an accident or incident.
- .2 Evacuation Plan: site plan layouts showing escape routes, marshalling areas and muster stations. Details on alarm notification methods, fire drills, location of fire-fighting equipment and other related data. Harmonize Plan with facility's Emergency Response and Evacuation Plan. Departmental Representative will provide pertinent data including facility management contacts.

Communication Plan and Procedures

- .1 Name, duties and responsibilities of persons designated as Emergency Warden(s) and deputies.
- .2 Emergency Contacts: name and telephone number of officials from:
  - .1 General Contractor and subcontractors.
  - .2 Pertinent federal and provincial Departments and Authorities having jurisdiction.
  - .3 Local emergency resource organizations.
- .3 Name of Contractor's designated Health & Safety Site Representative and information showing proof of his/her

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 10

- competence and reporting relationship in Contractor's company.
- .4 Names, competence and reporting relationship of other supervisory personnel used in the Work for occupational health and safety purposes.
- .5 Procedures for sharing of workrelated safety information to workers and subcontractors, including emergency and evacuation measures.
- .6 List of critical construction activities to be communicated with the Facility Manager and designated Harbour Authority representative(s) that could affect facility and user operations or pose a risk to the health and safety of their employees and to the general public.
- .3 Prepare Health and Safety Plan in a threecolumn format, addressing the three parts specified above, as follows:

Column 1	Column 2	Column 3
Identified	Control	Emergency
Hazard	Measures	Measures and
	Implemented	Communication
		Procedures

- .4 Develop Health and Safety Plan in collaboration with all Subcontractors. Address all work and activities of Subcontractors as they arrive on site. Immediately update Plan and submit to Departmental Representative.
- .5 Implement, maintain and enforce compliance with requirements of the Health and Safety Plan until final completion of work and demobilization from site.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 11

- . 6 As work progresses, review and update Plan addressing additional health risks and safety hazards identified by on-going hazard assessments.
- . 7 Submit revised versions of Plan to Departmental Representative.
- .8 Post a typed written copy, including all updates, of the Health and Safety Plan in a common visible location at work site.
- . 9 Submission of the Health and Safety Plan, and updates, to the Departmental Representative is for review and information purposes only. Its submission shall not be construed to imply approval by Departmental Representative, be interpreted as a warranty of being complete, accurate or legislative compliant and shall not relieve the Contractor of legal obligations for the provision of Health and Safety on the construction project.

#### 1.14 Safety Supervision

- Employ Health and Safety Site . 1 Representative responsible for daily supervision of health and safety of the Work.
- . 2 Health and Safety Site Representative may be the Superintendent of the Work or other person designated by Contractor and shall be assigned the responsibility and authority to:
  - Implement, monitor and enforce daily compliance with health and safety requirements of the Work.
  - Monitor and enforce Contractor's . 2 site-specific Health and Safety Plan.
  - .3 Conduct site safety orientation session to persons granted access to Work Site.
  - Ensure that persons allowed site . 4 access are knowledgeable and trained in health and safety pertinent to

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 12

their activities at the site or are escorted by a competent person while on the Work Site.

- .5 Stop the Work as deemed necessary for reasons of health and safety.
- .3 Health & Safety Site Representative must:
  - .1 Be qualified and competent person in occupational health and safety.
  - .2 Have site-related working experience specific to activities of the Work.
  - .3 Be on Work Site at all times during execution of the Work.
- .4 All supervisory personnel assigned to the Work shall also be competent persons.
- .5 Inspections:
  - .1 Conduct regularly scheduled safety inspections of the Work on a minimum bi-weekly basis. Record deficiencies and remedial action taken. Follow-up and ensure corrective measures are taken.
- .6 Cooperate with facility's Occupational Health and Safety representative, should one be designated by Departmental Representative.
- .7 Keep inspection reports and supervision related documentation on site.
- .1 Use only skilled workers on Work Site who are effectively trained in occupational health and safety procedures and practices

pertinent to their assigned task.

- .2 Maintain employee records and evidence of training received. Make data available to Departmental Representative upon request.
- .3 When unforeseen or peculiar safety-related hazard, or condition occur during performance of Work, follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of

1.15 Training

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 13

Province having jurisdiction and advise Departmental Representative verbally and in writing.

## 1.16 Minimum Site Safety Rules

- .1 Notwithstanding requirement to abide by federal and provincial health and safety regulations; ensure the following minimum safety rules are obeyed by persons granted access to Work Site:
  - .1 Wear appropriate PPE pertinent to the Work or assigned task; minimum being hard hat, safety footwear, safety glasses and hearing protection.
  - .2 Immediately report unsafe condition at site, near-miss accident, injury and damage.
  - .3 Maintain site and storage areas in a tidy condition free of hazards causing injury.
  - .4 Obey warning signs and safety tags.
- .2 The following actions or conduct by Contractor, workers and Subcontractors shall be considered as non-conformance with the health and safety requirements of the contract for which a Non-Compliance Notification will be issued to the General Contractor by the Departmental Representative:
  - .1 Failure to follow the minimum site safety rules specified above.
  - .2 Negligence resulting in serious injury or major property damage.
  - .3 Deliberate non-compliance with Federal and Provincial Acts and Regulations.
  - .4 Falsification of information in Workers' Compensation Reports, safety reports or other health and safety related documents submitted to Departmental Representative or to Authority Having Jurisdiction.
  - .5 Possession of firearms on site.
  - .6 Possession of non-prescriptive illegal drugs or alcohol.
  - .7 Action, or lack thereof, resulting in

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Health and Safety Requirements

Page 14

- the issuance of warnings, fines or stop work orders from an Authority having jurisdiction.
- .8 Violation of other specified health and safety rules and requirements as determined by the *Departmental Representative*.
- .3 The final decision as to what constitutes a safety violation or non-compliance issue will be made by *Departmental*Representative.
- .4 Brief workers on site safety rules and on the disciplinary measures to be taken for violation or non-compliance of such rules. Post such information on site.

## 1.17 Correction of Non-Compliance

- .1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by *Departmental Representative*.
- .2 Provide Departmental Representative with written report of action taken to correct non-compliance of health and safety issues identified.
- .3 Departmental Representative will stop Work if non-compliance of health and safety regulations is not corrected in a timely manner.

### 1.18 Incident Reporting

- .1 Investigate and report the following incidents to Departmental Representative:
  - Incidents requiring notification to Provincial Department of Occupational Safety and Health, Workers Compensation Board or to another regulatory agency.
  - .2 Medical aid injuries.
  - .3 Property damage in excess of \$10,000.00,
  - .4 Interruptions to facility operations resulting in an operational lost to a federal department in excess of

Fisheries and Oceans Canada Section 01 35 30 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Health and Safety Requirements

Page 15

\$5,000.00.

- .2 Submit report in writing.
- 1.19 Tools and Equipment Safety
- .1 Implement and follow a scheduled tool and equipment inspection/maintenance program at the work site. Regularly check tools, equipment and machinery for safe operation and perform maintenance at pre-established time and frequency intervals as recommended by manufacturer. Include Subcontractor's equipment as part of the inspection process.
- .2 Do not modify tools or remove guards or safety devices.
- .3 Use appropriate PPE including safety glasses, safety goggles, gloves and hearing protection.
- .4 Use standardized checklists to ensure established safety checks are stringently followed.
- .5 Immediately tag and remove items found faulty or defective off site.
- .6 Maintain written documentation on each inspection. Make available to Departmental Representative upon request.
- 1.20 Hazardous Products
- .1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS).
- .2 Keep MSDS data sheets for all products delivered to site.
  - .1 Post on site.
  - .2 Submit copy to Departmental Representative.

- 1.21 Confined Spaces
- .1 Abide by occupational health and safety regulations regarding work in confined spaces.

Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Health and Safety Requirements Page 16 1.22 Site Records . 1 Maintain on Work Site copy of safetyrelated documentation and reports stipulated to be produced in compliance with Acts and Regulations of authorities having jurisdiction and of those documents specified herein. . 2 Upon request, make available to Departmental Representative or authorized Safety Officer for inspection. 1.23 Posting of Ensure applicable items, articles, notices . 1 and orders are posted in conspicuous Documents location on Work Site in accordance with Acts and Regulations of Province having jurisdiction. . 2 Post other documents as specified herein, including: Site-specific Health and Safety Plan . 1 . 2 WHMIS data sheets -----END of SECTION-----

Section 01 35 30

Fisheries and Oceans Canada

Fisheries and Oceans Canada Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00115

# Environmental Protection Procedures

for Marine Work Page 1 Section 31 11 00 - Site Work, Demolition 1.1 Related Sections . 1 and Removals . 2 Refer to other Specification Sections for related information. Canada Shipping Act, 2001, amended 2013-1.2 References . 1 12-01; Transport Canada . 2 Canadian Coast Guard Regulations, Fisheries and Oceans Canada .3 Canadian Environmental Protection Act, 1999, amended 2014-03-28; Environment and Climate Change Canada Canadian Navigable Waters Act, 2019-08-28; . 4 Transport Canada . 5 Fisheries Act, 1985, amended 2019-06-21; Fisheries and Oceans Canada . 6 Impact Assessment Act, 2019-08-28; Environment and Climate Change Canada . 7 Migratory Birds Convention Act, 1994, amended 2010-12-10; Environment and Climate Change Canada Nova Scotia - Environment Act .8 . 9 Species at Risk Act, 2002, amended 2013-03-08; Environment and Climate Change Canada and Fisheries and Oceans Canada .10 The Federal Policy on Wetland Conservation, 1991; Environment and

> .12 Workplace Hazardous Materials Information System; Health Canada.

Transportation of Dangerous Goods Act,

1992, amended 2009-06-16; Transport Canada

Climate Change Canada

.11

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 2

#### 1.3 Definitions

- .1 Archaeological resources: all tangible evidence of human activity that is of historical, cultural or scientific interest. Examples include features, structures, archaeological objects or remains at or from an archaeological site, or an object recorded as an isolated archaeological find.
- .2 Buffer zone: a vegetated land that protects watercourses from adjacent land uses. It refers to the land adjacent to watercourses, such as streams, rivers, lakes, ponds, oceans, and wetlands, including the floodplain and the transitional lands between the watercourse and the drier upland areas.
- Deleterious substance: (a) any substance . 3 that, if added to any water, would degrade or alter or form part of a process of degradation or alteration of the quality of that water so that it is rendered or is likely to be rendered deleterious to fish or fish habitat or to the use by man of fish that frequent that water, or (b) any water that contains a substance in such quantity or concentration, or that has been so treated, processed or changed, by heat or other means, from a natural state that it would, if added to any other water, degrade or alter or form part of a process of degradation or alteration of the quality of that water so that it is rendered or is likely to be rendered deleterious to fish or fish habitat or to the use by man of fish that frequent that water.
- .4 Fish habitat: spawning grounds and other areas, including nursery, rearing, food supply and migration areas, on which fish depend directly or indirectly in order to carry out their life processes.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 3

- .5 Hazardous material: product, substance, or organism that is used for its original purpose; and that is either dangerous goods or a material that may cause adverse impact to the environment or adversely affect health of persons, animals, or plant life when released into the environment.
- .6 Invasive or alien species: refers to a species or subspecies introduced outside its normal distribution whose establishment and spread threaten ecosystems, habitats or species with economic or environmental harm.
- .7 Navigable water: a canal and any other body of water created or altered as a result of the construction of any work.
- .8 Surface watercourse: refers to the bed and shore of a river, stream, lake, creek, pond, marsh, estuary or salt-water body that contains water for at least part of each year.
- .9 Wetlands: land where the water table is at, near or above the surface or which is saturated for a long enough period to promote such features as wet-altered soils and water tolerant vegetation. Wetlands include organic wetlands or "peatlands," and mineral wetlands that are influenced by excess water but produce little or no peat.

#### 1.4 Transportation

- .1 Transport hazardous materials and hazardous waste in compliance with the *Transportation of Dangerous Goods Act*.
- .2 It will be the Contractor's responsibility to gain access to all areas of the work site. Contractor to use public roadways and established access routes whenever possible and provide appropriate signage and traffic control personnel as required.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures

for Marine Work

Page 4

- .3 Prior to commencement of work, advise and obtain approval from the *Departmental Representative* of the existing roads and temporary routes / roads proposed to be used to access work areas and to haul material to and from the site.
- .4 All vessels and barges used in the work must comply with all Canada Shipping Act requirements for inspection, which includes certification of the vessel and adequate training and appropriate certificate of competency for the operators and codes and standards of practice for shipping.
- .5 Vessels are to be permitted safe access through the worksite at all times and assisted as necessary.
- .6 All materials and equipment used in construction must be marked in accordance with the Collision Regulations of the Canada Shipping Act, 2001 when located on the waterway.

#### 1.5 Work Site Access

- .1 It will be the Contractor's responsibility to gain access to all areas of the work site, including excavation areas.
- .2 Use public roadways and established access routes whenever possible and provide appropriate signage and traffic control personnel as required.
- .3 Ensure that public and private road surfaces remain free from dredge spoils, clay, mud, etc. throughout the hauling activities.
- .4 Prior to commencement of work, submit a site plan for any new terrestrial access roads to the *Departmental Representative* for approval. Construction will only commence after approval is received from the *Departmental Representative*.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 5

- .5 Limit impacts on riparian vegetation to those approved for the work:
  - .1 Limit access to banks or areas adjacent to waterbodies.
  - .2 Avoid tree removal/grubbing/uprooting and instream prune or top the vegetation.
  - .3 Limit grubbing on watercourse banks to the area required for the footprint of work.
  - .4 Construct access points and approaches perpendicular to the watercourse or waterbody.
  - .5 Use methods to prevent soil compaction and/or rutting, such as swamp mats or pads.
  - .6 Remove vegetation or species selectively and in phases.
  - .7 If required, re-vegetate the disturbed areas with native species suitable for the site.
- .6 Vegetation clearing required for access roads should be scheduled to avoid the regional migratory bird nesting period.
- .7 The construction and removal of temporary in-water access roads and causeways will be at the Contactor's expense and will be removed immediately after construction and/or clearance of the dredge area.
- .8 The construction of temporary in-water access roads and causeways below the mean high water mark will only be placed within the footprint of the approved work area or dredge boundaries.
- .9 All material used for construction of temporary in-water access roads and causeways must be clean and free from excessive fines, organics, debris and non-toxic (i.e., free of fuel, oil, grease and/or any other contaminants), non-ore bearing and from a provincially approved, non-water source.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 6

- .10 No construction or infill material may be obtained from any coastal feature, namely a beach, dune or coastal wetland.
- .11 Temporary in-water access roads and causeways shall be constructed to an elevation such that machinery and equipment are operating completely out of the water at all stages of the tide. If tidal work is being carried out, machinery and equipment shall be relocated back to a suitable elevation to prevent operating in submerged waters. Bidders are advised to consult the Canadian Tide and Current Tables issued by Fisheries and Oceans in order to make sure of the tidal conditions affecting work.
- .12 Limit impacts on fish habitat components:
  - .1 Avoid sensitive habitats such as wetlands, eelgrass and spawning areas.
  - .2 Salvage, reinstate or match habitat structure (e.g., large wood debris, boulders, instream aquatic vegetation/substrate) to its initial state.
  - .3 Restore stream geomorphology (i.e., restore the bed and banks, gradient and contour of the waterbody) to its initial state.
  - .4 Replace/restore any other disturbed habitat features and remediate any areas impacted by the work.
- in-water access roads and causeways must be reused in the work or disposed of in a provincially approved manner. For disposal, this may include transportation to and disposal at a registered environmental facility approved to accept the material or at a location predetermined under the contract. It is the Contractor's responsibility to dispose of the material at its approved location.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 7

Disposal slips must be submitted to the Departmental Representative before final payment is to be made under the contract

- .14 Supply, install and maintain temporary buoys to mark the position of temporary access roads and causeways including the outer toe as construction proceeds. All buoys are to meet requirements for the applicable Canadian Coast Guard standards and be equipped with radar reflectors.
- .15 Any tools, equipment, vehicles, temporary structures or parts thereof used or maintained for the purpose of building or placing a work in navigable water are to be removed upon completion of the project.
- 1.6 Operation of Machinery
- .1 Ensure that machinery arrives on site in a clean condition and is maintained free of fluid leaks, invasive species and noxious weeds.
- .2 Whenever possible, operate machinery on land above the high water mark in a manner that minimizes disturbance to the banks and bed of the water body.
- .3 Wash, refuel and service machinery and store fuel and other materials in such a way as to prevent any deleterious substances from entering the water.
- .4 Do not perform cleaning and wash down within a 30-metre buffer zone of a wetland, watercourse or other identified environmentally sensitive area.
- 1.7 Containment and Spill Management
- .1 Comply with Federal (CEPA Storage Tank
  Systems for Petroleum Products and Allied
  Petroleum Products Regulations) and
  provincial regulations, codes, standards
  and guidelines for the storage of fuel and
  petroleum products on site.
- .2 Do not dump petroleum products or any

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 8

other deleterious substances on ground or in the water.

- .3 Be diligent and take all necessary precautions to avoid spills when handling petroleum products on site and during fueling and servicing of vehicles and equipment.
- .4 Maintain vehicles and equipment in good working order to prevent leaks on site. Hoses, couplings and tanks are to be inspected on a regular basis to prevent fractures and breaks.
- .5 All equipment to be used in or over the marine environment is to be free from leaks or coatings of hydrocarbon-based fluids and/or lubricants harmful to the environment. Hoses and tanks are to be inspected on a regular basis to prevent fractures and breaks.
- .6 Materials such as paint, primers, blasting abrasives, rust solvents, degreasers, grout, or other chemicals are not to enter the watercourse or soils.
- .7 Ensure that building material used in a watercourse has been handled and treated in a manner to prevent the release or leaching of substances into the water that may be deleterious to fish.
- .8 Maintain on site appropriate emergency spill response equipment consisting of at least one 250-litre (55 gallon) overpack spill kit for containment and cleanup of spills. Develop a response plan that is to be implemented immediately in the event of a release or spill of a deleterious substance.
- .9 If using a floating barge:
  - .1 Associated vessels should be compliant with all *Canada Shipping*

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 9

- Act, 2001, requirements for inspection, which includes certification of the vessel and adequate training and appropriate certification of competency for the operator.
- .2 Ensure that all vessels will have procedures in place to ensure safeguards against marine pollution: awareness training of all employees, means of retention of waste oil on board and discharge to shore-based reception facilities, capacity of responding to and clean-up of accidental spill caused by vessels involved in any particular part of the project.
- from a barge, on-site crews to have emergency spill clean-up equipment, adequate for the activity involved, on the barge. Spill equipment will include, as a minimum, one 250 L (55 gallon) overpack spill kit containing items to prevent a spill from spreading; absorbent booms, pillows, and mats; rubber gloves; and plastic disposal bags. Take appropriate measures to contain and clean up any spills and all releases into the environment.
- .10 In the event of a petroleum spill and release into the environment, stop work and immediately notify the Departmental Representative and the Canadian Coast Guard 24-Hour Environment Emergencies Report System (1-800-565-1633). Contain spill and perform clean-up in accordance with all regulations and procedures stipulated by authority having jurisdiction.
- 1.8 Hazardous Material Handling
- .1 Store and handle hazardous materials in accordance with applicable federal and provincial regulations, codes, standards

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 10

and guidelines. Store in location that will prevent spillage into the environment.

- .2 Label containers to WHMIS requirements and keep MSDS data sheets on site for all hazardous materials.
- .3 Maintain inventory of hazardous materials and hazardous waste stored on site. List items by product name, quantity and date when stored.
- .4 Store and handle flammable and combustible materials in accordance with National Fire Code.
- .5 Workers in contact with hazardous materials must be provided with, and use regulated Personal Protective Equipment (PPE) and must have the necessary training to know how to handle the different hazardous materials in accordance with applicable health and safety and environmental regulations.

# 1.9 Disposal of Wastes

- .1 Do not bury construction and demolitionrelated debris (e.g., concrete, creosote timbers, steel, impacted soil, etc.) or other waste materials on site.
- .2 Dispose and recycle construction and demolition-related debris and waste materials in accordance with provincial waste management regulations.
- .3 Do not dispose of hazardous wastes (e.g., paints, batteries, cleaners, acids, etc.) including volatile materials (e.g., solvents, mineral spirits, aerosol cans, etc.) and petroleum products on the ground or into waterways, wetlands, sewers or in landfills. Dispose of hazardous wastes in accordance with applicable federal and provincial, regulations, codes, standards and guidelines.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 11

- .4 All salvageable stockpiles of creosote timbers must be situated a minimum of 100 meters from any dwelling or potable water well and a minimum of 100 meters from any watercourse, wetland or other environmentally sensitive area. All stockpiles must be contained on federal land, unless approved by Departmental Representative. Prior to completion of the work, all salvageable/disposal material must be removed from the site as directed by the Departmental Representative.
- .5 Dispose of hazardous waste in accordance with applicable federal and provincial, regulations, codes, standards and guidelines.
- .6 Conduct daily clean-up of floating or sinking construction materials, litter, and other debris arising from the work site to ensure protection of the marine environment. Any construction debris/material that enters the marine environment must be removed immediately and be disposed of in a provincially approved manner.

# 1.10 Water Quality

- .1 Where work may affect water quality, schedule work in cooperation with the Harbour Authority as directed by Departmental Representative to minimize interference and impact on harbour users.
- .2 Contractor will be required to develop and implement an Erosion and Sediment Control Plan for the project site that minimizes risk of sedimentation of the water body during all phases of the work. Erosion and sediment control measures should be maintained until all disturbed ground has been permanently stabilized, suspended sediment has resettled to the bed of the water body or settling basin and runoff water is clear. The plan must be submitted

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 12

to the *Departmental Representative* for approval and should, where applicable, include:

- .1 Installation of effective erosion and sediment control measures before starting work to prevent sediment from entering the water body.
- .2 Measures for managing water flowing to the site, as well as water being pumped/diverted from the site such that sediment is filtered out prior to the water entering a water body. For example, pumping/diversion of water to a vegetated area, construction of a settling basin or other filtration system.
- .3 Measures for containing and stabilizing waste material (e.g., excavated material, construction waste and materials, commercial logging waste, uprooted or cut aquatic plants, accumulated debris) above the high water mark of nearby water bodies to prevent re-entry.
- .4 Regular inspection and maintenance of erosion and sediment control measures and structures during the course of the work.
- .5 Repairs to erosion and sediment control measures and structures if damage occurs.
- .6 Removal of non-biodegradable erosion and sediment control materials once site is stabilized.
- .3 Any construction debris entering the marine environment will be immediately retrieved when it is safe to do so.
- .4 The construction material used must be clean and non-toxic (free of fuel, oil, grease, and/or any contaminants).
- .5 All rock and fill material that will be used for the project must be free of excessive fines, clean, non-ore bearing,

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 13

non-toxic material (i.e., free from fuels, oil, grease and/or contaminants) from an approved non-watercourse, and approved for use in marine infilling projects.

- .6 Conduct excavation operations in such a manner to limit turbidity and reduce sediment suspension in the water to an absolute minimum at all times:
  - And momentum of the excavation equipment. Make adjustments as required and as approved by Departmental Representative.
  - .2 Strategically position excavation equipment and haul vehicles to avoid over the water swings of finer excavated material whenever possible.
- .7 Where required, install effective sediment control measures before starting work to prevent the entry or re-suspension of sediment in the water body. Use biodegradable sediment control measures whenever possible.
- .8 Keep erosion and sediment control measures in place until all disturbed ground has been stabilized. Inspect sediment control measures regularly to ensure they are functioning properly, and make all necessary repairs if any damage occurs.
- .9 All soils resulting from the construction must be stabilized as soon as possible in order to control sediment runoff during and after construction. Upon completion of work, remove erosion and sedimentation controls in a way that prevents the escape of settled sediment and restore and stabilize areas disturbed during removal.
- .10 Weather conditions are to be assessed on a daily basis to determine the potential risk of extreme weather in the project area. Avoid work during periods which

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00115

## Environmental Protection Procedures for Marine Work

Page 14

1.11 Socioeconomic Restrictions

- Environment and Climate Change Canada (ECCC) has issued rainfall or wave warning for the work area that may increase erosion and/or sedimentation.
- Abide by municipal and provincial . 1 regulations for any restrictions on work performed during the nighttime and with flood lighting of the site. Obtain applicable permits.
- Place flood lights in opposite direction . 2 of adjacent residential and business areas. Use LED lights instead of other types of lights, where possible. LED light fixtures are less prone to light trespass (i.e., are better at directing light where it needs to be, and do not bleed light into the surrounding area).
- . 3 Work equipment and machinery must be adequately equipped with mufflers to reduce noise on site to lowest possible level. Maintain mufflers in good operating condition at all times.
- The Contractor will coordinate with the . 4 local Harbour Authority prior to commencement of the project activities such that the schedule with the least possible conflicts will be implemented.
- 1.12 Fish and Fish Habitat Protection
- Monitor and assess weather forecast on a . 1 daily basis to determine the risk of extreme weather. Secure the work site and avoid work during periods for which Environment and Climate Change Canada has issued rainfall, storm surge or other weather warnings for the area.
- Ensure that all in-water activities, or . 2 associated in-water structures, do not interfere with fish passage, constrict the channel width, or reduce flows.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115

Environmental Protection Procedures for Marine Work

Page 15

#### 1.13 Invasive Species

- .1 Contractor shall be aware of the risk for contamination of the fish habitat at the site as a result of alien species being introduced into the marine environment.
- . 2 To minimize the possibility of fish habitat contamination and the spread of aquatic invasive/alien species, all construction equipment which will be immersed into the water of a watercourse, or has the possibility of coming into contact with such water during the course of the work, must be cleaned and washed to ensure that it is free of marine growth and invasive/alien species. Equipment shall include boats, barges, rafts, cranes, excavators, haul trucks, pumps, pipelines and all other miscellaneous tools and equipment previously used in a marine environment.
- .3 Cleaning and washing of equipment shall be performed immediately upon arrival at the site and before use in or over the body of water.
- .4 Conduct cleaning and washing operations as follows, at a minimum:
  - .1 Scrape and remove heavy accumulation of mud and dispose appropriately.
  - .2 Wash all surfaces of equipment by use of a pressurized fresh water supply.
  - .3 Immediately follow with application of a heavy sprayed coating of undiluted vinegar or other environmentally approved cleaning agent to thoroughly remove all plant matter, animals and sediments.
  - .4 Check and remove all plant, animal and sediment matter from all bilges and filters.
  - .5 Drain standing water from equipment and let fully dry before use.
  - .6 Upon removal from the water, drain standing water from equipment and let fully dry before removal off site.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00115

# Environmental Protection Procedures for Marine Work

Page 16

# 1.14 Bird and Bird Habitat

- .1 Become knowledgeable with and abide by the Migratory Birds Convention Act (MBCA) in regard to the protection of migratory birds, their eggs, nests and their young encountered on site and in the vicinity.
- .2 Minimize disturbance to all birds on site and adjacent areas during the entire course of the Work.
- .3 Do not approach concentrations of seabirds, waterfowl and shorebirds when anchoring equipment, accessing wharves or ferrying supplies.
- .4 During nighttime work, position flood lights in opposite direction of nearby bird nesting habitat.
- .5 Do not use beaches, dunes and other natural previously undisturbed areas of the site to conduct work unless specifically approved by the *Departmental Representative*.
- .6 Should nests of migratory birds in wetlands be encountered during work, immediately notify *Departmental Representative* for directives to be followed.
  - .1 Do not disturb nest site and neighbouring vegetation until nesting is completed.
  - .2 Minimize work immediately adjacent to such areas until nesting is completed.
  - .3 Protect these areas by following recommendations of Canadian Wildlife Service.
- .7 All machinery must be well muffled. If necessary, trucks may be required to avoid the use of "hammer" braking along specific sections of the route.

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00115

# Environmental Protection Procedures for Marine Work

Page 17

# 1.15 Species at Risk and Marine Mammals

- .1 A safety zone for leatherback sea turtles and marine mammals must be established at the work site. The safety zone shall consist of a circle with a radius of at least 500 meters as measured from the center of the site.
- .2 Maintain periodic visual surveys for leatherback sea turtles and marine mammals within the safety zone.
- .3 If leatherback sea turtles or marine mammals are observed within the safety zone while in-water activities are underway, all in-water activities must cease until the animals leave the safety zone and are not observed within the safety zone for a minimum period of 30 minutes.
- .4 Work may start or restart if marine mammals are not observed within the safety zone within the 30-minute period.

#### 1.16 Air Quality

- .1 Keep airborne dust and dirt resulting from the work on site to an absolute minimum.
- .2 Dust suppression by the application of water must be employed, when required. Apply dust control measures to roads, parking lots and work areas. The Departmental Representative shall determine locations where water is to be applied, the amount of water to be applied, and the times at which it shall be applied.
- .3 Spray surfaces with water or other environmentally approved product. Use purposely suited equipment or machinery and apply in sufficient quantity and frequency to provide effective result and continued dust control during the entire course of the work.
- .4 Do not use oil or any other petroleum

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00115 Section 01 35 44

arine Work Page 18

Environmental Protection Procedures for Marine Work

products for dust control.

#### 1.17 Fires

- .1 Fires and burning of rubbish on site are not permitted.
- 1.18 Archaeological
- .1 All construction personnel are responsible for reporting any unusual materials unearthed during construction to the construction supervisor. If the find is believed to be an archaeological resource, the Construction Supervisor will immediately stop work in the vicinity of the find and notify the Departmental Representative.
- .2 If an archaeological and/or historically significant item is discovered during the work activities, work in the area will be stopped immediately and the *Departmental Representative* will be contacted as well as the provincial Archaeological Services Unit.
  - .1 Nova Scotia Department of Communities, Culture, Tourism and Heritage, Special Places Program, telephone: (902) 424-6475.
- .3 Work can only resume in the vicinity of the find when authorized by the Departmental Representative and Construction Supervisor, after approval has been granted by the Nova Scotia Department of Communities, Culture, Tourism and Heritage.
- .4 In the event of the discovery of human remains of evidence of burials, excavation work will immediately cease, and nearest law enforcement agency will be contacted immediately by the *Departmental Representative* and/or the Construction Supervisor.

-----END of SECTION------

Fisheries and Oceans Canada Section 01 45 00 Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.

. 1

Project No.: C2-00155

Testing Laboratory Services

Page 1

## 1.1 Related Requirements

Particular requirements for inspection and testing to be carried out by testing laboratory designated by *Departmental Representative* are specified under various sections.

- 1.2 Appointment and Payment
- .1 Departmental Representative will appoint and pay for services of testing laboratory except for the following:
  - .1 Inspection and testing required by laws, ordinances, rules, regulations, or orders of public authorities
  - .2 Inspection and testing performed exclusively for Contractor's convenience.
  - .3 Testing, adjustment and balancing of conveying systems, mechanical and electrical equipment, and other systems.
  - .4 Mill tests and certificates of compliance.
  - .5 Tests specified to be carried out by Contractor under the supervision of Departmental Representative.
- .2 Where tests or inspections by designated testing laboratory reveal work not in accordance with contract requirements, Contractor shall pay costs for additional tests or inspections as Departmental Representative may require to verify the acceptability of corrected work.

# 1.3 Contractor's Responsibilities

- .1 Furnish labour and facilities to:
  - .1 Provide access to work to be inspected and tested.
  - .2 Facilitate inspections and tests.
  - .3 Make good work disturbed by inspection and test.
  - .4 Provide storage on site for laboratory's exclusive use to store equipment and cure test samples.
- .2 Notify Departmental Representative sufficiently in advance of operations to

Fisheries and Oceans Canada Section 01 45 00 Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Testing Laboratory Services

Page 2

allow for assignment of laboratory personal and scheduling of test.

- .3 Where materials are specified to be tested, deliver representative samples in required quantity to testing laboratory.
- .4 Pay costs for uncovering and making good work that is covered before required inspection or testing is completed and approved by *Departmental Representative*.

-----END of SECTION------

Fisheries and Oceans Canada Section 01 51 00

Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Proj	ect No.: C2-00155	Tem	porary Facilities Page 1
1.1	Access	.1	Provide and maintain adequate access to project site.
		.2	If authorized to use existing roads or structures for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractor's use of roads.
		.3	Maintain full access to the work site. Should a court injunction be required ordering a person or group to refrain from impeding access to the site, such as a demonstration, picketing or union action, then obtaining the injunction and any associated costs will be considered incidental to this contract. Any delays associated with such activity will be considered incidental to this contract.
1.2	Contractor's Site Office	.1	Not Required.
		.2	Keep on site a copy of contract documents, all letters, orders, notices and other communications as well as all other materials as specified under Section 01 10 10 - General Instructions.
1.3	Departmental Representative's Site Office	.1	Not Required.
		.2	Provide outside sanitary facilities to approval of <i>Departmental Representative</i> . Maintain in clean condition.
1.4	Storage Sheds	.1	Provide adequate weather tight sheds with raised floors, for storage of materials, tools and equipment, which are subject to damage by weather.
		.2	Contractor to make own arrangements for on-site laydown and storage areas.
1.5	Sanitary Facilities	.1	Provide sanitary facilities for work force in accordance with governing regulations

and ordinances.

Fisheries and Oceans Canada Section 01 51 00 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Project No.: C2-00155	Tem	porary Facilities	Page 2
	.2	Post notices and take such precautarequired by local health authorities Keep area and premises in sanitary condition.	es.
1.6 <u>Parking</u>	.1	Contractor to make own arrangements provide parking space for employees	
1.7 <u>Power</u>	.1	Arrange, pay for and maintain temper electrical power supply in accordant governing regulations.	_
	.2	Install temporary facilities for posuch as poles, lines and cables to approval of local electric utility	
1.8 <u>Barricades</u>	.1	Provide and maintain sufficient barricades, fencing, notices, warn signs, light signals, etc. for the protection of adjoining property as warn others and workmen engaged on of the dangers caused by the work.	nd to
	.2	Types and location of barricades, be in accordance with local regular and to the satisfaction of Department Representative.	tions
	.3	The presence of such barricades, letc. shall not relieve the Contract the responsibility for any damages	tor of
1.9 <u>Security</u>	.1	Contractor to make arrangements for security of his equipment, material damages resulting from fire and the	ls,
1.10 Site Signs and Notices	.1	Only Project Identification and Consultant/ Contractor signboards notices for safety or instruction permitted on site.	
	.2	Format, location and quantity of saigns and notices to be accepted by Departmental Representative.	

Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Temporary Facilities Page 3 . 3 Signs and notices for safety or instruction to be in English and French languages, or commonly understood graphic symbols. 1.11 Removal of Remove temporary facilities from site when . 1 directed by Departmental Representative. Temporary Facilities . 2 If project is closed down for a period of time, keep temporary facilities operational until no longer required by Departmental Representative. ------

Section 01 51 00

Fisheries and Oceans Canada

Section 01 61 00

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

# Material and Equipment

Page 1

#### 1.1 General

- .1 Use new material and equipment unless otherwise specified.
- .2 Submit following information for any or all materials and products proposed for supply within seven (7) days of request by Departmental Representative:
  - .1 name and address of manufacturer;
  - .2 trade name, model and catalogue
    number;
  - .3 performance, descriptive and test
     data;
  - .4 manufacturer's installation or application instructions; and
  - .5 evidence of arrangements to procure.
- .3 Provide material and equipment of specified design and quality, performing to published ratings and for which replacement parts are readily available.
- .4 Use products of one manufacturer for equipment or material of same type or classification unless otherwise specified.

# 1.2 Manufacturer's Instructions

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods.
- .2 Notify Departmental Representative in writing of any conflict between these specifications and manufacturer's instructions. Departmental Representative will designate which document is to be followed.

## 1.3 Delivery and Storage

- .1 Deliver, store and maintain packaged material and equipment with manufacturer's seal and labels intact.
- .2 Prevent damage, adulteration and soiling of material and equipment during delivery, handling and storage. Immediately remove rejected material and equipment from site.
- .3 Store material and equipment in accordance

Fisheries and Oceans Canada Section 01 61 00 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Material and Equipment

Page 2

# 1.4 Conformance

# .1 When material or equipment is specified by standard or performance specifications, upon request of *Departmental Representative*, obtain from manufacturer an independent testing laboratory report, stating that material or equipment meets or exceeds specified requirements.

with supplier's instructions.

#### 1.5 Substitution

- .1 Proposals for substitution may be submitted only after award of Contract. Such requests must include statements of respective costs of items originally specified and proposed substitutions.
- .2 Proposals will be considered by Departmental Representative if:
  - .1 Products selected by tenderer from those specified, are not available, or
  - .2 Delivery date of products from those specified would unduly delay completion of Contract, or
  - .3 Alternative products to those specified, which are brought to attention of, and considered by Departmental Representative as equivalent to those specified and will result in a credit to Contract amount.
- .3 Should proposed substitution be accepted either in part or in whole, assume full responsibility and costs when substitution affects other work on project. Pay for design or drawing changes required as result of substitution.
- .4 Amounts of all credits arising from approval of substitutions will be determined by Departmental Representative and Contract price will be reduced accordingly. No substitutions will be permitted without prior written approval of Departmental Representative.

Fisheries and Oceans Canada Section 01 61 00 Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Material and Equipment Page 3 .5 Departmental Representative reserves the right for acceptance or rejection of substitution of materials. 1.6 Construction . 1 On request, prove to the satisfaction of Departmental Representative that the Equipment and Plant construction equipment and plant are adequate to manufacture, transport, place and finish work to quality and production rates specified. If inadequate, replace or provide additional equipment or plant as directed. Maintain construction equipment and plant . 2 in good operating order. Immediately replace, repair or otherwise 1.7 Damaged and Rejected . 1 Materials make good any material damaged, broken or defaced during construction to the

-----END of SECTION-----

. 2

Representative.

satisfaction of Departmental

Remove rejected materials from site.

Project No.: C2-00155

# Project Record Documents

Page 1

# 1.1 Record Drawings

- . 1 Departmental Representative will provide two (2) sets of white prints for record drawing purposes.
- . 2 Maintain project record drawings and accurately record deviations from contract documents caused by site conditions and changes ordered by Departmental Representative.
- . 3 Mark changes in red coloured ink.
- . 4 Record following information:
  - .1 Elevations of various elements in relation to Chart Datum.
  - Field changes in dimensions and . 2 details.
  - .3 Changes made by Change Order.
- Make Contractor's set of marked-up Record . 5 Drawings available for Departmental Representative's review on a regular monthly basis and more frequently if requested.
- At completion of project and prior to . 6 final inspection, neatly transfer notations to second set and submit both sets to Departmental Representative. An electronic version of the Record Drawings to be submitted to Departmental Representative.

-----END of SECTION-----

Fisheries and Oceans Canada

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

			Cleaning	Page 1
1.1	<u>General</u>	.1	Conduct cleaning and disposal ope to comply with ordinances and law	
		.2	Store volatile waste in covered m containers, and remove from premi end of each working day.	
		.3	Prevent accumulation of waste whi create hazardous conditions.	ch
1.2	Cleaning During Construction	.1	Maintain the work, at least on a basis free from accumulations of material and debris.	-
		.2	Provide on-site containers for collection of waste materials, an debris.	d
		.3	Remove all waste and debris from	site.
		. 4	Schedule cleaning operations so tresulting dust, debris and other contaminants will not fall on wet concrete or newly painted surface	
1.3	Final Cleaning	.1	In preparation for acceptance of project on an interim or final certificate of completion perform cleaning.	
		.2	Remove grease, dust, dirt, stains other foreign materials from fini surface.	
		.3	Remove surplus materials, rubbish and equipment.	, tools
			ND of CECETON	

-----END of SECTION------

Fisheries and Oceans Canada Section 31 11 00

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Sitework, Demolition and Removals

Page 1

#### PART 1 - GENERAL

1.1	Description	of
	Work	

- .1 This Section includes but is not limited to the following:
  - .1 All normal demolition and removals as required to complete the work in accordance with the plans and these specifications.
  - .2 Removal, sorting, stockpiling and reinstallation of armour stone and filter stone as directed by the Departmental Representative.
  - .3 Removal of excess soils and other granular material not to be reused in the new work.
  - .4 Grading existing service area and sloping existing embankment.

# 1.2 Related Work

- .1 Section 01 35 44 Environmental Protection Procedures for Marine Work
- .2 Section 01 74 00 Cleaning
- .3 Refer to other Specification sections for related information.

#### 1.3 Submissions

- .1 Methodology:
  - .1 When requested by *Departmental Representative*, provide methodology for carrying out the work.
- .2 Provide submission in accordance with Section 01 33 00.

## 1.4 Protection

- .1 Protect existing harbour facilities throughout the execution of the work.
- .2 Prevent movement, settlement or damage of adjacent structures. Provided bracing and shoring as required. In event of damage, immediately replace such items or make repairs to approval of Departmental Representative and at no additional cost to Departmental Representative.
- .3 Prevent debris from going adrift and

Fisheries and Oceans Canada

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Sitework, Demolition and Removals

Page 2

becoming a menace to navigation.

- .4 All damage to existing structures, roadways, pipelines, electrical systems not specified for removal to be repaired at the Contractor's cost to the satisfaction of the Departmental Representative.
- 1.5 Measurement for Payment
- .1 Sitework, demolition and removals will be measured in accordance with Section 01 29 00.

#### PART 2 - PRODUCTS

Not applicable.

# PART 3 - EXECUTION

3.1 Preparation

- .1 Inspect site and verify with *Departmental Representative* items designated for removal and items to be preserved.
- .2 Locate and protect utility lines. Preserve in operating condition active utilities traversing site.
- .3 Provide temporary power and lighting as required to carry out the work.

3.2 Removals

- .1 Remove all items as indicated.
- .2 Do not disturb adjacent structures designated to remain in place.
- .3 At end of each day's work, leave work in safe condition so no part is in danger of toppling or falling.
- 3.3 Salvage
  Stockpiling and
  Reinstallation
- .1 Remove, sort, salvage and stockpile existing armour stone and filter stone within designated areas shown on the drawings. Salvaged armour and filter stone to be incorporated into the new work as specified (where suitable).

3.4 Disposal of Material

.1 Excess soils and other granular materials not designated for salvage or re-use in

Fisheries and Oceans Canada Section 31 11 00 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Sitework, Demolition and Removals

Page 3

work shall be stockpiled and placed in the containment cell upon completion of the work.

.2 Material designated for disposal shall be transported and disposed of in an environmentally acceptable manner to the satisfaction of the *Departmental Representative*, and in accordance with any provincial, federal, or municipal regulations or by-laws.

3.5 Restoration

- .1 Regrade existing service area used as part of the construction operations.
- .2 Prepare and install side slope on embankment where filter and armour stone was removed to a uniform 1.5 horizontal to 1 vertical (1.5:1) top to bottom and full length.
- .3 Upon completion of work, remove debris, trim surfaces and leave work site clean.
- .4 Reinstate areas and existing works outside areas of demolition to conditions that existed prior to commencement of work.

  Match condition of adjacent, undisturbed areas.

-----END of SECTION------

Section 31 23 10

Fisheries and Oceans Canada Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Excavating, Trenching and Backfilling

Page 1

#### PART 1 - GENERAL

- 1.1 Related Sections .1 Section 01 35 44 Environmental
  - Protection Procedures for Marine Work
  - .2 Section 31 11 00 Sitework, Demolition and Removals
  - .3 Refer to other Specification sections for related information.

1.2 <u>Definitions</u>

- .1 Rock excavation: excavation of material from solid masses of igneous, sedimentary or metamorphic rock which, prior to its removal, was integral with its parent mass, and boulders or rock fragments having individual volume in excess of 1.5  $\rm m^3$ .
- .2 Common excavation: excavation of materials of whatever nature, which are not included under definitions of rock excavation including dense tills, hardpan, frozen materials and partially cemented materials such as asphalt which can be ripped and excavated with heavy construction equipment.
- 1.3 Protection of
   Existing Features
- .1 Existing buried utilities and structures:
  - .1 Prior to commencing any excavation work, notify applicable owner or authorities, establish location and state of use of buried utilities and structures. Clearly mark such locations to prevent disturbance during work.
- .2 Existing buildings and surface features:
  - .1 Protect existing buildings and surface features which may be affected by work from damage while work is in progress and repair damage resulting from work.

- 1.5 Shoring and Bracing
- .1 Comply with applicable regulations to protect existing features.

Fisheries and Oceans Canada Section 31 23 10 Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155 Excavating, Trenching and Backfilling Page 2 1.6 Measurement for .2 No measurement for payment will be made for this item. Include cost of Excavating Payment and Backfilling into items for which Excavating and Backfilling are required. PART 2 - PRODUCTS Not Applicable PART 3 - EXECUTION 3.1 Site Preparation . 1 Remove obstructions, ice and snow, from surfaces to be excavated within limits indicated. . 2 Plan and execute work in a manner that will not impede navigation including movement of vessels in the channel, at any wharf site or any other vessel traffic at adjacent wharves in the harbour. 3.2 Stockpiling . 1 Stockpile materials designated for salvage in areas approved by Departmental Representative. . 1 It will be the Contractor's responsibility 3.3 Excavation to gain access to the excavation areas. The construction of temporary causeways, roads, etc., will be at the Contractor's expense and will be removed at the completion of the project. It will be the Contractor's responsibility to obtain all environmental approvals associated with the construction of temporary access roads that are outside the areas designated for excavation. Any power lines that will require removal will be done so at the Contractor's expense and will be replaced to satisfaction of the Departmental Representative. . 2 Advise Departmental Representative of proposed methodology to carry out excavation, salvage and removal of material. . 3 Excavate to approximated lines, grades,

elevations and dimensions indicated on the

Section 31 23 10

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S. Project No.: C2-00155

Excavating, Trenching and Backfilling

Page 3

plans or as directed by Departmental Representative. If elevations indicated on the plans are below actual bedrock elevations, excavation to include common excavation only down to bedrock elevations only (i.e. no rock excavation will be required to toe in armourstone).

- .4 Do not obstruct flow of surface drainage or natural watercourses.
- .5 Remove materials above specified grade depths, within approximate limits indicated. Remove all material as a result of sloughing or infilling.

  Material removed from below grade depth or outside specified area or side slope is not part of work.
- .6 Excavate side slopes to slopes indicated on the drawings, or as required to maintain stable slopes.
- .7 Immediately notify Departmental
  Representative upon encountering an object which might be classified as an obstruction. By-pass the object after clearly marking its location and continue work.
- .8 Segregate and stockpile designated excavated materials in approved locations.
- 3.5 Disposal of Excess Materials
- .1 All underwater excavated material designated for disposal is to be placed within the disposal site/cell unless otherwise directed by the *Departmental Representative*.
- .2 Contractor will be responsible for developing and maintaining access to the disposal site/cell and any other modifications required for execution of the work.

Fisheries and Oceans Canada	Section 31 23 10
Containment Cell Construction	
Little Judique Ponds, Inverness	County, N.S.
Project No.: C2-00155	
Excavating,	Trenching and Backfilling Page 4
.3	All debris including timber, concrete, rebar, logs, cable, etc. must be segregated and be disposed of at an approved landfill.
3.9 <u>Restoration</u> .1	Upon completion of work, remove surplus materials and debris and correct defects noted by <i>Departmental Representative</i> .
.2	Clean and reinstate areas affected by work as directed by Departmental Representative.
	-END of SECTION

Fisheries and Oceans Canada Section 31 32 21 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Geotextiles Page 1

#### PART 1 - GENERAL

- 1.1 Related Work .1 Refer to other Specification sections for related information.
- 1.2 Reference Standards

- .1 All reference standards in this section shall be current issue or latest revision at the first date of project tender advertisement.
- .2 American Society for Testing and Materials International (ASTM):
  - .1 ASTM D4595-17, Standard Test Method for Tensile Properties of Geotextiles by the Wide-Width Strip Method.
  - .2 ASTM D4491/D4491M-22, Standard Test Methods for Water Permeability of Geotextiles Permittivity.
  - .3 ASTM D4533/D4533M-13 (R2016), Standard Test Method for Trapezoid Tearing Strength of Geotextiles.
  - .4 ASTM D4632/D4632M-15a (R2016), Standard Test Method for Grab Breaking Load and Elongation of Geotextiles.
  - .5 ASTM D4751-21a, Standard Test Methods for Determining Apparent Opening Size of a Geotextile.
- .3 Canadian General Standards Board (CGSB):
  - 1 CGSB-4.2 No.14-2005, Textile Test Methods: Quantitative Analysis for Fibre Mixtures.
  - .2 CGSB-148.1, Methods of Testing Geosynthetics.

1.3 Submittals

- .1 At least two (2) weeks prior to start of work, furnish *Departmental Representative* with copies of mill test data and certificate that filter fabric delivered to job site meets requirements of this section.
- .2 Submit in accordance with Section 01 33 00 Submittal Procedures.

Fisheries and Oceans Canada			Section 31 32 21	
Containment Cell Construction Little Judique Ponds, Inverness Project No.: C2-00155			County, N.S.	
			Geotextiles Page 2	
1.4	<u>Approval</u>	.1	Obtain written approval of <i>Departmental</i> Representative for geotextile fabric before installation of material in work.	
1.5	Measurement for Payment	.1	Geotextile fabric will be measured in accordance with Section 01 29 00.	
PART	2 - PRODUCTS			
2.1	<u>Materials</u>	.1	Synthetic fiber: rot proof, unaffected by action of oil or salt water and not subject to attack by insects or rodents.	
		.2	Fabric: nonwoven polyester and/or polypropylene fabric.	
		.3	Seams: sewn in accordance with manufacturer's recommendations.	
		. 4	Physical properties: .1 Tensile Strength: 1100 N .2 Tear Strength: 440 N .3 Elongation at break: 50% .4 Filtration Opening Size: .180mm .5 Permeability: 1.2 x 10 <sup>-1</sup> cm sec <sup>-1</sup> .	
PART	3 - EXECUTION			
3.1	Preparation of Base	.1	Fine grade area to be covered with geotextile fabric to a uniform surface area. Fill depressions with suitable material.	
3.2	Placing Geotextile Fabric	.1	Place geotextile fabric on prepared surface loosely from top of the slope to the bottom allowing fabric to conform easily to contours of the slope.	
		.2	Allow one (1) metre of fabric for overlapping and anchoring purposes, 700 mm at the top and 300 mm at the bottom of the slope.	
		.3	Longitudinal seems will have a minimum of 450 mm overlap and will be pinned/stitched	

Fisheries and Oceans Canada
Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.
Project No.: C2-00155

Geotextiles
Page 3

every 600 mm with 100 mm galvanized nails.

.4 Anchor top of fabric at 1 metre-intervals with 15 mm diameter steel rods 600 mm in length. Anchor bottom of fabric by

-----END of SECTION-------

folding fabric and placing stone on top.

Fisheries and Oceans Canada Section 35 31 24.1

Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment	Cell	Page	1

## PART 1 - GENERAL

- 1.1 <u>Description</u>

  .1 This section specifies requirements for construction of the containment cell consisting of component layers, including core stone, filter stone, armour stone, and to dimensions indicated.
- 1.2 Reference .1 American Society for Testing and Materials

  Standards International (ASTM):
  - .1 ASTM C 127-15 (or latest edition)
    Standard Test Method for Relative
    Density (Specific Gravity) and
    Absorption of Coarse Aggregate.
  - .2 American Association of State Highway and Transport Officials (AASHTO):
    - .1 AASHTO T85 (latest edition) Standard Method of Test for Specific Gravity and Absorption of Coarse Aggregate.
- 1.3 <u>Related Work</u> .1 Refer to other Specification Sections for related information.
- 1.4 <u>Source Sampling</u> .1 Inform *Departmental Representative* of proposed source of materials and provide access for sampling at least two (2) weeks prior to commencing work.
  - .2 Forward, prepaid, a sample rock to be used to a testing consultant to be determined by the *Departmental Representative* for approval. Sample to be between 5 and 10 kg, representative of quarry and submitted minimum two (2) weeks prior to starting work.
- 1.5 Existing Conditions and Haul Roads
- .1 The land surrounding the site is both privately owned and is also the property of His Majesty the King in the Right of Canada and the Contractor will exercise extreme care to prevent damage to the abutting lands.
- .2 It is important that Contractors intending to bid on work visit the site and

Fisheries and Oceans Canada Section 35 31 24.1 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 2

ascertain what preparatory work will be required for the following:

- .1 Condition of existing access roads and structures over which material must be hauled.
- .2 Preparation, maintenance, and removal of temporary roadways to and on the site for the use of trucks, loaders, cranes, long-reach excavators, draglines, etc.
- .3 Preparation, maintenance and removal of all temporary causeways and/or fills as required for trucks, loaders, long-reach excavators, cranes, draglines, etc.
- .4 Contractor shall be solely responsible for construction and maintenance of haul roads which shall be considered incidental to the work. All temporary roads shall be removed at the completion of the project and the land restored to its original condition.

## 1.3 Measurement for Payment

- .1 <u>Core stone</u> will be measured in accordance with Section 01 29 00.
- .2 <u>Filter stone</u> will be measured in accordance with Section 01 29 00.
- .3 <u>Armour stone</u> will be measured in accordance with Section 01 29 00.
- .4 Mobilization and demobilization will be measured in accordance with Section 01 29 00.
- .5 No payment will be made for material used to construct and/or maintain haul roads, causeways, fills or working roadways on top of filter and armour layers.
- .6 Clearing, grubbing and stripping of quarries to be incidental to the work.

Fisheries and Oceans Canada Section 35 31 24.1
Containment Cell Construction
Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 3

- .7 Making good to the satisfaction of the Departmental Representative, any damage to the existing structures will be considered incidental to the work.
- .8 Do not mix different categories of material in the same truckload. Only one class of material will be weighed for payment at any given time. If rocks of markedly different sizes are present, Departmental Representative reserves the right to weigh such rocks separately for payment. There will be no additional payment for weighing individual stone units which do not meet the category of material listed for the truckload.

## PART 2 - PRODUCTS

## 2.1 Materials

- .1 Rock Material:
  - .1 All rock materials to be tested and approved by the *Departmental Representative* prior to installation in the work.
  - .2 All field stone supplied by the Contractor must be accepted before it is used in the work.
  - .3 All rock materials to be free from cracks, seams and other defects which may impair durability.
- .2 Armour stone and Filter stone to meet the following requirements:
  - 1 Specific Gravity minimum 2.65 and absorption maximum 2.0%. Slate, sandstone, shale, and stone containing mica not acceptable for filter stone or armour stone.
  - .2 Quarried or field stone, rough and angular in shape.
  - .3 Greatest dimension of each stone not to exceed two times least dimension.

Fisheries and Oceans Canada Section 35 31 24.1 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 4

#### .3 Armour stone:

- .1 Armour stone will be hard, dense, durable, angular stone, free from cracks, or other structural defects.
- .2 Minimum individual weight of armour stones will be 5 tonne, maximum weight will be 7 tonnes, based on a specific gravity of 2.65 tonnes per cubic metre.
- .3 Fifty percent (50%) by weight of the armour stone will be individual stones greater than, or equal to 6 tonnes.
- .4 Filter stone for first and second
  underlayers:
  - .1 All filter stone will be hard, dense, durable, angular stone, free from cracks, or other structural defects.
  - .2 Underlayers:
    - .1 Filter stones to consist of stones weighing 200 to 700 kg.
    - .2 Fifty percent (50%) by weight of the filter stone shall be individual stones greater than, or equal 450 kg.

#### .5 Core stone:

- .1 Specific Gravity minimum 2.65.
- .2 Actual Specific Gravity and absorption will be determined by testing selected samples of material being incorporated into the works.

  Materials with a specific gravity less than 2.65 or an absorption rate in excess of 2% will be rejected.
- .3 To be pit run or quarried material rough and angular in shape requiring approval by the *Departmental Representative* prior to being used in the work.
- .4 Material not to contain organic matter, frozen lumps, sod, roots, logs, stumps, excessive fines, or any other objectionable matter.

Section 35 31 24.1

Fisheries and Oceans Canada Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 5

.5 Core stone gradation shall be within the following limits:

IMPERIAL	METRIC	9
SIZE	SIZE	PASSING
		BY MASS
10"	250 mm	100
6"	150 mm	20 - 35
4"	100mm	0 - 10

.6 Material to be blended so that a homogeneous mix of smaller and larger sizes within the approved range is attained.

#### PART 3 - EXECUTION

- 3.1 Toe Protection
- 3.2 Construction Sequence
- .1 Excavate overburden and provide toe as shown on the plans.
- .1 Construction of new containment cell berm to begin prior to demolition, removal and salvage of existing filter stone and armour stone.
- .2 Construction of new containment cell to begin at the existing shoreline embankment and progress seaward to the outer end.
- .3 Schedule and carry out construction so that each phase of work is not left exposed longer than necessary.
- .4 Construct new containment cell berm in 6 m long sections while removing filter and armour stone from existing revetment to place in the new Work.
- .5 New armour stone and filter stone to be delivered to site as required to avoid exposing more than 15 m of the existing revetment at one time.
- .6 Alternative sequencing may be presented by

Fisheries and Oceans Canada Section 35 31 24.1 Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 6

the contractor for approval by the Departmental Representative based on site conditions at the time of construction.

## 3.3 Core Stone

- .1 Place core material in lifts and in sequence using suitable equipment to lines, grades and dimensions indicated on the plans.
- .2 Place material on harbour bottom to specified grades, and after the removal of kelp, debris, snow, ice, etc.
- .3 Execute work in such a manner to protect core material from storm wave action or tidal erosion damage. Replacement of material lost due to storm or erosion damage will be the responsibility of the Contractor.
- .4 Core stone material shall be placed by excavator. End dumping is not permissible. Contractor shall note that due to the side slopes of the breakwater that mechanical placing of the core will be necessary to produce the slopes and shapes required.
- .5 Grades, lines, dimensions, slope, and quantity of core, to be reviewed and approved by the *Departmental*Representative before proceeding with overlaying filter layers.

## 3.4 Filter Stone

- .1 Two underlayers are to be placed over the core stone.
- .2 Place filter layer material to lines, grades and dimensions indicated on the plans.
- .3 Place each filter stone individually using mechanical means to the lines, grades and dimensions shown on the plans. Do not dump filter units into place. Commence placement at toe of slope and proceed up the slope towards the crest. Place each

Section 35 31 24.1

Fisheries and Oceans Canada Containment Cell Construction Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 7

filter stone so that it is stable, secure on slope and supported by units below. Control placement of filter stone so as to produce a uniform and continuous cover over the underlying layer.

- .4 Replace filter stone units broken or damaged during placement. Damaged units to be removed from the work and will not be paid for.
- .5 Grades, lines, dimensions, slopes, and quantity of filter stone to be reviewed and approved by *Departmental*\*Representative before proceeding with the overlying armour layer.
- 3.5 Armour Stone
- .1 Place armour stone layer as shown on the plan to the lines, grades and dimensions shown on the plan.
- .2 Place each armour stone individually using mechanical means to the lines, grades and dimensions shown on the plans. Do not dump armour units into place. Commence placement at toe of slope and proceed up the slope towards the crest elevation.

  Place each unit so that it is stable and secure on slope and supported by units below. Control placement of armour units so as to produce a uniform and continuous cover.
- .3 Replace armour stone units broken or damaged during placement. Damaged units to be removed from the work and will not be paid for.
- 3.6 Existing Armour stone .1
  Filter stone and Core
  stone Removal, Salvage
  and Installation
- Remove, salvage and sort existing armour stone filter stone and core stone within designated areas shown on the plans.
- .2 Salvaged armour stone, filter stone and core stone to be incorporated into the new work as specified (where suitable).

Fisheries and Oceans Canada Section 35 31 24.1 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 8

#### 3.7 Tolerances

- .1 Completed component layers to be within following tolerances of line and grades indicated:
  - .1 Core stone: +50 mm
  - .2 Filter stone  $\pm 100$  mm
  - .3 Armour stone: +150 mm
  - .4 Armour crest: Minimum design elevation

#### 3.8 Cross Sections

- .1 During construction the Contractor shall submit cross-section sheets to the Departmental Representative showing the following:
  - .1 Cross-sections at stations every 10 metres along the breakwater slope.
  - .2 The design cross-section showing proposed core, filter, and armour stone in solid lines.
  - .3 Superimposed in dashed lines elevations taken at 2 metre intervals perpendicular to the centreline and at top and toe of slopes showing core, filter, and armour stone as constructed surfaces.
  - .4 Cross-sections to be referenced to the plan view of the breakwater with stations shown for reference.
  - .5 Cross-sections to be submitted as work at each station is completed for each class of stone. Next layer not to be placed until *Departmental Representative* has reviewed and approved the as-built elevations for underlying layer.
  - .6 After construction is complete and before the Final Certificate of Completion will be paid, Contractor to submit detailed as-built survey plan to Departmental Representative to show that contract grades and elevations have been achieved. Provide an electronic file and two sets of prints. The following minimum requirements to be met:
    - .1 Elevations every 10 metres along the centreline of the breakwater

Fisheries and Oceans Canada Section 35 31 24.1 Containment Cell Construction

Little Judique Ponds, Inverness County, N.S.

Project No.: C2-00155

Containment Cell

Page 9

and every 3 metres perpendicular to the centreline, on the end cone, and top and toe of slopes.

## 3.9 Protection

- .1 Take into account anticipated weather conditions and degree of exposure of site and tidal conditions in setting requirements for protection.
- .2 Schedule and carry out construction so that each phase of work is not left exposed longer than necessary. Place core stone, filter stone and armour stone concurrently in sections. Do not leave any more than 6 m new berm exposed to open water.
- .3 Progress of placement of core and stone to be recorded daily by Departmental Representative's inspector with Contractor's concurrence. Replacement of material lost due to storm wave action or tidal erosion damage to be based on daily journal of work progress and to be considered incidental to the work.

#### 3.10 Roadways

.1 Construction, maintenance, and removal of working roadway layers to be the responsibility of the Contractor and is to be considered incidental to the work.

# 3.11 Temporary Navigational Buoys

- .1 Maintain temporary buoys to mark the position of the outer end of the breakwater toe as construction proceeds.
- .2 All buoys are to meet the requirements of Canadian Coast Guard Standard TP968 and Section 01 10 10.
- .3 Coordinate the buoy installation with the local Harbour Authority.
- .4 Pay all costs associated with the supply, installation, and removal of all temporary navigational buoys.