

NRC-CNRC

**Real Property Planning and Management** 

# **SPECIFICATIONS**

**SOLICITATION #:** 23-58051

**BUILDING:** 100 Sussex,


Ottawa, Ontario

S77 Room B12 PD5, PD2 and PD6 Electrical PROJECT:

Panel Replacement

6295 PROJECT #:

Date: June 2023





# **SPECIFICATION**

TABLE OF CONTENTS	
Construction Tender Form	
Buy and Sell Notice	
Instructions to Bidders	
Ontario Sales Tax	
Acceptable Bonding Companies	
Articles of Agreement	
Plans and Specifications	Α
Terms of Payment	В
General Conditions	С
Labour Conditions and Fair Wage Schedule	D
N/A	
Insurance Conditions	E
<b>Contract Security Conditions</b>	F

G

**Security Requirement Check List** 

National Research Council	Conseil national de recherches
Canada	Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

# **Construction Tender Form**

S77 Room B12 PD5, PD2 and PD6 Electrical Panel Replacement **Project Identification** 

t Identi	<u>ication</u> Of A Room B12 1 Bo, 1 B2 and 1 Bo Electrical 1 and Replacement
Tende	er No.: 23-58051
Busin	ess Name and Address of Tenderer
Name	
	ess
Conta	ct Person(Print Name)
	hone () Fax: ()
<u>er</u>	
to as comp and o Amou	the Tenderer, hereby offer to His Majesty the King in Right of Canada (hereinafter referred 'His Majesty") represented by the National Research Council Canada to perform and lete the work for the above named project in accordance with the Plans and Specifications ther Tender Documents, at the place and in the manner set out therein for the Total Tender and (to be expressed in numbers only) of: \$ in lawful y of Canada (excluding GST/HST)
excep the O legisl	bove amount is inclusive of all applicable (*) Federal, Provincial and Municipal taxes t that in the event of a change in any tax imposed under the Excise Act, the Excise Tax Act ld Age Security Act, the Customs Act, the Customs Tariff or any provincial sales tax ation imposing a retail sales tax on the purchase of tangible personal property incorporated teal Property, that occurs
.1	after the date this tender was mailed or delivered, or

the amount of this offer shall be decreased or decreased in the manner provided for in GC22 of the General Conditions of the Contract Documents.

National Research Council	Conseil national de recherches
Canada	Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

# **1.3.1** Offer (continued)

(\*) For the purpose of this tender, the Goods and Services Tax (GST) is not to be considered as an applicable tax.

In the province of Quebec, the Quebec Sales Tax is not to be included in the tender amount because the Federal Government is exempt from this tax. Tenderers shall make arrangements directly with the provincial Revenue Department to recover any tax they may pay on good and servives acquired in the performance of this contract. However, tenderers should include in their tender amount Quebec Sales Tax for which an Input Tax Refund is not available.

# 1.4 Acceptance and Entry into Contract

I/We undertake, within fourteen (14) days of notification of acceptance of my/our offer, to sign a contract for the performance of the work provided I/we are notified, by the Department, of the acceptance of my/our offer within 30 days of the tender closing date.

# 1.5 <u>Construction Time</u>

I/We Agree to complete the work within the time stipulated in the specification from the date of notification of acceptance of my/our offer.

# 1.6 Bid Security

I/We herewith enclose tender security in accordance with Article 5 of the General Instruction to Tenderers.

I/We understand that if a security deposit is furnished as tender security and if I/we refuse to enter into a contract when called upon to do so, my/our security deposit shall be forfeited but the Minister may, if it is in the public interest, waive the right of His Majesty to forfeit the security deposit.

I/We understand that if the security furnished is not in the approved from as described in Article 5 of the General Instructions to Tenderers, my/our tender is subject to disqualification.

National Research Council	Conseil national de recherches
Canada	Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

# 1.7 <u>Contract Security</u>

Within fourteen (14) days after receipt of written notification of the acceptance of my/our offer, I/we will furnish contract security in accordance with the Contract Conditions "F" of the Contract Documents.

I/We understand that the contract security referred to herein, if provided in the form of a bill of exchange, will be deposited into the Consolidated Revenue Fund of Canada.

1.8	<u>Appendices</u>	<u>Appendices</u>	
	This Tender Form includes Appendix NoN/A	This Tender Form includes Appendix NoN/A_	

# 1.9 Addenda

The Total Tender Amount provides for the Work described in the following Addenda:

NUMBER	DATE	NUMBER	DATE

(Tenderers shall enter numbers and dates of addenda)

National Research Council	Conseil national de recherches
Canada	Canada
Finance and Procurement Services Branch	Direction des services financiers et d'approvisionnement

# 1.10 Execution of Tender

The Tenderer shall refer to Article 2 of the General Instructions to Tenderers.

# 1.11 Pricing Table

SIGNED, ATTESTED TO AND DELIVERED on theon behalf of	day of	
(Type or print the business name of the Tenderer)		
AUTHORIZED SIGNATORY (IES)		
(Signature of Signatory)		
(Print name & Title of Signatory)		
(Signature of Signatory)		
(Print name & Title of Signatory)		

**SEAL** 

# **Pricing Table**

ITEM	DESCRIPTION	PRICE
A	Proponent's lump sum bid for panel PD5	\$
В	Proponent's lump sum bid for panel PD2 and PD6	\$
C	<b>BID TOTAL</b> $(A + B = C)$	\$

### **BUY AND SELL NOTICE**

# S77 Room B12 PD5, PD2 and PD6 Electrical Panel Replacement

The National Research Council Canada, 100 Sussex Drive Ottawa, has a requirement for a project that includes:

Work under this contract covers the panel PD2, PD5 and PD6 replacement in the Council's Building S77 of the National Research Council.

# **Tender Destination**

Tenders are to be submitted by email only:
 National Research Council Canada

NRC.BidReceiving-ReceptiondesSoumissions.CNRC@nrc-cnrc.gc.ca

Endorsed "Tender for (insert title of work as it appears in the drawings and specifications)" and must bear the name and address of the tenderer.

b) Unless otherwise specified, the only documents required to be submitted with the tender are the Tender form and the Bid Security.

# 1. GENERAL

Questions regarding any aspect of the project are to be addressed to and answered only by the Departmental Representative (or his designate) or the Contracting Authority.

Any information received other than from the Departmental Representative (or his designate) or the Contracting Authority will be disregarded when awarding the contract and during construction.

Firms intending to submit tenders on this project should obtain tender documents through the Buyandsell.gc.ca TMA services provider. Addenda, when issued, will be available from the Buyandsell.gc.ca TMA service provider. Firms that elect to base their bids on tender documents obtained from other sources do so at their own risk and will be solely responsible to inform the tender calling authority of their intention to bid. Tender packages are not available for distribution on the actual day of tender closing.

# 2. MANDATORY SITE VISIT

It is mandatory that the bidder attends one of the site visits at the designated date and time. At least one representative from proponents that intend to bid must attend.

The site visits will be held on July 11<sup>th</sup> and July 12<sup>th</sup> 2023 at **10:00am**. Meet Mark O'Connor at 100 Sussex, Main Entrance, Ottawa, ON. Bidders who, for any reason, cannot attend at the specified date and time will not be given an alternative appointment to view the site and their tenders, therefore, will be considered as non-responsive. **NO EXCEPTIONS WILL BE MADE.** 

As proof of attendance, at the site visit, the Contracting Authority will have an Attendance Form which MUST be signed by the bidder's representative. It is the responsibility of all bidders to ensure they have signed the Mandatory Site Visit Attendance form prior to leaving the site. Proposals submitted by bidders who have not attended the site visit or failed to sign the Attendance Form will be deemed non-responsive.

# 3. CLOSING DATE

Closing date is August 1st, 2023, 14:00

### 4. TENDER RESULTS

Following the Tender closing, the tender results will be sent by email to all Contractors who submitted a tender.

# 5. SECURITY REQUIREMENT FOR CANADIAN CONTRACTORS

### 5.1 MANDATORY SECURITY REQUIREMENT:

This procurement contains a mandatory security requirement as follows:

- 1. The Contractor must, at all times during the performance of the Contract, hold a valid Designated Organization Screening (DOS), issued by the Canadian Industrial Security Director (CISD), Public Works Government Services Canada.
- 2. The Contractor personnel requiring access to sensitive work site(s) must EACH hold a valid RELIABILITY STATUS, granted or approved by CISD/PWGSC.
- 3. The Contractor must comply with the provisions of the:
  - a. Security Requirements Checklist attached at Appendix "D"
  - b. Industrial Security Manual (Latest Edition) available at: <a href="https://www.tpsgc-pwgsc.gc.ca/esc-src/msi-ism/index-eng.html">https://www.tpsgc-pwgsc.gc.ca/esc-src/msi-ism/index-eng.html</a>

### 5.2 VERIFICATION OF SECURITY CLEARANCE AT BID CLOSING

- 1. The Bidder must hold a valid Designated Organization Screening (DOS) issued by the Canadian Industrial Security Directorate (CISD), Public Works and Government Services Canada (PWGSC), TO BE INCLUDED WITH THEIR TENDER OR PROVIDED WITHIN 48 HOURS FROM THE DATE AND TIME OF TENDER CLOSING. Verifications will be made through CISD to confirm the security clearance status of the Bidder. Failure to comply with this requirement will render the bid non-compliant and no further consideration will be given to the bid.
- 2. Within 72 hours of tender closing, the General Contractor must name all of his sub-contractors, each of whom must hold a valid RELIABILITY STATUS, granted or approved by CISD/PWGSC, or any other Federal Department or Agency along with the names and birthdates or security clearance certificate numbers of all personnel who will be assigned to the project.
- 3. It is to be noted that any subcontractor required to perform any part of the work during the performance of the subsequent contract must also adhere to the mandatory security requirement of the contract. As well, no personnel without the required level of security will be allowed on site. It will be the responsibility of the successful bidder to ensure that the security requirement is met throughout the performance of the contract. The Crown will not be held liable or accountable for any delays or additional costs associated with the

contractor's non-compliance to the mandatory security requirement. Failure to comply with the mandatory security requirement will be grounds for being declared in default of contract.

4. For any enquiries concerning the project security requirement during the bidding period, the Bidder/Tenderer must contact the Security Officer @ 613-993-8956.

# 6. WSIB (WORKPLACE SAFETY AND INSURANCE BOARD)

All Bidders must provide a valid WSIB certificate with their Tender or prior to contract award.

### 7. OFFICE OF THE PROCUREMENT OMBUDSMAN

1. Clause for solicitation documents and regret letters for unsuccessful bidders

The Office of the Procurement Ombudsman (OPO) was established by the Government of Canada to provide an independent venue for Canadian bidders to raise complaints regarding the award of federal contracts under \$25,300 for goods and under \$101,100 for services. Should you have any issues or concerns regarding the award of a federal contract below these dollar amounts, contact OPO by e-mail at boa.opo@boa-opo.gc.ca, by telephone at 1-866-734-5169, or by web at www.opo-boa.gc.ca. For more information about OPO, including the available services, please visit the OPO website.

### 2. Contract Administration

The parties understand that the Procurement Ombudsman appointed pursuant to Subsection 22.1 (1) of the Department of Public Works and Government Services Act will review a complaint filed by the complainant respecting the administration of the Contract if the requirements of Subsection 22.2(1) of the Department of Public Works and Government Services Act and Sections 15 and 16 of the Procurement Ombudsman Regulations have been met.

To file a complaint, the Office of the Procurement Ombudsmai1 may be contacted by e-mail at boa.opo@boa-opo.gc.ca, by telephone at 1-866-734-5169, or by web at www.opo-boa.gc.ca.

# 3. Dispute Resolution

The Parties agree to make every reasonable eff01i, in good faith, to settle amicably all disputes or claims relating to or arising from the Contract, through negotiations between the Parties' representatives authorized to settle. If the Parties do not reach a settlement within 10 working days, each party hereby consents to fully participate in ai1d bear the cost of mediation led by the Procurement Ombudsman pt1rsuai1t to Subsection 22.1(3)(d) of the Department of Public Work and Government Services Act and Section 23 of the Procurement Ombudsman Regulations.

The Office of the Procurement Ombudsman may be contacted by telephone at 1-866-734-5169, by e-mail at boa.opo@boa-opo.gc.ca, or by web at www.opo-boa.gc.ca.

The Departmental Representative or his designate for this project is: Mark O'Connor

Mark.O'Connor@nrc-cnrc.gc.ca Telephone: (613) 301-3576

Contracting Authority for this project is: Collin Long

Collin.Long@nrc-cnrc.gc.ca

### **INSTRUCTIONS TO BIDDERS**

# Article 1 – Receipt of Tender

- Tender must be received <u>by email only</u> not later than the specified tender closing time. Electronic bids <u>received</u> after the indicated closing time <u>NRC servers received time</u> will be irrevocably rejected. Bidders are urged to send their proposal sufficient time in advance of the closing time to prevent any technical issues. NRC will not be held responsible for bids sent before closing time but received by the NRC servers after the closing time. <u>Tenders received after this time are invalid</u> and shall not be considered, regardless of any reason for their late arrival.
- 1b) A letter of printed telecommunication from a bidder quoting a price shall not be considered as a valid tender unless a formal tender has been received on the prescribed Tender Form.
- 1c) Bidders may amend their tenders by **email only** provided that such <u>amendments are received not</u> later than the specified tender closing time.
- 1d) Any amendments to the tender which are transmitted by **email only** must be signed and must clearly identify the tenderer.

All such amendments are to be addressed to: National Research Council of Canada Collin Long, Senior Contracting Officer

NRC.BidReceiving-ReceptiondesSoumissions.CNRC@nrc-cnrc.gc.ca

# Article 2 – Tender Form & Qualifications

- 1) All tenders must be submitted on the Construction Tender Form and the tender must be signed in compliance with the following requirements:
  - a) Limited Company: The full names of the Company and the name(s) and status of the authorized signing officer(s) must be printed in the space provided for that purpose. The signature(s) of the authorized officer(s) and the corporate seal must be affixed.
  - b) Partnership: The firm name and the name(s) of the person(s) signing must be printed in the space provided. One or more of the partners must sign in the presence of a witness who must also sign. An adhesive colored seal must be affixed beside each signature.

- c) Sole Proprietorship: The business name and the name of the sole proprietor must be printed in the space provided. The sole proprietor must sign in the presence of a witness who must also sign. An adhesive coloured seal must be affixed beside each signature.
- 2) Any alterations in the printed part of the Construction Tender Form or failure to provide the information requested therein, may render the tender invalid.
- 3) All space in the Construction Tender Form must be completed and any handwritten or typewritten corrections to the parts so completed must be initialed immediately to the side of the corrections by the person or persons executing the tender on behalf of the tenderer.
- 4) Tenders must be based on the plans, specifications and tender documents provided.
  - 5) A proposal submitted by a bidder who's Board of Directors or proprietor (s) are in majority the same as a former vendor who has declared bankruptcy while performing work for NRC over the last 7-years from the date of issuance of this RFP may be rejected and not eligible for award at NRC's sole discretion. In such case, NRC will advise the ineligible proponent(s).
  - 6) A proposal submitted by a bidder who has had a previous contracts cancelled by NRC due to lack of performance within 3 years from the issuance date of this RFP may be rejected and not eligible for award at NRC's sole discretion. In such case, NRC will advise the ineligible proponent (s).
  - 7) If there is discrepancy between the English version and the French version of this document and any of the attachments and amendments, the English version will takes precedence.
  - 8) The Council does not bind itself to accept the lowest or any tender.

# Article 3 - Contract

1) The Contractor will be required to sign a contract similar to the Standard Contract Form for Fixed Price Construction Contracts, a blank specimen of which is enclosed in the package for reference purposes.

# <u>Article 4</u> – Tender Destination

1a) Tenders are to be submitted by email only: National Research Council Canada

NRC.BidReceiving-ReceptiondesSoumissions.CNRC@nrc-cnrc.gc.ca

Endorsed "Tender for (insert title of work as it appears in the drawings and specifications)" and must bear the name and address of the tenderer.

1b) Unless otherwise specified, the only documents required to be submitted with the tender are the Tender form and the Bid Security.

# Article 5 - Security

1a) Bid Security is required and must be submitted in one of the following forms:

- i) bonds of the Government of Canada, or bonds unconditionally guaranteed as to principal and interest by the Government of Canada; **OR**
- ii) a bid bond.
- 1b) Regardless of the Bid Security submitted, it should never be more than \$250,000 maximum, calculated at 10% of the first \$250,000 of the tendered price, plus 5% of any amount in excess of \$250,000.
- 1c) Bid Security shall accompany each tender or, if forwarded separately from the tender, shall be provided not later than the specified tender closing time. Bid bond or E-bond Security must be in the <u>ORIGINAL</u> form. PDF via email is acceptable. <u>FAILURE TO PROVIDE THE REQUIRED BID SECURITY SHALL INVALIDATE THE TENDER.</u>
- 1d) The successful tenderer is required to provide security within 14 days of receiving notice of tender acceptance. The tenderer must furnish EITHER:
  - i) a Security Deposit as described in 1(b) above together with a Labour and Material Payment Bond in the amount of at least 50% of the amout payable under the contract, OR
  - ii) a Performance Bond and a Labour and Material Payment Bond each in the amount of 50% of the amount payable under the contract.
- 1e) Bonds must be in an approved form and from the companies whose

bonds are acceptable to the Government of Canada. Samples of the approved form of Bid Bond, Performance Bond and Labour and Material Payment Bond and a list of acceptable Bonding Companies may be obtained from the Contracting Officer, National Research Council, Building M-58, Montreal Road, Ottawa, Ontario, K1A 0R6.

# Article 7 - Sales Tax

- 1) The amount of the tender shall include all taxes as levied under the Excise Act, the Excise Tax Act, the Old Age Security Act, the Customs Act or the Customs Tariff, in force or applicable at the time.
- In Quebec, the Provincial Sales Tax should not be included in the Tender Price as the Federal Government is exempt. Tenderers should contact the Provincial Revenue Minister to recover all taxes paid for goods and services rendered under this contract.

Tenderers must include in their Tender Price the amount of Provincial Sales Tax for which the exemption does not apply.

# Article 8 - Examination of Site

All parties tendering shall examine the sites of the proposed work before sending in their tender and make themselves thoroughly acquainted with the same and obtain for themselves any and all information that may be necessary for the proper carrying out of the Contract. No after claim will be allowed or entertained for any work or material that may be requisite and necessary for the proper execution and completion of this Contract with the exception of that provided for under GC 35 in the General Conditions of the General Specification.

# Article 9 - Discrepancies, Omissions, Etc.

- 1a) Bidders finding discrepancies in, or omissions from, drawings, specifications or other documents, or having any doubt as to the meaning or intent of any part thereof, should at once notify the Engineer who will send written instructions or explanation to all bidders.
- 1b) Neither the Engineer nor the Council will be responsible for oral instructions.
- Addenda or corrections issued during the time of the bidding shall be covered in the proposal. However, the contract supersedes all communications, negotiations and agreements, either written or oral, relating to the work and made prior to the date of the contract.

# Article 10 - No additional Payments for Increased Costs

1) The only other adjustments in the contract price allowed are those specified in the General Conditions of the General Specification. The contract price will not be amended for change in freight rates, exchange rates, wage rates or cost of materials, plant or services.

# Article 11 - Awards

- 1a) The Council reserves the power and right to reject tenders received from parties who cannot show a reasonable acquaintance with and preparation for the proper performance of the class of work herein specified and shown on plans. Evidence of such competence must be furnished by the tenderers if required to do so.
- 1b) A tenderer may be required to furnish to the Contracting Office, National Research Council of Canada, Building M-58, 1200 Montreal Road, Ottawa, Ontario, K1A 0R6, Canada, unsigned copies of the insurance requirements as covered by the Insurance Conditions of the General Specification.
- 1c) The Council will accept the Lowest Compliant Bid for Contract Award.

# Article 12 - Harmonized Sales Tax

The Harmonized Sales Tax (HST) which in now in effect shall be considered an applicable tax for the purpose of this tender. However, the bidder shall <u>NOT</u> include any amount in the bid price for said HST. The successful contractor will indicate on each application for payment as a separate amount the appropriate HST the Owner is legally obliged to pay. This amount will be paid to the Contractor in addition to the amount certified for payment under the Contract in addition to the amount certified for payment under the Contract and will therefore not affect the Contract Price. The Contractor agrees to remit any HST collected or due to Revenue Canada.

# **Non-resident contractors**

RST guide 804 Published August 2006

ISBN: 1-4249-2007-8 (Print), 1-4249-2009-4 (PDF), 1-4249-2008-6 (HTML)

### **Publication Archived**

**Notice to the reader: For Retail Sales Tax (RST)** – On July 1, 2010 the 13 per cent Harmonized Sales Tax (HST) took effect in Ontario replacing the existing provincial Retail Sales Tax (RST) and combining it with the federal Goods and Services Tax (GST). As a result, RST provisions described on this page and in other publications ended on June 30, 2010.

Effective July 1, 2010 this publication was archived for RST purposes **only**. Use caution when you refer to it, since it reflects the law in force for RST at the time it was released and may no longer apply.

• The information in this Guide explains the Retail Sales Tax (RST) responsibilities of a non-resident contractor who is awarded a construction contract to perform work in Ontario and their Ontario customers. Please note that this Guide replaces the previous version dated March 2001.

# Non-Resident Contractor Defined

A non-resident contractor is a contractor located outside Ontario who has been awarded a construction contract to perform work in Ontario, and who has not maintained a permanent place of business in Ontario continuously for twelve months immediately prior to signing the contract, or which is not a company incorporated under the laws of Ontario. A construction contract is a contract for the erection, remodelling or repair of a building or other structure on land.

A contractor is a person who is in the business of constructing, altering, repairing or improving real property and includes, but is not limited to,

- 1. a general contractor and subcontractor,
- 2. a carpenter, bricklayer, stonemason, electrician, plasterer, plumber, painter, decorator, paver, and bridge builder,
- 3. a sheet metal, tile and terrazzo, heating, air conditioning, insulation, ventilating, papering, road, roofing and cement contractor, who installs or incorporates items into real property. (See RST <u>Guide 206 Real Property and Fixtures</u>).

# Registration and Guarantee Deposit

Non-resident contractors who are awarded a construction contract in Ontario are required to register with the Ministry of Finance (ministry), Centralized Programs Unit and post a guarantee equal to 4 per cent of the total of each Ontario contract. The guarantee can be paid in cash, by certified cheque (payable to the Minister of Finance), letter of credit or by a guarantee bond.

To register with the ministry and to obtain further information on posting a guarantee, contractors should contact the ministry's Centralized Programs Unit, 33 King Street West, PO Box 623, Oshawa, Ontario, L1H 8H7, toll-free 1 866 ONT-TAXS (1 866 668-8297) or fax to 905 435-3617.

Non-resident contractors who sell taxable goods on a supply only basis to Ontario customers, or provide taxable services in Ontario, may obtain a regular Vendor Permit to collect and remit RST on their sales. Non-resident contractors who have been issued a regular Vendor Permit must still register separately with the ministry and post a guarantee if they are awarded a construction contract in Ontario.

# Letter of Compliance

After receiving the guarantee, the ministry mails out two copies of a "letter of compliance" to the contractor certifying the Retail Sales Tax (RST) requirements have been met. Contractors must give a copy of the letter to their customers.

If a copy of the compliance letter is not provided, the customer must withhold 4 per cent of all amounts payable to the non resident contractor and pay the withheld amounts to the Minister of Finance (minister). Details relating to the contract should be sent along with the payments to the Centralized Programs Unit. Customers may give the minister a guarantee bond equal to 4 per cent of the total contract price instead of making the 4 per cent payments.

Note: Customers who do not follow these requirements may be held liable for 4 per cent of all amounts payable to the non resident contractor or any other amount that the Ministry deems to be the RST payable resulting from the performance of the contract.

# Calculation of RST

### Fair Value

RST is payable on the "fair value" of materials, purchased or brought into Ontario, to be used for work performed in Ontario. "Fair value" includes:

- the purchase price in Canadian funds;
- all charges by the supplier for handling and delivery, and
- any federal customs duties and excise taxes paid (but not the federal Goods and Services Tax (GST)).

Contractors are also required to pay RST to Ontario suppliers on the purchase, rental or lease of taxable services, materials, machinery, or equipment.

# Machinery and Equipment - Leased

If machinery or equipment is leased from a supplier outside Ontario and brought into the province, RST is payable on the lease payments for the period the machinery or equipment is in Ontario.

# Machinery and Equipment - Owned by Contractor

If machinery or equipment is owned by the contractor, RST may be calculated in one of the following ways:

a. If a contractor brings machinery and equipment into Ontario for less than 12 months' use, RST is to be calculated using the following formula:

1/36 x net book value at date of import x number of months in Ontario x tax rate

For the purpose of this formula, RST is payable for each month or part of a month that the goods are in Ontario. A month is considered 31 consecutive days and a part month is considered more than 12 days. The RST payable is based on the number of days the machinery and equipment are located in Ontario and not the number of days the items are actually used.

Example: Equipment is brought into Ontario on March 28 and taken out on May 8. The items were in the province for 41 days. RST is payable on the first 31 days' temporary stay in Ontario vs. use of the equipment. Since the remainder (10 days) is not considered part of a month, no RST is payable on this portion.

b. If, at the time the goods are brought into Ontario, it is expected that the machinery or equipment will be in Ontario for more than twelve months, contractors must pay Retail Sales Tax (RST) on the following basis:

net book value at date of import x tax rate

If, at the time of import, the length of time is not known, vendors may use the formula under (a). If they later find it necessary to keep the machinery and equipment in Ontario for more than 12 months, the RST paid under (a) may be deducted from the RST payable under (b).

Using formula (a) or (b) above, contractors will calculate and remit the RST payable on the return that is filed when the contract is finished.

(See Completion of Contract section)

# Manufacturing for Own Use

Contractors may need to manufacture items, such as doors and windows, for their construction contracts. Manufacturing is work done in a factory away from a construction site, or in a mobile unit or workshop that is on or near the construction site. Manufacturing occurs when raw materials are changed into manufactured goods for use in real property contracts.

Contractors are considered to be manufacturing contractors if they produce goods:

- 1. for their own use in real property contracts, and
- 2. the manufactured cost of the goods is more than \$50,000 a year.

(See RST Guide 401 - Manufacturing Contractors)

# Contracts with the Federal Government

Where a non-resident contractor enters into a construction contract with the federal government, for the construction of a building and/or the installation of equipment, the nature of the equipment will determine whether the contract should be let on a tax-included or tax excluded basis.

Contracts for the construction of a building and the installation of equipment that directly services that building (i.e., elevators, escalators, light fixtures, central heating and air conditioning, etc.) should be tendered on a tax -included basis. Contractors are the consumers of the materials used in fulfilling these contracts and must pay or account for RST on the materials used to complete the contracts. There is NO exemption just because the contract is with the federal government.

Contracts for the installation of equipment that becomes a fixture and does not directly service a building (i.e., material handling equipment, production machinery, communication equipment, training equipment) may be tendered on a tax-excluded basis. Contractors engaged in contracts of this nature are permitted to make tax exempt purchases of such equipment by issuing a valid Purchase Exemption Certificate (PEC) to their supplier. Only non-resident contractors who have registered with the ministry and posted a guarantee may issue a PEC.

# Exemptions

Contractors may supply and install equipment or materials for certain customers that may be entitled to an exemption from RST (e.g., manufacturers, Indian band councils, farmers and diplomatic organizations). The equipment or materials, when installed, becomes real property if it is permanently attached to land, or a fixture if it is permanently attached to a building or real property structure. Since

contractors are liable for RST, they should contact the ministry to find out if the customer qualifies for exemption before tendering the contract on a tax-excluded basis.

# Status Indians, Indian Bands and Band Councils

Non-resident contractors may purchase building materials exempt from Retail Sales Tax (RST) for certain buildings and structures situated on reserves. The cost of such projects must be paid by the band council, and the buildings must provide a community service for the reserve. Contracts for the construction of an exempt community building project should be made on an RST-excluded basis. Non-resident contractors may purchase the materials exempt from RST by providing suppliers with a valid Purchase Exemption Certificate (PEC). As noted previously, only non-resident contractors who have registered with the ministry and posted a guarantee may issue a PEC. (See RST Guide 204 - Purchase Exemption Certificates).

Non-resident contractors must pay RST on items purchased for incorporation into a building or structure built for individual status Indians on a reserve. (See RST <u>Guide 808 - Status Indians, Indian Bands and Band Councils</u>).

# Completion of Contract

When a contract is completed, non-resident contractors who were required to post a guarantee must complete a <u>Non-Resident Contractor Retail Sales Tax Return [PDF - 92 KB]</u> that is provided by the ministry.

If a contractor's guarantee was given in cash or by certified cheque, the amount of the deposit can be deducted from the RST liability owed by the contractor. If the liability is greater than the deposit, the amount remaining must be paid by the contractor. If the deposit is more than the liability, the contractor will receive a refund.

If a guarantee bond was posted instead of cash, the bond will be discharged once the RST liability is paid in full.

All returns are subject to audit.

# Legislative References

- Retail Sales Tax Act, Subsections 19(2) and 39(3)(4) and (5)
- Regulation 1012 under the Act, Subsections 15.3(1)(2)(5)(6) and (7)
- Regulation 1013 under the Act, Sections 1 and 3

### For More Information

The information contained in this publication is only a guideline. For more information, please contact the Ontario Ministry of Finance at 1 866 ONT-TAXS (1 866 668-8297) or visit our website at ontario.ca/finance.

# **Acceptable Bonding Companies**

Published September 2010

The following is a list of insurance companies whose bonds may be accepted as security by the government.

# 1. Canadian Companies

- ACE INA Insurance
- Allstate Insurance Company of Canada
- Ascentus Insurance Ltd. (Surety only)
- Aviva Insurance Company of Canada
- AXA Insurance (Canada)
- AXA Pacific Insurance Company
- Canadian Northern Shield Insurance Company
- Certas Direct Insurance Company (Surety only)
- Chartis Insurance Company of Canada (formerly AIG Commercial Insurance Company of Canada)
- Chubb Insurance Company of Canada
- Commonwealth Insurance Company
- Co-operators General Insurance Company
- CUMIS General Insurance Company
- The Dominion of Canada General Insurance Company
- Echelon General Insurance Company (Surety only)
- Economical Mutual Insurance Company
- Elite Insurance Company
- Everest Insurance Company of Canada
- Federated Insurance Company of Canada
- Federation Insurance Company of Canada
- Gore Mutual Insurance Company
- Grain Insurance and Guarantee Company
- The Guarantee Company of North America
- Industrial Alliance Pacific General Insurance Corporation
- Intact Insurance Company
- Jevco Insurance Company (Surety only)
- Lombard General Insurance Company of Canada
- Lombard Insurance Company
- Markel Insurance Company of Canada
- The Missisquoi Insurance Company
- The Nordic Insurance Company of Canada
- The North Waterloo Farmers Mutual Insurance Company (Fidelity only)
- Novex Insurance Company (Fidelity only)
- The Personal Insurance Company
- Pilot Insurance Company
- Quebec Assurance Company
- Royal & Sun Alliance Insurance Company of Canada
- Saskatchewan Mutual Insurance Company
- · Scottish & York Insurance Co. Limited
- The Sovereign General Insurance Company
- TD General Insurance Company
- Temple Insurance Company
- Traders General Insurance Company

- Travelers Guarantee Company of Canada
- Trisura Guarantee Insurance Company
- The Wawanesa Mutual Insurance Company
- Waterloo Insurance Company
- Western Assurance Company
- Western Surety Company

# 2. Provincial Companies

Surety bonds issued by the following companies may be accepted provided that the contract of suretyship was executed in a province in which the company is licensed to do business as indicated in brackets.

- AXA Boreal Insurance Company (P.E.I., N.B., Que., Ont., Man., B.C.)
- AXA Boreal Insurance Company (P.E.I., N.B., Que., Ont., Man., B.C.)
- ALPHA, Compagnie d'Assurances Inc. (Que.)
- Canada West Insurance Company (Ont., Man., Sask, Alta., B.C., N.W.T.) (Surety only)
- The Canadian Union Assurance Company (Que.)
- La Capitale General Insurance Inc. (Nfld. & Lab., N.S., P.E.I., Que.(Surety only), Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- Coachman Insurance Company (Ont.)
- Continental Casualty Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- GCAN Insurance Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- The Insurance Company of Prince Edward Island (N.S., P.E.I., N.B.)
- Kingsway General Insurance Company (N.S., N.B., Que., Ont., Man., Sask., Alta., and B.C.)
- Liberty Mutual Insurance Company (Nfld. & Lab., N.S., P.E.I., N.B., Que., Ont., Man., Sask., Alta., B.C., Nun., N.W.T., Yuk.)
- Manitoba Public Insurance Corporation (Man.)
- Norgroupe Assurance Générales Inc.
- Orleans General Insurance Company (N.B., Que., Ont.)
- Saskatchewan Government Insurance Office (Sask.)
- SGI CANADA Insurance Services Ltd. (Ont., Man., Sask., Alta.)
- L'Unique General Insurance Inc. (Nfld. & Lab., N.S., P.E.I., N.B., Que.(Surety only), Ont.(Surety only), Man., Sask., Alta., B.C.(Surety only), Nun., N.W.T., Yuk.)

# 3. Foreign Companies

- Aspen Insurance UK Limited
- Compagnie Française d'Assurance pour le Commerce Extérieur (Fidelity only)
- Eagle Star Insurance Company Limited
- Ecclesiastical Insurance Office Public Limited Company (Fidelity only)
- Lloyd's Underwriters
- Mitsui Sumitomo Insurance Company, Limited
- NIPPONKOA Insurance Company, Limited
- Sompo Japan Insurance Inc.
- Tokio Marine & Nichido Fire Insurance Co., Ltd.
- XL Insurance Company Limited (Surety only)
- Zurich Insurance Company Ltd

# Standard Construction Contract – Articles of Agreement (23/01/2002)

- A1 Contract Documents
- A2 Date of Completion of Work and Description of Work
- A3 Contract Amount
- A4 Contractor's Address
- A5 Unit Price Table

These Articles of Agreement made in duplicate this day of

Between

**Her Majesty the Queen**, in right of Canada (referred to in the contract documents as "Her Majesty") represented by the National Research Council Canada (referred to in the contract documents as the "Council")

and

(referred to in the contract documents as the "Contractor")

Witness that in consideration for the mutual promises and obligations contained in the contract, Her Majesty and the Contractor covenant and agree as follows:

### A1 Contract Documents

### (23/01/2002)

- 1.1 Subject to A1.4 and A1.5, the documents forming the contract between Her Majesty and the Contractor, referred to herein as the contract documents, are
  - 1.1.1 these Articles of Agreement,
  - 1.1.2 the document attached hereto, marked "A" and entitled "Plans and Specifications", referred to herein as the Plans and Specifications,
  - 1.1.3 the document attached hereto, marked "B" and entitled "Terms of Payment", referred to herein as the Terms of Payment,
  - 1.1.4 the document attached hereto, marked "C" and entitled "General Conditions", referred to herein as the General Conditions,
  - 1.1.5 the document attached hereto, marked "D" and entitled "Labour Conditions", referred to herein as the Labour Conditions,
  - 1.1.6 the document attached hereto, marked "E" and entitled "Insurance Conditions", referred to herein as the Insurance Conditions,
  - 1.1.7 the document attached hereto, marked "F" and entitled "Contract Security Conditions", referred to herein as the Contract Security Conditions, and
  - 1.1.8 any amendment or variation of the contract documents that is made in accordance with the General Conditions.
  - 1.1.9 the document entitled Fair Wage Schedules for Federal Construction Contracts referred to herein as Fair Wage Schedules
  - 1.1.10

The Council hereby designates of of the Government of Canada as the Engineer for the purposes of the contract, and for all purposes of or incidental to the contract, the Engineer's address shall be deemed to be:

# 1.2 In the contract

- 1.3.1 "Fixed Price Arrangement" means that part of the contract that prescribes a lump sum as payment for performance of the work to which it relates; and
- 1.3.2 "Unit Price Arrangement" means that part of the contract that prescribes the product of a price multiplied by a number of units of measurement of a class as payment for performance of the work to which it relates.
- 1.3 Any of the provisions of the contract that are expressly stipulated to be applicable only to a Unit Price Arrangement are not applicable to any part of the work to which a Fixed Price Arrangement is applicable.
- 1.4 Any of the provisions of the contract that are expressly stipulated to be applicable only to a Fixed Price Arrangement are not applicable to any part of the work to which a Unit Price Arrangement is applicable.
- A2 Date of Completion of Work and Description of Work **(23/01/2002)**
- 2.1 The contractor shall, between the date of these Articles of Agreement and the , in the careful and workmanlike manner, diligently perform and complete the following work:

which work is more particularly described in the Plans and Specifications, including addendum(s).

# A3 Contract Amount

# (23/01/2002)

- 3.1 Subject to any increase, decrease, deduction, reduction or set-off that may be made under the Contract, Her Majesty shall pay the Contractor at the times and in the manner that is set out or referred to in the Terms of Payment
  - 3.1.1 the sum of (GST/HST extra), in consideration for the performance of the work or the part thereof that is subject to Fixed Price Arrangement, and
  - 3.1.2 a sum that is equal to the aggregate of the products of the number of units of Measurement of each class of labour, plant and material that is set out in a Final Certificate of Measurement referred to in GC44.8 multiplied in each case by the appropriate unit price that is set out in the Unit Price Table in consideration for the performance of the work or the part thereof that is subject to a Unit Price Arrangement.
- 3.2 For the information and guidance of the Contractor and the persons administering the contract on behalf of Her Majesty, but not so as to constitute a warranty, representation or undertaking of any nature by either party, it is estimated that the total amount payable by Her Majesty to the Contractor for the part of the work to which a Unit Price Arrangement is applicable will be approximately \$N/A
- 3.3 A3.1.1 is applicable only to a Fixed Price Arrangement.
- 3.4 A3.1.2 and A3.2 applicable only to a Unit Price Arrangement.

# A4 Contractor's Address

# (23/01/2002)

4.1 For all purposes of or incidental to the contract, the Contractor's address shall be deemed to be:

# A5 Unit Price Table

# (23/01/2002)

Her Majesty and the Contractor agree that the following table is the Unit Price Table for the purposes of the contract.

Column 1 Item	Column 2 Class of Labour Plant	Column 3 Unit of Measurement	Column 4 Estimated Total Quantity	Column 5 Price per Unit	Column 6 Estimated Total Price
	Or Material				
					<b></b>
		N/A			

- 5.2 The Unit Price Table that is set out in A5.1 designates the part of the work to which a Unit Price Arrangement is applicable.
- 5.3 The part of the work that is not designated in the Unit Price Table referred to in A5.2 is the part of the work to which a Fixed Price Arrangement is applicable.

Signed on behalf of Her Majesty by	
as Senior Contracting Officer	_
and	
as	_
of the National Research Council Canada	
on the	
day of	
Signed, sealed and delivered by	
asPosition	and
by	_
asPosition	Seal
of	
on the	_
day of	

NRC-CNRC	Table of Contents	00 01 10
Project No.		Page 1 of 1
S77- 6295		-

Pa	ges
Division 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS	
Section 00 01 10 - Table of Contents	.1
Division 01 - GENERAL REQUIREMENTS	
Section 01 10 00 - General Instructions1	3
Section 01 15 45 - General and Fire Safety Requirements	.6
Section 01 74 19 - Waste Management and Disposal	8
Division 02 – EXISTING CONDITIONS	
Section 02 42 00 - Removal and Salvage of Construction Materials	3
Division 26 – ELECTRICAL	
Section 26 05 00 - Common Work Results for Electrical	10
Section 26 05 05 - Selective Demolition for Electrical	5
Section 26 05 20 - Wire and Box Connection 0 – 1000V	2
Section 26 05 21 - Wires and Cables 0 -1000V	3
Section 26 05 22 - Connectors and Terminations	2
Section 26 05 34 – Conduits and Conduits Fastening and Conduit Fittings4	4

END OF TABLE

# 1. SCOPE OF WORK

.1 Work under this contract covers the panel PD2, PD5 and PD6 replacement in the Council's Building S77 of the National Research Council.

### 2. DRAWINGS

.1 The following drawings illustrate the work and form part of the contract documents:

6295-E01 PD5 SINGLE LINE DIAGRAM AND FLOOR PLAN

6295-E02 PD2, PD6 SINGLE LINE DIAGRAM AND FLOOR PLAN

### 3. COMPLETION

.1 Complete all work within 48 week(s) after receipt of notification of acceptance of tender.

# 4. GENERAL

- .1 The word "provide" in this Specification means to supply and install.
- .2 Provide items mentioned in either the drawings or the specification.

# 5. SPECIFIED ACCEPTABLE & ALTERNATIVE EQUIPMENT & MATERIALS

- .1 Materials and equipment scheduled and/or specified on the drawings or in the specifications have been selected to establish a performance and quality standard. In most cases, acceptable manufacturers are stated for any material or equipment specified by manufacturer's name and model number. Contractors may base their tender price on materials and equipment supplied by any of the manufacturers' names as acceptable for the particular material or equipment.
- .2 In addition to the manufacturers specified or named as acceptable, you may propose alternative manufacturers of materials or equipment to the Departmental Representative for acceptance. For a product to be considered as an alternative product substitute, make a written application to the Departmental Representative during the tender period, not later than ten (10) working days before tender closing.
- .3 Certify in writing that the alternative meets all requirements of the specified material or equipment. In addition, it shall be understood that all costs required by or as a result of acceptance or proposed alternatives, will be borne by the Contractor.
- .4 Approval of alternatives will be signified by issue of an Addendum to the Tender Documents.
- .5 Any alternative manufacturers or materials submitted which are incomplete and cannot be evaluated, or are later than ten (10) working days before tender closing date or after the tender period, will not be considered.

# 6. MINIMUM STANDARDS

- .1 Conform to or exceed minimum acceptable standards of the various applicable federal, provincial and municipal codes such as The National Building Code, The National Fire Code, Canadian Plumbing Code, Canadian Electrical Code, Canadian Code for Construction Safety and the Provincial Construction Safety Act.
- .2 Work to conform to referenced standards and codes as reaffirmed or revised to date of specification.

# 7. WORKPLACE HAZARDOUS MATERIAL INFORMATION SYSTEM (WHMIS)

- .1 The General Contractor shall comply with Federal and Provincial legislation regarding the WHMIS. The Contractor's responsibilities include, but are not limited to the following:
  - .1 To ensure that any controlled product brought on site by the Contractor or subcontractor is labeled;
  - .2 To make available to the workers and the Departmental Representative, Material Safety Data Sheets (MSDS) for these controlled products;
  - .3 To train own workers about WHMIS, and about the controlled products that they use on site;
  - .4 To inform other Contractors, sub-contractors, the Departmental Representative, authorized visitors and outside inspection agency personnel about the presence and use of such products on the site.
  - .5 The site foreman or superintendent must be able to demonstrate, to the satisfaction of the Departmental Representative, that he/she has had WHMIS training and is knowledgeable in its requirements. The Departmental Representative can require replacement of this person if this condition or implementation of WHMIS is not satisfactory

# 8. REQUIREMENTS OF BILL 208, SECTION 18(a)

Under the requirements of Bill 208 of the Ontario Ministry of Labour Occupational Health & Safety Act, the following designated substances may be encountered while performing the work described in these contract documents:

- .1 Acrylonitrile, Isocyanates, Arsenic, Lead, Asbestos, Mercury, Benzene, Silica, Coke Oven Emissions, Vinyl Chloride, and Ethylene Oxide
  - .1 It is the responsibility of the General Contractor to ensure that each prospective sub-contractor for this project has received a copy of the above list.
  - .2 In addition to the above designated substances, the following may also be present:

# 9. COST BREAKDOWN

- .1 Submit, for approval by the Departmental Representative, a cost breakdown of tender 72 hours after the contract is awarded.
- .2 Use the approved cost breakdown as the basis for submitting all claims.

- .3 Request Departmental Representative's verbal approval to amount of claim prior to preparing and submitting the claim in its final form.
- .4 Contractor costs associated with compliance with occupational health and safety requirements (Canada Labour Code) related to the Coronavirus/COVID-19 pandemic must be included in the initial bid price. These costs may include, but are not limited to, the provision of additional personal protective equipment (PPE) and social distancing requirements as required to complete the project. Contractor must review and incorporate into initial bid pricing compliance with any Coronavirus/COVID-19 related health and safety guidance issued by the local Medical Officer of Health (applicable in the jurisdiction of the project), the Public Health Agency of Canada, Health Canada and/or the provincial Ministry of Health, as applicable.

# 10. SUB-TRADES

.1 Submit no later than 72 hours after tender closing, a complete list of sub trades for the Departmental Representative's review.

# 11. PERSONNEL SECURITY AND IDENTIFICATION

- .1 All persons employed by the Contractor, or by any sub-contractor and present on the site must be security cleared in accordance with the requirements of the Section entitled Special Instructions to Tenderers.
- .2 All such persons must wear and keep visible identification badges as issued by the Security Office of NRC.

# 12. WORKING HOURS AND SECURITY

- .1 Normal working hours on the NRC property are from 8:00 a.m. until 4:30 p.m., Monday to Friday inclusive, except statutory holidays.
- .2 At all other times, special written passes are required for access to the building site.
- .3 Before scheduling any work outside normal working hours, obtain permission from the Departmental Representative to perform the specific tasks.
- .4 An escort may be required whenever working outside normal hours. Contractor to bear the associated costs.

# 13. SCHEDULE

- .1 The Contractor shall prepare a detailed schedule, fixing the date for commencement and completion of the various parts of the work and update the said schedule. Such schedule shall be made available to the Departmental Representative not later than two weeks after the award of the contract and prior to commencement of any work on site.
- .2 Notify Departmental Representative in writing of any changes in the schedule.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
S77-6295	Page 4 of 13

.3 14 day(s) before the scheduled completion date, arrange to do an interim inspection with the Departmental Representative.

# 14. PROJECT MEETINGS

- .1 Hold regular project meetings at times and locations approved by the Departmental Representative.
- .2 Notify all parties concerned of meetings to ensure proper coordination of work.
- .3 Departmental Representative will set times for project meetings and assumes responsibility for recording and distributing minutes.

# 15. SHOP DRAWINGS

- .1 Submit to Departmental Representative for review, shop drawings, product data and samples specified within 4 week(s) after contract award.
- .2 Submit to Departmental Representative for review a complete list of all shop drawings, product data and samples specified and written confirmation of corresponding delivery dates within one (1) week after shop drawings, product data and samples approval date. This list shall be updated on a 2 week basis and any changes to the list shall be immediately notified in writing to the Departmental Representative.
- .3 Review shop drawings, data sheets and samples prior to submission.
- .4 Submit one (1) electronic copy of all shop drawings and product data and samples for review, unless otherwise specified.
- .5 Review of shop drawings and product data by the Departmental Representative does not relieve the Contractor of the responsibility for errors and omissions and for the conformity with contract documents.

# 16. SAMPLES AND MOCK-UPS

- .1 Submit samples in sizes and quantities as specified.
- .2 Where colour, pattern or texture is criterion, submit full range of samples.
- .3 Construct field samples and mock-ups at locations acceptable to Departmental Representative.
- .4 Reviewed samples or mock-ups will become standards of workmanship and material against which installed work will be checked on the project.

# 17. MATERIALS AND WORKMANSHIP

.1 Install only new materials on this project unless specifically noted otherwise.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
<u>\$77-6295</u>	Page 5 of 13

Only first class workmanship will be accepted, not only with regard to safety, efficiency, durability, but also with regard to neatness of detail and performance.

# 18. WORK & MATERIALS SUPPLIED BY OWNER

- .1 Work and materials not included in this contract are described on this specification.
- .2 Deliver to a storage place, as directed by the Departmental Representative, all materials returned to the Owner.
- .3 Unless otherwise specified, accept owner-supplied materials at their storage location and provide all transportation as required.
- .4 General Contractor's duties:
  - .1 Unload at site.
  - .2 Promptly inspect products and report damaged or defective items.
  - .3 Give written notification to the Departmental Representative for items accepted in good order.
  - .4 Handle at site, including uncrating and storage.
  - .5 Repair or replace items damaged on site.
  - .6 Install, connect finished products as specified.

### 19. SITE ACCESS

- .1 Make prior arrangements with the Departmental Representative before starting work or moving materials and equipment on site.
- .2 Obtain approval of Departmental Representative for regular means of access during the construction period.
- .3 Obtain approval of Departmental Representative before temporarily suspending operations on site; before returning to the site and before leaving the site at the end of the job.
- .4 Provide and maintain access to site.
- .5 Build and maintain temporary roads and provide snow removal during period of work.
- .6 Provide snow clearing and removal as required during the contract period.
- .7 Make good any damage and clean up dirt, debris, etc., resulting from Contractor's use of existing roads.

# 20. USE OF SITE

- .1 Restrict operations on the site to the areas approved by the Departmental Representative
- .2 Locate all temporary structures, equipment, storage, etc., to the designated areas.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
S77-6295	Page 6 of 13

.3 Restrict parking to the designated areas.

# 21. ACCEPTANCE OF SITE

- .1 Inspect the site before commencing work, review any unexpected conditions with the Departmental Representative.
- .2 Commencement of work will imply acceptance of existing conditions.

# 22. SITE OFFICE & TELEPHONE

- .1 Contractor to erect a temporary site office at his own expense.
- .2 Install and maintain a telephone, if necessary.
- .3 Use of NRC phones is not permitted unless in the case of an emergency.

# 23. SANITARY FACILITIES

.1 Obtain permission from the Departmental Representative to use the existing washroom facilities in the building.

# 24. TEMPORARY SERVICES

- .1 A source of temporary power will be made available in the area. Bear all costs to make connections to the power source and perform distribution on site.
- .2 Provide all load centres, breakers, conduit, wiring, disconnects, extension cords, transformers, as required from the source of power.
- .3 Power is to be used only for power tools, lighting, controls, motors, and not for space heating.
- .4 A source of temporary water will be made available if required.
- .5 Bear all costs associated with distributing the water to the required locations.
- .6 Comply with NRC requirements when connecting to existing systems in accordance with the articles entitled "Co-operation" and "Service Interruptions" of this section.

# 25. DOCUMENTS REQUIRED AT WORK SITE

- .1 The Contractor shall keep on the site, one (1) up-to-date copy of all contract documents, including specifications, drawings, addenda, shop drawings, change notices, schedule and any reports or bulletins pertaining to the work, in good order, available to the Departmental Representative and to his / her representatives at all times.
- .2 At least one (1) copy of specifications and drawings shall be marked by the Contractor to show all work "As Built" and shall be provided to the Departmental Representative with the Application for Payment and for the Final Certificate of Completion.

# 26. CO-OPERATION

- .1 Co-operate with NRC staff in order to keep disruption of normal research work to an absolute minimum.
- .2 Work out in advance, a schedule for all work which might disrupt normal work in the building.
- .3 Have schedule approved by the Departmental Representative.
- .4 Notify the Departmental Representative in writing, 72 hours prior to any intended interruption of facilities, areas, corridors, mechanical or electrical services and obtain requisite permission.

### 27. PROTECTION AND WARNING NOTICES

- .1 Provide all materials required to protect existing equipment.
- .2 Erect dust barriers to prevent dust and debris from spreading through the building.
- .3 Place dust protection in the form of cover sheets over equipment and furniture and tape these sheets to floors, to ensure no dust infiltration.
- .4 Repair or replace any and all damage to Owner's property caused during construction, at no cost to the Owner and to the satisfaction of the Departmental Representative.
- .5 Protect the buildings, roads, lawns, services, etc. from damage which might occur as a result of this work.
- .6 Plan and co-ordinate the work to protect the buildings from the leakage of water, dust, etc.
- .7 Ensure that all doors, windows, etc., that could allow transfer of dust, noise, fumes, etc., to other areas of the building are kept closed.
- .8 Be responsible for security of all areas affected by the work under the Contract until acceptance by NRC. Take all necessary precautions to prevent entry to the work area by unauthorized persons and guard against theft, fire and damage by any cause. Secure working area at the end of each day's work and be responsible for same.
- .9 Provide and maintain adequate safety barricades around the work sites to protect NRC personnel and the public from injury during the construction.
- .10 Post warnings, in all instances where possible injury could occur such as Work Overhead, Hard Hat Areas, etc. or as required by the Departmental Representative.
- Provide temporary protective enclosures over building entrances and exits to protect pedestrians. All enclosures to be structurally sound against weather and falling debris.

# 28. BILINGUALISM

.1 Ensure that all signs, notices, etc. are posted in both official languages.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
S77-6295	Page 8 of 13

.2 Ensure that all identification of services called for by under this contract are bilingual.

# 29. LAYOUT OF WORK

- .1 Location of equipment, fixtures, outlets and openings indicated on drawings or specified are to be considered as approximate.
- .2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with the manufacturer's recommendations for safety, access and maintenance.
- .3 Employ competent person to lay out work in accordance with the contract documents.

# 30. DISCREPANCIES & INTERFERENCES

- .1 Prior to the start of the work, examine drawings and specifications. Report at once to the Departmental Representative, any defects, discrepancies, omissions or interferences affecting the work.
- .2 Contractor to immediately inform the Departmental Representative in writing, of any discrepancies between the plans and the physical conditions so the Departmental Representative may promptly verify same.
- .3 Any work done after such a discovery, until authorized, is at the Contractor's risk.
- .4 Where minor interferences as determined by the Departmental Representative are encountered on the job and they have not been pointed out on the original tender or on the plans and specifications, provide offsets, bends or reroute the services to suit job conditions at no extra cost.
- .5 Arrange all work so as not to interfere in any way with other work being carried out.

# 31. MANUFACTURER'S INSTRUCTIONS

- .1 Unless otherwise specified, comply with manufacturer's latest printed instructions for materials and installation methods.
- .2 Notify the Departmental Representative in writing of any conflict between these specifications and manufacturer's instruction. Departmental Representative will designate which document is to be followed.

# 32. TEMPORARY HEATING AND VENTILATING

- .1 Bear the costs of temporary heat and ventilation during construction including costs of installation, fuel, operation, maintenance, and removal of equipment.
- .2 Use of direct-fired heaters discharging waste products into the work areas will not be permitted unless prior approval is given by the Departmental Representative.
- .3 Furnish and install temporary heat and ventilation in enclosed areas as required to:

- .1 Facilitate progress of work.
- .2 Protect work and products against dampness and cold.
- .3 Reduce moisture condensation on surfaces to an acceptable level.
- .4 Provide ambient temperature and humidity levels for storage, installation and curing of materials.
- .5 Provide adequate ventilation to meet health regulations for a safe working environment.
- .4 Maintain minimum temperature of 10°C (50°F) or higher where specified as soon as finishing work is commenced and maintain until acceptance by the Departmental Representative.
  - .1 Maintain ambient temperature and humidity levels as required for comfort of NRC personnel.
- .5 Prevent hazardous or unhealthy accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction including also, storage areas and sanitary facilities.
  - .1 Dispose of exhaust materials in a manner that will not result in a harmful or unhealthy exposure to persons.
- .6 Maintain strict supervision of operation of temporary heating and ventilating equipment.
  - .1 Enforce conformance with applicable codes and standards.
  - .2 Comply with instructions of the Departmental Representative including provision of full-time watchman services when directed.
  - .3 Enforce safe practices.
  - .4 Vent direct-fired combustion units to outside.
- .7 Submit tenders assuming existing or new equipment and systems will not be used for temporary heating and ventilating.
- .8 After award of contract, Departmental Representative may permit use of the permanent system providing agreement can be reached on:
  - .1 Conditions of use, special equipment, protection, maintenance, and replacement of filters.
  - .2 Methods of ensuring that heating medium will not be wasted and in the case of steam, agreement on what is to be done with the condensate.
  - .3 Saving on contract price.
  - .4 Provisions relating to guarantees on equipment.

# 33. CONNECTIONS TO AND INTERRUPTIONS TO EXISTING SERVICES

- .1 Where work involves breaking into or connecting to existing services, carry out work at times and in the manner agreed to by the Departmental Representative and by authorities having jurisdiction, with minimum disruption to NRC Personnel and vehicular traffic and minimum service interruption. Do not operate any NRC equipment or plant.
- .2 Before commencing work, establish location and extent of service lines in area of work and notify Departmental Representative of findings.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
<u>\$77-6295</u>	Page 10 of 13

- .3 Submit a schedule to and obtain approval from the Departmental Representative for any shut-down or closure of active service or facility; allow minimum 72 hours notice. Adhere to approved schedule and provide notice to the Departmental Representative.
- .4 Where unknown services are encountered, immediately advise Departmental Representative and confirm findings in writing.
- .5 Provide detours, bridges, alternate feeds, etc., as required to minimize disruptions.
- .6 Protect existing services as required and immediately make repairs if damage occurs.
- .7 Remove any abandoned service lines as indicated on the contract documents and as approved by the Departmental Representative; cap or otherwise seal lines at cut-off points. Record and provide a copy to the Departmental Representative of locations of maintained, re-routed and abandoned service lines.

## 34. CUTTING AND PATCHING

- .1 Cut existing surfaces as required to accommodate new work.
- .2 Remove all items as shown or specified.
- .3 Patch and make good with identical materials, the surfaces that have been disturbed, cut or damaged, to the satisfaction of the Departmental Representative.
- .4 Where new pipes pass through existing construction, core drill an opening. Size openings to leave 12mm (1/2") clearance around the pipes or pipe insulation. Do not drill or cut any surface without the approval of the Departmental Representative.
- .5 Obtain written approval of the Departmental Representative before cutting openings through existing or new structural members.
- .6 Seal all openings where cables, conduits or pipes pass through walls with an acoustic sealant conforming to CAN/CGSB-19.21-M87.
- .7 Where cables, conduits and pipes pass through fire rated walls and floors, pack space between with compressed glass fibres and seal with fire stop caulking in accordance with CAN/CGSB-19.13-M87 AND NBC 3.1.7.

## 35. FASTENING DEVICES

- .1 Do not use explosive actuated tools, without first obtaining permission from the Departmental Representative.
- .2 Comply with the requirements of CSA A-166 (Safety Code for Explosive Actuated Tools).
- .3 Do not use any kind of impact or percussion tool without first obtaining permission from the Departmental Representative.

## 36. OVERLOADING

.1 Ensure that no part of the building or work is subjected to a load which will endanger safety or cause permanent deformation or structural damage.

#### 37. DRAINAGE

.1 Provide temporary drainage and pumping as required to keep excavations and site free of water.

#### 38. ENCLOSURE OF STRUCTURES

- .1 Construct and maintain all temporary enclosures as required to protect foundations, sub-soil, concrete, masonry, etc., from frost penetration or damage.
- .2 Maintain in place until all chances of damage are over and proper curing has taken place.
- .3 Provide temporary weather tight enclosures for exterior openings until permanent sash and glazing and exterior doors are installed.
- .4 Provide lockable enclosures as required to maintain the security of NRC facilities and be responsible for the same.
- .5 Provide keys to NRC security personnel when required.
- .6 Lay out the work carefully and accurately and verify all dimensions and be responsible for them. Locate and preserve general reference points.
- .7 Throughout the course of construction, keep continuously acquainted with field conditions, and the work being developed by all trades involved in the project. Maintain an awareness of responsibility to avoid space conflict with other trades.
- .8 Conceal all services, piping, wiring, ductwork, etc., in floors, walls or ceilings except where indicated otherwise.

## 39. STORAGE

- .1 Provide storage as required to protect all tools, materials, etc., from damage or theft and be responsible for the same.
- .2 Do not store flammable or explosive materials on site without the authorization of the Departmental Representative.

## 40. GENERAL REVIEW

.1 Periodic review of the Contractor's work by the Departmental Representative does not relieve the Contractor of the responsibility of making the work in accordance with contract documents. Contractor shall carry out his own quality control to ensure that the construction work is in accordance with contract documents.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
<u>\$77-6295</u>	Page 12 of 13

.2 Inform the Departmental Representative of any impediments to the installation and obtain his / her approval for actual location.

## 41. INSPECTION OF BURIED OR CONCEALED SERVICES

.1 Prior to concealing any services that are installed, ensure that all inspection bodies concerned, including NRC, have inspected the work and have witnessed all tests. Failure to do so may result in exposing the services again at the Contractor's expense.

#### 42. TESTING

- .1 On completion, or as required by local authority inspectors and/or Departmental Representative during progress of work and before any services are covered up and flushing is complete, test all installations in the presence of the Departmental Representative.
- .2 Obtain and hand to the Departmental Representative all acceptance certificates or test reports from authority having jurisdiction. The project will be considered incomplete without the same.

## 43. PARTIAL OCCUPANCY

- .1 NRC may request partial occupancy of the facility if the contract extends beyond the expected completion date.
- .2 Do not restrict access to the building, routes, and services.
- .3 Do not encumber the site with materials or equipment.

#### 44. DISPOSAL OF WASTES

.1 Dispose of waste materials including volatiles, safely off NRC property. Refer to the section entitled "General and Fire Safety Requirements" included as part of this specification.

#### 45. CLEAN-UP DURING CONSTRUCTION

- .1 On a daily basis, maintain project site and adjacent area of campus including roofs, free from debris and waste materials.
- .2 Provide on-site dump containers for collection of waste materials and rubbish.

#### 46. FINAL CLEAN-UP

- .1 Upon completion do a final clean-up to the satisfaction of the Departmental Representative.
- .2 Clean all new surfaces, lights, existing surfaces affected by this work, replace filters, etc.
- .3 Clean all resilient flooring and prepare to receive protective finish. Protective finish applied by NRC.

NRC	Section 00 10 00
Project No.	GENERAL INSTRUCTIONS
S77-6295	Page 13 of 13

## 47. WARRANTY AND RECTIFICATION OF DEFECTS IN WORK

- .1 Refer to General Conditions "C", section GC32.
- .2 Ensure that all manufacturers' guarantees and warranties are issued in the name of the **General Contractor** and the National Research Council.

#### 48. MAINTENANCE MANUALS

- .1 Provide two (2) bilingual copies of maintenance manuals or two (2) English and two (2) French maintenance manuals and one (1) electronic copy of same immediately upon completion of the work and prior to release of holdbacks.
- .2 Manuals to be neatly bound in hard cover loose leaf binders.
- .3 Manuals to include operating and maintenance instructions, all guarantees and warranties, shop drawings, technical data, etc., for the material and apparatus supplied under this contract.

**END OF SECTION** 

# 1. GENERAL CONSTRUCTION SAFETY REQUIREMENTS

- .1 The Contractor shall take all necessary steps to protect personnel (workers, visitors, general public, etc.) and property from any harm during the course of the contract.
- .2 The Contractor shall be solely responsible for the construction safety of both its employees and those of its sub-contractors at the work site, and for initiating, maintaining and supervising safety precautions, programs and procedures in connection with the performance of the work.
- .3 The Contractor shall comply with all Federal, Provincial and Municipal safety codes and regulations and the Occupational Health and Safety Act and the Workplace Safety and Insurance Board. In the event of any conflict between any provisions in legislation or codes, the most stringent provisions shall apply.
- .4 Periodic review of the Contractor's work by the Departmental Representative, using the criteria of the contract documents, does not relieve the Contractor of his safety responsibilities in carrying out the work in accordance with the contract documents. The Contractor shall consult with the Departmental Representative to ensure that this responsibility is carried out.
- .5 The Contractor shall ensure that only competent personnel are permitted to work on site. Throughout the term of the contract, any person will be removed from the site who is not observing or complying with the safety requirements.
- .6 All equipment shall be in safe operating condition and appropriate to the task.
- .7 Following a project and site hazard assessment, the Contractor shall develop a Site Specific Safety Plan based on the following minimum requirements. Site Specific Safety Plans must also be robust enough to address any abnormal occurrences, such as, but not limited to: pandemics (COVID-19 or a similar), fire, flooding, inclimate weather or other environmental anomalies.
  - .1 Provide a safety board mounted in a visible location on the project site, with the following information included thereon:
    - .1 Notice of Project.
    - .2 Site specific Safety Policy.
    - .3 Copy of Ontario Health and Safety Act.
    - .4 Building Schematic showing emergency exits.
    - .5 Building emergency procedures.
    - .6 Contact list for NRC, Contractor and all involved sub-contractors.
    - .7 Any related MSDS sheets.
    - .8 NRC Emergency phone number.
- .8 The Contractor shall provide competent personnel to implement its safety program and those of any Health and Safety Act legislation applicable at this project location, and to ensure they are being complied with.

- .9 The Contractor shall provide safety orientation to all its employees as well as those of any sub-contractors under its jurisdiction.
- .10 The Departmental Representative will monitor to ensure that safety requirements are met and that safety records are properly kept and maintained. Continued disregard for safety standards can cause the contract to be cancelled and the Contractor or sub-contractors removed from the site.
- .11 The Contractor will report to the Departmental Representative and jurisdictional authorities, any accident or incident involving Contractor or NRC personnel or the public and/or property arising from the Contractor's execution of the work.
- .12 If entry to a laboratory is required as part of the work of the Contractor, a safety orientation shall be provided to all his employees as well as those of any sub-contractors regarding lab safety requirements and procedures, as provided by the Researcher or the Departmental Representative.

# 2. FIRE SAFETY REQUIREMENTS

## .1 Authorities

- 1. The Fire Commissioner of Canada (FC) is the authority for fire safety at NRC.
- 2. For the purpose of this document, "Departmental Representative" will be deemed as the NRC person in charge of the project and who will enforce these Fire Safety Requirements.
- 3. Comply with the following standards as published by the Office of the Fire Commissioner of Canada:
  - a. Standard No. 301 June 1982 "Standard for Construction Operations";
  - b. Standard No. 302 June 1982 "Standard for Welding and Cutting".

## .2 Smoking

- .1 Smoking is prohibited inside all NRC buildings, as well as roof areas.
- .2 Obey all "NO SMOKING" signs on NRC premises.

## .3 Hot Work

- .1 Prior to commencement of any "Hot Work" involving welding, soldering, burning, heating, use of torches or salamanders or any open flame, obtain a Hot Work Permit from the Departmental Representative.
- .2 Prior to commencement of "Hot Work", review the area of hot work with the Departmental Representative to determine the level of fire safety precautions to be taken.

## .4 Reporting Fires

.1 Know the exact location of the nearest Fire Alarm Pull Station and telephone, including the emergency phone number.

- .2 REPORT immediately, all fire incidents as follows:
  - 1. Activate nearest fire alarm pull station; and
  - 2. Telephone the following emergency phone number as appropriate:

FROM AN NRC PHONE 333 FROM ANY OTHER PHONE (613) 993-2411

- 3. When reporting a fire by phone, give the location of fire, building number and be prepared to verify location.
- 4. The person activating fire alarm pull station must remain at a safe distance from the scene of the fire but readily available to provide information and direction to the Fire Department personnel.

## .5 Interior and Exterior Fire protection & Alarm Systems

- .1 DO NOT OBSTRUCT OR SHUT OFF FIRE PROTECTION EQUIPMENT OR SYSTEMS, INCLUDING BUT NOT LIMITED TO FIRE ALARM SYSTEMS, SMOKE/HEAT DETECTORS, SPRINKLER SYSTEM, PULL STATIONS, EMERGENCY CALL BUTTONS AND PA SYSTEMS, WITHOUT AUTHORIZATION FROM THE DEPARTMENTAL REPRESENTATIVE.
- .2 WHEN ANY FIRE PROTECTION EQUIPMENT IS TEMPORARILY SHUT DOWN, ALTERNATIVE MEASURES AS PRESCRIBED BY THE DEPARTMENTAL REPRESENTATIVE SHALL BE TAKEN TO ENSURE THAT FIRE PROTECTION IS MAINTAINED.
- .3 DO NOT LEAVE FIRE PROTECTION OR ALARM SYSTEMS INACTIVE AT THE END OF A WORKING DAY WITHOUT NOTIFICATION AND AUTHORISATION FROM THE DEPARTMENTAL REPRESENTATIVE. THE DEPARTMENTAL REPRESENTATIVE WILL ADVISE THE (FPO) OF THE DETAILS OF ANY SUCH EVENT.
- .4 DO NOT USE FIRE HYDRANTS, STANDPIPES AND HOSE SYSTEMS FOR OTHER THAN FIRE FIGHTING PURPOSES UNLESS AUTHORISED BY DEPARTMENTAL REPRESENTATIVE.

## .6 Fire Extinguishers

- .1 Provide a minimum of 1-20 lb. ABC Dry Chemical Fire Extinguisher at each hot work or open flame location.
- .2 Provide fire extinguishers for hot asphalt and roofing operations as follows:
  - 1. Kettle area 1-20 lb. ABC Dry Chemical; and
  - 2. Roof 1-20 lb. ABC Dry Chemical at each open flame location.
- .3 Provide fire extinguishers equipped as below:
  - 1. Pinned and sealed;
  - 2. With a pressure gauge; and
  - 3. With an extinguisher tag signed by a fire extinguisher servicing company.

.4 Carbon Dioxide (CO2) extinguishers will not be considered as substitutes for the above.

## .7 Roofing Operations

- .1 Kettles:
  - .1 Arrange for the location of asphalt kettles and material storage with the Departmental Representative before moving on site. Do not locate kettles on any roof or structure and keep them at least 10m (30 feet) away from a building.
  - .2 Equip kettles with two (2) thermometers or gauges in good working order; a hand held and a kettle-mounted model.
  - .3 Do not operate kettles at temperatures in excess of 232°C (450°F).
  - .4 Maintain continuous supervision while kettles are in operation and provide metal covers for the kettles to smother any flames in case of fire. Provide fire extinguishers as required in article 2.6.
  - .5 Demonstrate container capacities to Departmental Representative prior to start of work.
  - .6 Store materials a minimum of 6m (20 feet) from the kettle.

# .2 Mops:

- .1 Use only glass fibre roofing mops.
- .2 Remove used mops from the roof site at the end of each working day.

## .3 Torch Applied Systems:

- .1 DO NOT USE TORCHES NEXT TO WALLS.
- .2 DO NOT TORCH MEMBRANES TO EXPOSED WOOD OR CAVITY.
- .3 Provide a Fire Watch as required by article 2.9 of this section.

## .4 Fire and Smoke Hazard Management:

- .1 Contractor shall identify "Designated Roofing Marshall" for duration of construction activities. "Designated Roofing Marshall" shall be responsible for the following:
  - .1 Perform NRC Daily Fire and Smoke Risk Hazard Assessment each day prior to commencement of roofing activities.
  - .2 Provide completed NRC Daily Fire and Smoke Risk Hazard Assessment to Departmental Representative every morning by email prior to commencement of roofing activities.
  - .3 Follow behind any torch activities with a thermal scanner periodically to identify any hot spots and rectify immediately. Interval for periodic thermal scanning to be approved on site with Departmental Representative.
- .2 Any proposed changes to "Designated Roofing Marshall" must be reviewed and approved by Departmental Representative.

- .5 Store all combustible roofing materials at least 3m (10 feet) away from any structure.
- .6 Keep compressed gas cylinders a minimum of 6m (20 feet) away from the kettle, protected from mechanical damage and secured in an upright position.

## .8 Welding / Grinding Operations

.1 Contractor to provide fire blankets, portable fume extraction devices, screens or similar equipment to prevent exposure to welding flash, or sparks from grinding.

#### .9 Fire Watch

- .1 Provide a fire watch for a minimum of one hour after the termination of any hot work operation.
- .2 For temporary heating, refer to General Instructions Section 00 010 00.
- .3 Equip fire watch personnel with fire extinguishers as required by article 2.6.

## .10 Obstruction of access/egress routes-roadways, halls, doors, or elevators

- .1 Advise the Departmental Representative in advance of any work that would impede the response of Fire Department personnel and their apparatus. This includes violation of minimum overhead clearance, erection of barricades and the digging of trenches.
- .2 Building exit routes must not be obstructed in any way without special permission from the Departmental Representative, who will ensure that adequate alternative routes are maintained.
- .3 The Departmental Representative will advise the FPO of any obstruction that may warrant advanced planning and communication to ensure the safety of building occupants and the effectiveness of the Fire Department.

#### .11 Rubbish and Waste Materials

- .1 Keep rubbish and waste materials to a minimum and a minimum distance of 6m (20 feet) from any kettle or torches.
- .2 Do not burn rubbish on site.

#### .3 Rubbish Containers:

- .1 Consult with the Departmental Representative to determine an acceptable safe location for any containers and the arrangement of chutes etc. prior to bringing the containers on site.
- .2 Do not overfill the containers and keep area around the perimeter free and clear of any debris.

## .4 Storage:

- .1 Exercise extreme care when storing combustible waste materials in work areas. Ensure maximum possible cleanliness, ventilation and that all safety standards are adhered to when storing any combustible materials.
- .2 Deposit greasy or oily rags or materials subject to spontaneous combustion in CSA or ULC approved receptacles and remove at the end of the work day or shift, or as directed.

## .12 Flammable Liquids

- .1 The handling, storage and use of flammable liquids is governed by the current National Fire Code of Canada.
- .2 Flammable Liquids such as gasoline, kerosene and naphtha may be kept for ready use in quantities not exceeding 45 litres (10 imp gal), provided they are stored in approved safety cans bearing the ULC seal of approval and kept away from buildings, stockpiled combustible materials etc. Storage of quantities of flammable liquids exceeding 45 litres (10 imp gal) for work purposes, require the permission of the Departmental Representative.
- .3 Flammable liquids are not to be left on any roof areas after normal working hours.
- .4 Transfer of flammable liquids is prohibited within buildings.
- .5 Do not transfer flammable liquids in the vicinity of open flames or any type of heat producing device.
- Do not use flammable liquids having a flash point below 38°C (100°F) such as naphtha or gasoline as solvents or cleaning agents.
- .7 Store flammable waste liquids for disposal in approved container located in a safe, ventilated area. Waste flammable liquids are to be removed from the site on a regular basis.
- .8 Where flammable liquids, such as lacquers or urethane are used, ensure proper ventilation and eliminate all sources of ignition. Inform the Departmental Representative prior to, and at the cessation of such work.

## 3. **QUESTINONS OR CLARIFICATIONS**

.1 Direct any questions or clarification on Fire or General Safety, in addition to the above requirements, to the Departmental Representative.

#### **END OF SECTION**

#### Part 1 General

#### 1.1 SUMMARY

- .1 This Section includes requirements for management of construction waste and disposal, which forms the Contractor's commitment to reduce and divert waste materials from landfill and includes the following:
  - .1 Preparation of a Draft Construction Waste Management Plan that will be used to track the success of the Construction Waste Management Plan against actual waste diversion from landfill.
  - .2 Preparation of monthly progress reports indicating cumulative totals representing progress towards achieving diversion and reduction goals of waste materials away from landfill and identifying any special programs, landfill options or alternatives to landfill used during construction.
  - .3 Preparation of a Construction Waste Management Report containing detailed information indicating total waste produced by the project, types of waste material and quantity of each material, and total waste diverted and diversion rates indicated as a percentage of the total waste produced.
- .2 Owner has established that this project shall generate the least amount of waste possible and that processes that ensure the generation of as little waste as possible due to error, poor planning, breakage, mishandling, contamination, or other factors be employed by the Contractor.

## 1.2 RELATED REQUIREMENTS

- .1 [Section 00 10 00 General Instructions]
- .2 [Section 02 42 00 Removal and Salvage of Construction Material]
- .3 [Section 26 05 05 Selective Demolition for Electrical]

# 1.3 REFERENCE STANDARDS

- .1 ASTM International (ASTM)
  - .1 ASTM E1609 01, Standard Guide for Development and Implementation of a Pollution Prevention Program
- .2 Canada Green Building Council (CaGBC)
  - .1 LEED Reference Guide for Building Design and Construction, Version 4
- .3 Recycling Certification Institute (RCI):
  - .1 RCI Certification Construction and Demolition Materials Recycling

#### 1.4 **DEFINITIONS**

- .1 Clean Waste: Untreated and unpainted; not contaminated with oils, solvents, sealants or similar materials.
- .2 Construction and Demolition Waste: Solid wastes typically including building materials, packaging, trash, debris, and rubble resulting from construction, re-modeling, repair and demolition operations.
- .3 Hazardous: Exhibiting the characteristics of hazardous substances including properties such as ignitability, corrosiveness, toxicity or reactivity.
- .4 Non-hazardous: Exhibiting none of the characteristics of hazardous substances, including properties such as ignitability, corrosiveness, toxicity, or reactivity.
- .5 Non-toxic: Not poisonous to humans either immediately or after a long period of exposure.
- Recyclable: The ability of a product or material to be recovered at the end of its life cycle and remanufactured into a new product for reuse by others.
- .7 Recycle: To remove a waste material from the project site to another site for remanufacture into a new product for reuse by others.
- .8 Recycling: The process of sorting, cleansing, treating and reconstituting solid waste and other discarded materials for the purpose of using the altered form; recycling does not include burning, incinerating, or thermally destroying waste.
- .9 Return: To give back reusable items or unused products to vendors for credit.
- .10 Reuse: To reuse a construction waste material in some manner on the project site.
- .11 Salvage: To remove a waste material from the project site to another site for resale or reuse by others.
- .12 Sediment: Soil and other debris that has been eroded and transported by storm or well production run off water.
- .13 Source Separation: The act of keeping different types of waste materials separate beginning from the first time they become waste.
- .14 Toxic: Poisonous to humans either immediately or after a long period of exposure.
- .15 Trash: Any product or material unable to be reused, returned, recycled, or salvaged.
- .16 Volatile Organic Compounds (VOC's): Chemical compounds common in and emitted by many building products over time through outgassing:
  - .1 Solvents in paints and other coatings;
  - .2 Wood preservatives; strippers and household cleaners;
  - .3 Adhesives in particleboard, fiberboard, and some plywood; and foam insulation.

- .4 When released, VOC's can contribute to the formation of smog and can cause respiratory tract problems, headaches, eye irritations, nausea, damage to the liver, kidneys, and central nervous system, and possibly cancer.
- .17 Waste: Extra material or material that has reached the end of its useful life in its intended use. Waste includes salvageable, returnable, recyclable, and reusable material.
- .18 Construction Waste Management Plan: A project related plan for the collection, transportation, and disposal of the waste generated at the construction site; the purpose of the plan is to ultimately reduce the amount of material being landfilled.

# 1.5 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination: Coordinate waste management requirements with all Divisions of the Work for the project, and ensure that requirements of the Construction Waste Management Plan are followed.
- .2 Preconstruction Meeting: Arrange a pre-construction meeting in accordance with Section 01 10 00 General Instructions before starting any Work of the Contract attended by the Owner, Contractor, affected Subcontractor's and Departmental Representative to discuss the Contractor's Construction Waste Management Plan and to develop mutual understanding of the requirements for a consistent policy towards waste reduction and recycling.

#### 1.6 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide required information in accordance with Section 01 10 00 General Instructions.
- .2 Action Submittals: Provide the following submittals before starting any work of this Section:
  - .1 Draft Construction Waste Management Plan (Draft CWM Plan): Submit to Departmental Representative a preliminary analysis of anticipated site generated waste by listing a minimum of five (5) construction or demolition waste streams that have potential to generate the most volume of material indicating methods that will be used to divert construction waste from landfill and source reduction strategies; Departmental Representative will provide commentary before development of Contractor's Construction Waste Management Plan.
  - .2 Construction Waste Management Plan (CWM Plan): Submit a CWM Plan for this project prior to any waste removal from site and that includes the following information:
    - .1 Material Streams: Analysis of the proposed jobsite waste being generated, including material types and quantities forming a part of identified material streams in the Draft CWM Plan; materials removed from site destined for alternative daily cover at landfill sites and land clearing debris cannot be considered as contributing to waste diversion and will be included as a component of the total waste generated for the site.
    - .2 Recycling Haulers and Markets: Investigate local haulers and markets for recyclable materials, and incorporate into CWM Plan.
    - .3 Alternative Waste Disposal: Prepare a listing of each material proposed to be salvaged, reused, recycled or composted during the course of the project, and the proposed local market for each material.

- .4 Landfill Materials: Identify materials that cannot be recycled, reused or composted and provide explanation or justification; energy will be considered as a viable alternative diversion strategy for these materials where facilities exist and are operated in accordance with LEED Construction and Demolition Waste Management requirements.
- .5 Landfill Options: The name of the landfill where trash will be disposed of; landfill materials will form a part of the total waste generated by the project.
- .6 Materials Handling Procedures: A description of the means by which any recycled waste materials will be protected from contamination, and a description of the means to be employed in recycling the above materials consistent with requirements for acceptance by designated facilities.
- .7 Transportation: A description of the means of transportation of the recyclable materials, whether materials will be site separated and self-hauled to designated centers, or whether mixed materials will be collected by a waste hauler and removed from the site, and destination of materials.

# 1.7 PROJECT CLOSEOUT SUBMISSIONS

- .1 Record Documentation: Submit as constructed information in accordance with Section 01 10 00 General Instructions as follows:
  - .1 Construction Waste Management Report (CWM Report): Submit a CWM Report for this project in a format that includes the following information:
    - .1 Accounting: Submit information indicating total waste produced by the project.
    - .2 Composition: Submit information indicating types of waste material and quantity of each material.
    - .3 Diversion Rate: Submit information indicating total waste diverted from landfill as a percentage of the total waste produced by the project.
    - .4 Transportation Documentation and Diversion Documentation: Submit copies of transportation documents or shipping manifests indicating weights of materials, and other evidence of disposal indicating final location of waste diverted from landfill and waste sent to landfill.
    - .5 Multiple Waste Hauling: Compile all information into a single CWM Report where multiple waste hauling and diversion strategies were used for the project.

## 1.8 QUALITY ASSURANCE

- .1 Resources for Development of Construction Waste Management Report (CWM Report): The following sources may be useful in developing the Draft Construction Waste Management Plan:
  - .1 Recycling Haulers and Markets: Investigate local haulers and markets for recyclable materials, and incorporate into CWM Plan.
  - .2 Waste-to-Energy Systems: Investigate local waste-to-energy incentives where systems for diverting materials from landfill for reuse or recycling are not available.
  - .3 Municipal Garbage & Recycling Waste Websites:
    - .1 [Ontario Region
      - .1 London

EnviroDepots | City of London

.2 Mississauga

How to sort your waste - Region of Peel (peelregion.ca)

.3 National Capital Region (City of Ottawa)

Garbage and recycling | City of Ottawa

- .2 Quebec Region
  - .1 Boucherville

Accueil | Ville de Longueuil

.2 Montreal

Get details about bulky items and construction debris collections | Ville de Montréal (montreal.ca)

.3 Saguenay

<u>Demolition Waste Management | Demex-Centrem group (groupedemexcentrem.com)</u>

- .3 East Region
  - .1 Charlettetown

Sorting Guide - Island Waste Management Corporation | Prince Edward Island Recycling, Compost and Waste Disposal (iwmc.pe.ca)

.2 Fredericton

<u>Construction and Demolition - Fredericton Region Solid Waste :</u> Fredericton Region Solid Waste (frswc.ca)

.3 Halifax

Halifax C&D Recycling (halifaxcdrecycling.ca)

.4 Ketch Harbour

Halifax C&D Recycling (halifaxcdrecycling.ca)

.5 St. John's

Accepted Material at RHB (Commercial/ Municipal Users) | Robin Hood Bay Facility | Garbage Disposal | St. John's

.4 West Region

- .1 Edmonton
  - Material Recovery Facility (MRF) | KBL Environmental
- .2 Penticton
  - https://keremeos.civicweb.net/document/3069/
- .3 Saskatoon
  - Construction/Demolition/Fencing Loraas Disposal North
- .4 Victoria
  - Reno & Demo Waste | CRD
- .5 Vancouver
  - Construction and demolition waste disposal | City of Vancouver
- .6 Winnipeg

What goes where? Use the Recyclepedia - MyUtility - Water and Waste Department - City of Winnipeg / MesServices - Service des eaux et des déchets - Ville de Winnipeg ]

## 1.9 DELIVERY, STORAGE AND HANDLING

- .1 Storage Requirements: Implement a recycling/reuse program that includes separate collection of waste materials as appropriate to the project waste and the available recycling and reuse programs in the project area.
- .2 Handling Requirements: Clean materials that are contaminated before placing in collection containers and ensure that waste destined for landfill does not get mixed in with recycled materials:
  - .1 Deliver materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to recycling process.
  - .2 Arrange for collection by or delivery to the appropriate recycling or reuse facility.
- .3 Hazardous Waste and Hazardous Materials: Handle in accordance with applicable regulations.

## Part 2 Products

## 2.1 NOT USED

.1 Not Used.

#### Part 3 Execution

#### 3.1 OBJECTIVE

.1 The Federal Sustainable Development Strategy (FSDS) presents the Government of Canada's sustainable development goals and targets, as required by the *Federal Sustainable Development Act*. In keeping with the purpose of this Act – to provide the legal framework for developing and implementing a Federal Sustainable Development Strategy that will make environmental decision-making more transparent and accountable to Parliament – National Research Council (NRC) supports the goals laid out in the FSDS through the activities described in our

Departmental Sustainable Development Strategy (DSDS). NRC's DSDS waste management target is as follows:

- .1 Divert at least 90% (by weight) of all construction and demolition waste from landfills (striving to achieve 100% by 2030).
- .2 Project Waste Diversion Target: 90%.

# 3.2 (CWM PLAN) IMPLEMENTATION

- .1 Manager: Contractor is responsible for designating an on-site party or parties responsible for instructing workers and overseeing and documenting results of the CWM Plan for the project.
- .2 Distribution: Distribute copies of the CWM Plan to the job site foreman, each Subcontractor, the Owner, the Departmental Representative and other site personnel as required to maintain CWM Plan.
- .3 Instruction: Provide on-site instruction of appropriate separation, handling, and recycling, salvage, reuse, composting and return methods being used for the project to Subcontractor's at appropriate stages of the project.
- .4 Separation Facilities: Lay out and label a specific area to facilitate separation of materials for potential recycling, salvage, reuse, composting and return:
  - .1 Recycling and waste bin areas are to be kept neat and clean and clearly marked in order to avoid contamination of materials.
  - .2 Hazardous wastes shall be separated, stored, and disposed of in accordance with local regulations.
- .5 Progressive Documentation: Submit a monthly summary of waste generated by the project to ensure that waste diversion goals are on track with project requirements:
  - .1 Submission of waste summary can coincide with application for progress payment, or similar milestone event as agreed upon between the Contractor and Departmental Representative.
  - .2 Monthly waste summary shall contain the following information:
    - .1 The amount in tonnes or m3 and location of material landfilled;
    - .2 The amount in tonnes or m3 and location of materials diverted from landfill; and
    - .3 Indication of progress based on total waste generated by the project with materials diverted from landfill as a percentage.

#### 3.3 SUBCONTRACTOR'S RESPONSIBILITY

- .1 Subcontractor's shall cooperate fully with the Contractor to implement the CWM Plan.
- .2 Failure to cooperate may result in the Owner not achieving their environmental goals, and may result in penalties being assessed by the Contractor to the responsible Subcontractor's.

NRC-CNRC	Section 01 74 19
Project No.	WASTE MANAGEMENT AND DISPOSAL
S77-6295	Page 8 of 8

#### 3.4 CONSTRUCTION WASTE MANAGEMENT FORMS

- .1 Departmental Representative will provide Contractor will NRC Waste Management and Disposal Tracking Forms (sample provided below) for recording management of construction waste.
- .2 Contractor shall utilize these forms for all waste management and disposal tracking for the duration of the project, and is responsible for maintaining current up to date records at all times during construction.
- .3 Contractor is responsible to ensure all waste management tracking forms, weigh-bills, donation receipts, and summary information are incorporated into Operational and Maintenance Manuals upon construction completion in accordance with 01 10 00 General Instructions.

[INSERT WASTE MANAGEMENT FORMS]

**END OF SECTION** 

## Part 1 General

#### 1.1 SUMMARY

.1 This Section includes requirements for careful removal and salvage, and reconditioning of building components identified for storage at a designated remote site, for storage on site, and subsequent reinstallation forming a part of Project ready for re use at a later date.

## 1.2 RELATED REQUIREMENTS

- .1 [Section 01 10 00 General Instructions]
- .2 [Section 01 74 19 Waste Management and Disposal]
- .3 [Section 02 41 19.16 Selective Interior Demolition]
- .4 [Section 22 05 05 Selective Demolition for Plumbing]
- .5 [Section 23 05 05 Selective Demolition for HVAC]
- .6 [Section 26 05 05 Selective Demolition for Electrical]

## 1.3 **DEFINITIONS**

- .1 Remove and Salvage: Detach items from existing construction and deliver them ready for reuse.
- .2 Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.

## 1.4 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination Existing Salvaged Work: Coordinate with Departmental Representative for confirmation of materials, components, and items of equipment identified for removal and salvage from their present existing locations and as follows:
  - .1 Items that are turned over to Departmental Representative.
  - .2 Off-site or on-site storage locations.
  - .3 Confirmation of items that are renovated or refurbished ready for reinstallation as a part of Work.
  - .4 Confirmation of items that Departmental Representative will not re use, but will retain as follows:
    - .1 Contractor is responsible for loading and handling identified salvaged items using their own forces and equipment.

## Part 2 Products

## 2.1 SALVAGED ITEMS

.1 Items salvaged by Contractor include, but are not limited to:

Work	Deliver To
Diversion of miscellaneous office furniture from landfill through re-use/donation or recycling facilities (ie. metal filing cabinets and shelving, office desks and chairs, demountable panel partition systems, window blinds, wood cabinets, etc.)	Off-site applicable re-use or recycling facility
Lighting fixtures for salvage and re-installation	Departmental Representative approved storage location on-site for future re-installation
Diversion of miscellaneous metal mechanical equipment from landfill to appropriate recycling facility (ie. fan coil units, domestic cold water drinking fountains, mechanical piping (sprinkler, plumbing and chilled water), sheet metal ductwork and accessories, etc.)	Off-site applicable recycling facility
Carpet reclamation	Departmental Representative approved storage location on-site for future re-installation
Diversion of miscellaneous metal electrical conduits and wiring from landfill through recycling	Off-site applicable recycling facility
Diversion of architectural elements from landfill through re-use/donation to appropriate recycling facility (ie. ceiling grids, metal blinds, metal studs, doors and associated hardware, glazing, etc.)	Off-site applicable re-use or recycling facility
Diversion of miscellaneous packaging materials and cardboard from landfill through recycling facilities (ie. plastic wrap, cardboard, wood pallets, etc.)	Off-site applicable re-use or recycle facility

.2 Confirm with Departmental Representative additional items that appear salvageable prior to disposal.

#### Part 3 Execution

## 3.1 SALVAGE

- .1 Remove and handle salvageable items from site to minimize damage and to ensure that usability is maintained.
- .2 Clean, decontaminate, or remediate hazardous substances (lead based paint, asbestos dust, PCB residue, and similar substances) from salvaged materials so they are safe for reuse or resale.

NRC-CNRC	Section 02 42 00
Project No.	REMOVAL AND SALVAGE OF CONSTRUCITON MATERIALS
S77-6295	Page 3 of 3

- .3 Place materials on palettes or wrap in protective film to ensure that loose pieces and projections do not cause injury to personnel, and that salvaged items remain as complete units.
- .4 Clean items of construction or building debris, or materials that are not a part of salvaged work before delivering to Departmental Representative.

# **END OF SECTION**

## 1 GENERAL

#### 1.01 REFERENCE STANDARDS

- .1 CSA Group
  - .1 CSA C22.1-[12], Canadian Electrical Code, Part 1 (latest), Safety Standard for Electrical Installations.
  - .2 CAN/CSA-C22.3 No.1-[10], Overhead Systems.
  - .3 CAN3-C235-[83(R2010)], Preferred Voltage Levels for AC Systems, 0 to 50,000 V.
  - .4 Consider CSA Electrical Bulletins in force at time of tender submission, while not identified and specified by number in this Division, to be forming part of related CSA Part II standard.
  - .5 Where requirements of this specification exceed those of above mentioned standards, this specification shall govern
  - .6 Notify the NRC Departmental Representative as soon as possible when requested to connect equipment supplied by NRC which is not CSA approved.
- .2 Institute of Electrical and Electronics (IEEE)/National ElectricalSafety Code Product Line (NESC)
  - .1 IEEE SP1122-[2000], The Authoritative Dictionary of IEEEStandards Terms, 7th Edition.

## 1.02 **DEFINITIONS**

.1 Electrical and electronic terms: unless otherwise specified or indicated, terms used in these specifications, and on drawings, are those defined by IEEE SP1122.

## 1.03 RELATED REQUIREMENTS

.1 26 05 32 - Outlet Boxes, Conduit Boxes and Fittings

### 1.04 PERMITS AND FEES

- .1 Submit to Electrical Inspection Department and Supply Authority necessary number of drawings and specifications for examination and approval prior to commencement of work.
- .2 Pay all fees required for the performance of the work.

## 1.05 INSPECTION AND FEES

- .1 Furnish a Certificate of Acceptance from the Authorized Electrical Inspection Department on completion of work.
- .2 Request and obtain Special Inspection approval from the Authorized Electrical Inspection Department for any non-CSA approved control panels or other equipment fabricated by the contractor as part of this contract.
- .3 Pay all fees required for inspections.

#### 1.06 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section [01 33 00 SubmittalProcedures].
- .2 Product Data:
  - .1 Submit manufacturer's instructions, printed product literature and data sheets for and include product characteristics, performance criteria, physical size, finishand limitations.
- .3 Shop drawings:
  - .1 Submit wiring diagrams and installation details of equipment indicating proposed location, layout and arrangement, controlpanels, accessories, piping, ductwork, and other items that must be shown to ensure co-ordinated installation.
  - .2 Identify on wiring diagrams circuit terminals and indicate internal wiring for each item of equipment and interconnectionbetween each item of equipment.
  - .3 Indicate of drawings clearances for operation, maintenance, and replacement of operating equipment devices.
  - .4 Submit electronic drawings and product data.
  - .5 If changes are required, notify Departmental Representative of these changes before they are made.

#### .4 Certificates:

- .1 Provide CSA certified equipment and material.
- .2 Where CSA certified equipment and material is not available, submit such equipment and material to Departmental Representative for approval before delivery to site.
- .3 Submit test results of installed electrical systems and instrumentation.
- .4 Submit, upon completion of Work, load balance report asdescribed in PART 3 LOAD BALANCE.
- .5 Manufacturer's Field Reports: submit to Departmental Representative manufacturer's written report, within [3] days of review, verifying compliance of Work and electrical system and instrumentation testing, as described in PART 3 FIELD QUALITY CONTROL.
- .6 Sustainable Design Submittals:
  - .1 Construction Waste Management:
    - .1 Submit project Waste Management Plan highlighting recycling and salvage requirements.

#### 1.07 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section [01 78 00 CloseoutSubmittals].
- .2 Operation and Maintenance Data: submit operation and maintenancedata for incorporation into manual.
  - .1 Provide for each system and principal item of equipment asspecified in technical sections for use by operation and maintenance personnel.
  - .2 Operating instructions to include following:
    - .1 Wiring diagrams, control diagrams, and control sequencefor each principal system and item of equipment.
    - .2 Start up, proper adjustment, operating, lubrication, and shutdown procedures.

NRC-CNRC	Section 26 05 00
Project No.	COMMON WORK RESULTS FOR ELECTRICAL
S77-6295	Page 3 of 10

- .3 Safety precautions.
- .4 Procedures to be followed in event of equipment failure.
- .5 Other items of instruction as recommended by manufacturer of each system or item of equipment.
- .3 Post instructions where directed.
- .4 For operating instructions exposed to weather, provide weather-resistant materials or weatherproof enclosures.
- .5 Ensure operating instructions will not fade when exposed to sunlight and are secured to prevent easy removal or peeling.

# 1.08 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance with manufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site inoriginal factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
  - .1 Store materials in dry location andin accordance with manufacturer's recommendations in clean,dry, well-ventilated area.
  - .2 Store and protect from nicks, scratches, andblemishes.
  - .3 Replace defective or damaged materials with new.

## 2 PRODUCTS

## 2.01 DESIGN REQUIREMENTS

- .1 Operating voltages: to CAN3-C235
- .2 Motors, electric heating, control and distribution devices and equipment to operate satisfactorily at 60 Hz within normal operating limits established by above standard.
  - .1 Equipment to operate in extreme operating conditions established in above standard without damage to equipment.
- .3 Language operating requirements: provide identification nameplates and labels for control items in English andFrench.
- .4 Use one nameplate or label for each language.

## 2.02 MATERIALS AND EQUIPMENT

- .1 Provide material and equipment in accordance with Section01 61 00 Common Product Requirements.
- .2 Material and equipment to be CSA certified. Where CSA certified material and equipment are not available, obtain special approval from Departmental Representative before delivery to site and submit such approval as described in PART 1 - ACTION AND INFORMATIONAL SUBMITTALS.
- .3 Factory assemble control panels and component assemblies.

# 2.03 ELECTRIC MOTORS, EQUIPMENT AND CONTROLS

.1 Verify installation and co-ordination responsibilities related tomotors, equipment and controls, as indicated.

## 2.04 WARNING SIGNS

- .1 Provide warning labels for equipment fed from two or more sources "DANGER MULTIPLE POWER FEED" black letters on a yellow background. These labels are available from NRC's Facilities Maintenance group in building M-19.
- .2 Provide warning signs, as specified or to meet requirements of Authorized Electrical Inspection Department and NRC Departmental Representative.
- .3 Decal signs, minimum size 175 x 250 mm

#### 2.05 WIRING TERMINATIONS

.1 Ensure lugs, terminals, screws used for termination of wiring aresuitable for either copper or aluminum conductors.

## 2.06 EQUIPMENT IDENTIFICATION

- .1 Identify electrical equipment with nameplates and labels as follows:
  - .1 Lamicoid nameplates shall be rigid lamicoid, minimum 1.5 mm (1/16") thick with:
    - .1 Black letters engraved on a white background for normal power circuits.
    - .2 Black letters engraved on a yellow background for emergency power circuits.
  - .2 White letters engraved on a red background for fire alarm equipment.
  - Minimum border of 3 mm (1/8"). Characters shall be 9 mm (3/8") in size unless otherwise specified.

## .4 Sizes as follows:

#### NAMEPLATE SIZES

Size 1	10 x 50 mm	1 line	3 mm high letters
Size 2	12 x 70 mm	1 line	5 mm high letters
Size 3	12 x 70 mm	2 lines	3 mm high letters
Size 4	20 x 90 mm	1 line	8 mm high letters

#### NAMEPLATE SIZES

Size 5	20 x 90 mm	2 lines	5 mm high letters
Size 6	25 x 100 mm	1 line	12 mm high letters
Size 7	25 x 100 mm	2 lines	6 mm high letters

- .2 Labels: embossed plastic labels with [6] mm high letters unless specified otherwise.
  - .1 Black letters engraved on a white background for normal power circuits.
  - .2 Black letters engraved on a yellow background for emergency power circuits.
  - .3 White letters engraved on a red background for fire alarm equipment.
- .3 Wording on nameplates and labels to be approved by Departmental Representative prior to manufacture.
- .4 Allow for minimum of twenty-five (25) letters per nameplate and label.
- .5 Nameplates for terminal cabinets and junction boxes to indicate system and/or voltage characteristics.
- .6 Disconnects, starters and contactors: indicate equipment being controlled and voltage.
- .7 Terminal cabinets and pull boxes: indicate system and voltage.
- .8 Transformers: indicate capacity, primary and secondary voltages.
- .9 Identify with size 1 labels, or an alternate approved by the NRC Departmental Representative, all electrical outlets shown on drawings and/or mentioned in the specifications. These are the lighting switches, exit signs, recessed and surface mounted receptacles such as those in offices and service rooms and used to plug in office equipment, telecommunication equipment or small portable tools. Indicate only the source of power (Ex. for a receptacle fed from panel L32 circuit #1: "L32-1").
- in the specification such as motor control centers, switchgear, splitters, fused switches, isolation switches, motor starting switches, starters, molded case breaker, power breaker, panelboards, transformers, high voltage cables, industrial type receptacles, junction boxes, control panels, etc., regardless of whether or not the electrical equipment was furnished under this section of the specification. Example: A new 120/240 volt single phase circuit breaker panelboard, L16, is fed from panelboard LD1 circuit 10.

"PANEL L16 120/240 V FED FROM LD1-10"

"PANNEAU L16 120/240 V ALIMENTE PAR LD1-10"

.11 Coordinate names of equipment and systems with other Divisions to ensure that names and numbers

# Section 26 05 00 COMMON WORK RESULTS FOR ELECTRICAL Page 6 of 10

match.

- .12 For all interior nameplates, mount nameplates using two-sided tape.
- .13 For all exterior nameplates, mount nameplates using self-tapping 2.3 mm (3/32") dia. slot head screws two per nameplate for nameplates under 75 mm (3") in height and a minimum of 4 for larger nameplates. Holes in nameplates to be 3.7 mm (3/16") diameter to allow for expansion of nameplate due to exterior conditions.
  - .1 No drilling is to be done on live equipment.
  - .2 Metal filings from drilling are to be vacuumed from the enclosure interiors.
- .14 Identify lighting fixtures which are connected to emergency power with a label "EMERGENCY LIGHTING/ÉCLAIRAGE D'URGENCE", black letters on a yellow background. These labels are available from NRC's Facilities Maintenance group in building M-19. Lighting fixtures which are connected to normal power are not to be identified.
- .15 Provide neatly typed updated circuit directories in a plastic holder on the inside door of new or modified panelboards in the contract.

#### 2.07 WIRING IDENTIFICATION

- .1 Identify wiring with permanent indelible identifying markings, humbered or coloured plastic tapes, on both ends of phase conductors of feeders and branch circuit wiring.
- .2 Maintain phase sequence and colour coding throughout.
- .3 Colour coding: to CSA C22.1
- .4 Use colour coded wires in communication cables, matched throughoutsystem.

## 2.08 CONDUIT AND CABLE IDENTIFICATION

- .1 Colour code conduits, boxes and metallic sheathed cables.
- .2 Provide factory painted, colour-coded EMT for new conduits. Apply paint to the covers of junction boxes and condulets of existing conduits. Colour code as follows:
  - .1 Fire alarm red
  - .2 Emergency power circuits yellow
  - .3 Voice/data blue
  - .4 Gas detection system purple
  - .5 Building Automation system orange
  - .6 Other base building low voltage control system white
  - .7 Security system green
  - .8 Standalone control system black
- .3 All other systems to follow site instruction from NRC departmental representative.
- .4 Identify all electrical circuits in every junction box and pull box on the box cover with size 5 label.
- .5 Identify all electrical circuits on each conduit end where conduit penetrates a wall enclosure, junction box or pull box, and halfway of each conduit run between walls, enclosures, junction

boxes or pull boxes with size 1 label.

.6 Identify electrical circuit on each cable 250MCM or larger with nameplate, or cable 4/0 and smaller with size 1 label, on every splitter, every 10m of each cable run and cable end where cable penetrates a wall, enclosure, junction box or pull box

#### 2.09 FINISHES

- .1 Shop finish metal enclosure surfaces by application of rust resistant primer inside and outside, and at least two coats offinish enamel.
  - .1 Paint outdoor electrical equipment "equipment green" finish to EEMAC Y1-1-1955.
  - .2 Paint indoor switchgear and distribution enclosures light gray to gray to EEMAC 2Y-1-1958.
- .2 Clean and touch up surfaces of shop-painted equipment scratched or marred during shipment or installation, to match original paint.

## 3 EXECUTION

# 3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substratepreviously installed under other Sections or Contracts are acceptable for installation in accordance with manufacturer's written instructions.
  - .1 Visually inspect substrate in presence of DepartmentalRepresentative.
  - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
  - .3 Proceed with installation only after unacceptable conditionshave been remedied and after receipt of written approval to proceed from Departmental Representative.

#### 3.02 INSTALLATION

- .1 Do complete installation in accordance with CSA C22.1 except wherespecified otherwise
- .2 Do overhead and underground systems in accordance with CAN/CSA-C22.3 No.1 except where specified otherwise

## 3.03 NAMEPLATES AND LABELS

.1 Ensure manufacturer's nameplates, CSA labels and identificationnameplates are visible and legible after equipment is installed.

### 3.04 CONDUIT AND CABLE INSTALLATION

- .1 Install conduit and sleeves prior to pouring of concrete.
  - 1 Sleeves through concrete: schedule 40 steel pipe sized for free passage of conduit, and protruding 50 mm.
- .2 If plastic sleeves are used in fire rated walls or floors, removebefore conduit installation.
- .3 Install cables, conduits and fittings embedded or plastered over, close to building structure so furring can be kept to minimum.

#### 3.05 LOCATION OF OUTLETS

- .1 Locate outlets in accordance with Section 26 05 32 OutletBoxes, Conduit Boxes and
- .2 Fittings.
- .3 Do not install outlets back-to-back in wall; allow minimum 150mm horizontal clearance between boxes.
- .4 Change location of outlets at no extra cost or credit, providing distance does not exceed 3000 mm, and information is given before installation.
- .5 Locate light switches on latch side of doors.
  - .1 Locate disconnect devices in mechanical and elevator machinerooms on latch side of floor.

## 3.06 MOUNTING HEIGHTS

- .1 Mounting height of equipment is from finished floor to centrelineof equipment unless specified or indicated otherwise.
- .2 If mounting height of equipment is not specified or indicated, verify before proceeding with installation.
- .3 Install electrical equipment at following heights unless indicated otherwise.
  - .1 Local switches: 1400 mm.
  - .2 Wall receptacles:
    - .1 General: 300 mm.
    - .2 Above top of continuous baseboard heater: 200 mm.
    - .3 Above top of counters or counter splash backs: 175 mm.
    - .4 In mechanical rooms: 1400 mm.
  - .3 Panelboards: as required by Code or as indicated.
  - .4 Telephone and interphone outlets: 300 mm.
  - .5 Wall mounted telephone and interphone outlets: 1500 mm.
  - .6 Fire alarm stations: 1500 mm.
  - .7 Fire alarm bells: 2100 mm.
  - .8 Television outlets: 300 mm.
  - .9 Wall mounted speakers: 2100 mm.
  - .10 Clocks: 2100 mm.
  - .11 Door bell pushbuttons: 1500 mm.

### 3.07 CO-ORDINATION OF PROTECTIVE DEVICES

.1 Ensure circuit protective devices such as overcurrent trips, relays and fuses are installed to required values and settings.

## 3.08 FIELD QUALITY CONTROL

.1 Load Balance:

- .1 Measure phase current to panelboards with normal loads (lighting) operating at time of acceptance; adjust branchcircuit connections as required to obtain best balance of current between phases and record changes.
- .2 Measure phase voltages at loads and adjust transformer taps towithin 2% of rated voltage of equipment.
- .3 Provide upon completion of work, load balance report as directed in PART 1 ACTION AND INFORMATIONAL SUBMITTALS, phase and neutral currents on panelboards, dry-core transformers and motor control centres, operating under normal load, as well as hour and date on which each load wasmeasured, and voltage at time of test.

## .2 Conduct following tests.

- .1 Power generation and distribution system including phasing, voltage, grounding and load balancing.
- .2 Circuits originating from branch distribution panels.
- .3 Lighting and its control.
- .4 Motors, heaters and associated control equipment including sequenced operation of systems where applicable.
- .5 Systems: fire alarm.
- .6 Insulation resistance testing:
  - .1 Megger circuits, feeders and equipment up to 350 V with a 500 V instrument.
  - .2 Megger 350-600 V circuits, feeders and equipment with a1000 V instrument.
  - .3 Check resistance to ground before energizing.
- .3 Carry out tests in presence of Departmental Representative.
- .4 Provide instruments, meters, equipment and personnel required toconduct tests during and at conclusion of project.
- .5 Manufacturer's Field Services:
  - .1 Obtain written report from manufacturer verifying compliance of Work, in handling, installing, applying, protecting and cleaning of product and submit Manufacturer's Field Reports asdescribed in PART 1 ACTION AND INFORMATIONAL SUBMITTALS.
  - .2 Provide manufacturer's field services consisting of productuse recommendations and periodic site visits for inspection product installation in accordance with manufacturer's instructions.

## 3.09 SYSTEM STARTUP

- .1 Instruct Departmental Representative and operating personnel in operation, care and maintenance of systems, system equipment and components.
- .2 Arrange and pay for services of manufacturer's factory service engineer to supervise start-up of installation, check, adjust, balance and calibrate components and instruct operating personnel.
- .3 Provide these services for such period, and for as many visits as necessary to put equipment in operation, and ensure that operating personnel are conversant with aspects of its care and operation.

## 3.10 CLEANING

- .1 Progress Cleaning:
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish,tools and equipment.
- .3 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

# 3.11 WORK ON LIVE EQUIPMENT

- .1 NRC requires that work be performed on non-energized equipment, installation, conductors and power panels. For purposes of quotation assume that all work is to be done after normal working hours and that equipment, installation, conductors and power panels are to be de-energized when worked upon.
- .2 Coordinate all shutdowns with Departmental Representative.

END OF SECTION

## Part 1 General

#### 1.1 SUMMARY

.1 This Section includes requirements for selective demolition and removal of electrical, communications and safety and security components including removal of conduit, junction boxes, and panels to source (home run removal) and incidentals required to complete work described in this Section ready for new construction.

## 1.2 RELATED REQUIREMENTS

- .1 Section 01 10 00 General Instructions
- .2 Section 01 74 19 Waste Management and Disposal
- .3 Section 02 42 00 Removal and Salvage of Construction Materials

## 1.3 REFERENCE STANDARDS

- .1 CSA Group (CSA)
  - .1 CSA S350 M1980 (R2003), Code of Practice for Safety in Demolition of Structures

## 1.4 **DEFINITIONS**

- .1 Demolish: Detach items from existing construction and legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .2 Remove: Planned deconstruction and disassembly of electrical items from existing construction including removal of conduit, junction boxes, cabling and wiring from electrical component to panel taking care not to damage adjacent assemblies designated to remain; legally dispose of items off site, unless indicated as removed and salvaged, or removed and reinstalled.
- .3 Remove and Salvage: Detach items from existing construction and deliver them to Departmental Representative ready for reuse.
- .4 Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated.
- .5 Existing to Remain: Existing items of construction that are not removed and that are not otherwise indicated as being removed and salvaged, or removed and reinstalled.

## 1.5 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Action Submittals: Provide in accordance with Section 01 10 00 General Instructions before starting work of this Section:
  - .1 Construction Waste Management Plan (CWM Plan): Submit plan addressing opportunities for reduction, reuse, or recycling of materials prepared in accordance with Section 01 74 19 Waste Management and Disposal.
  - .2 Landfill Records: Indicate receipt and acceptance of selective demolition waste and hazardous wastes by a landfill facility licensed to accept hazardous wastes.

## 1.6 ADMINISTRATIVE REQUIREMENTS

- .1 Coordination: Coordinate work of this Section to avoid interference with work by other Sections.
- .2 Scheduling: Account for Departmental Representative continued occupancy requirements during selective demolition with Section 02 41 19.16 Selective Interior Demolition.

## 1.7 QUALITY ASSURANCE

- .1 Regulatory Requirements: Perform work of this Section in accordance with:
  - .1 Federal Workers' Compensation Service.
  - .2 Government of Canada, Labour Program: Workplace Safety.

#### 1.8 SITE CONDITIONS

- .1 Existing Conditions: Condition of materials identified as being salvaged or demolished are based on their observed condition on their observed condition at time of site examination before tendering.
- .2 Discovery of Hazardous Substances: It is not expected that Hazardous Substances will be encountered in Work; immediately notify Departmental Representative if materials suspected of containing hazardous substances are encountered and perform following activities:
  - .1 Refer to Section 01 10 00 General Instructions for directives associated with specific material types.
  - .2 Hazardous substances will be as defined in Hazardous Products Act.
  - .3 Stop work in area of suspected hazardous substances.
  - .4 Take preventative measures to limit users' and workers' exposure, provide barriers and other safety devices and do not disturb.
  - .5 .Hazardous substances will be removed by Departmental Representative under a separate contract or as a change to Work.
  - .6 Proceed only after written instructions have been received from Departmental Representative.

#### 1.9 SALVAGE AND DEBRIS MATERIALS

- .1 Demolished items become Contractor's property and will be removed from Project site; except for items indicated as being reused, salvaged, or otherwise indicated to remain Departmental Representative's property.
- .2 Carefully remove materials and items designated for salvage and store in a manner to prevent damage or devaluation of materials in accordance with Section 02 42 00 Removal and Salvage of Construction Materials.
  - .1 Leave main electrical distribution panel in place; panel can be used for temporary construction power for this and subsequent contracts in accordance with Section 01 10 00 General Instructions; coordinate temporary power connections with Departmental Representative.

#### Part 2 Products

## 2.1 MATERIALS

- .1 General Patching and Repair Materials: Refer to Section 02 41 19.16 Selective Interior Demolition or listing of patching and repair materials incidental to removal or demolition of components associated with work of this Section.
- .2 Electrical Repair Materials: Use only new materials, CSA or ULC labelled as appropriate and matching components remaining after work associated with components identified for removal or demolition are completed.
- .3 Fire stopping Repair Materials: Use fire stopping materials compatible with existing fire stopping systems where removal or demolition work affects rated assemblies, restore to match existing fire rated performance.

#### Part 3 Execution

#### 3.1 EXAMINATION

.1 Verification of Existing Conditions: Visit site, thoroughly examine and become familiar with conditions that may affect the work of this Section before tendering the Bid; Departmental Representative will not consider claims for extras for work or materials necessary for proper execution and completion of the contract that could have been determined by a site visit.

## 3.2 PREPARATION

- .1 Protection of Existing Systems to Remain: Protect systems and components indicated to remain in place during selective demolition operations and as follows:
  - .1 Prevent movement and install bracing to prevent settlement or damage of adjacent services and parts of existing buildings scheduled to remain.

# Section 26 05 05 SELECTIVE DEMOLITION FOR ELECTRICAL Page 4 of 5

- .2 Departmental Representative and cease operations where safety of buildings being demolished, adjacent structures or services appears to be endangered and await additional instructions before resuming demolition work specified in this Section.
- .3 Prevent debris from blocking drainage inlets.
- .4 Protect mechanical systems that will remain in operation.
- .2 Protection of Building Occupants: Sequence demolition work so that interference with the use of the building by the Departmental Representative and users is minimized and as follows:
  - .1 Prevent debris from endangering safe access to and egress from occupied buildings.
  - .2 Notify Departmental Representative and cease operations where safety of occupants appears to be endangered and await additional instructions before resuming demolition work specified in this Section.

#### 3.3 EXECUTION

- .1 Demolition and Removal: Coordinate requirements of this Section with information contained in Section 02 41 19.16 Selective Interior Demolition and as follows:
  - .1 Maintain electrical service and main distribution panel as is, ready for subsequent Work.
  - .2 Remove existing luminaires, electrical devices and equipment including associated conduits, boxes, wiring, and similar items unless specifically noted otherwise.
  - .3 Disconnect and remove existing fire alarm system including associated conduits, boxes, wiring, and similar items unless specifically noted otherwise.
  - .4 Disconnect and remove communication systems including associated conduits, boxes, cabling, and similar items unless specifically noted otherwise.
  - .5 Disconnect and remove telephone outlets, associated conduit, cabling and sub terminal backboards and related accessories; maintain telephone service and main terminal backboard as is.
  - .6 Perform demolition work in a neat and workmanlike manner:
    - .1 Remove tools or equipment after completion of work, and leave site clean and ready for subsequent renovation work.
    - .2 Repair and restore damages caused as a result of work of this Section to match existing materials and finishes.
  - .7 Place weatherproof blank cover plates on exterior outlet boxes remaining after demolition and removal activities.
  - .8 Remove existing conduits, boxes, cabling and wiring associated with removed luminaires, electrical devices and equipment.
  - .9 Grind off conduits and make flush with surface of concrete where conduits are cast into concrete; seal open ends of conduit with silicone sealant and leave in place.
  - .10 Seal open ends of conduit with silicone sealant and leave in place where they are inaccessible or cannot be removed without damaging adjacent construction.

## 3.4 CLOSEOUT ACTIVITIES

.1 Demolition Waste Disposal: Arrange for legal disposal and remove demolished materials to accredited provincial landfill site or alternative disposal site (recycle centre) except where

NRC-CNRC Project No. S77-6295

# Section 26 05 05 SELECTIVE DEMOLITION FOR ELECTRICAL Page 5 of 5

explicitly noted otherwise for materials being salvaged for re use in new construction in accordance with Section  $02\ 42\ 00$  - Removal and Salvage of Construction Materials.

# **END OF SECTION**

#### 1 **GENERAL**

#### 1.01 REFERENCE STANDARDS

- .1 CSA Group (CSA)
  - .1 CAN/CSA-C22.2 No.18-[98(R2003)], Outlet Boxes, ConduitBoxes and Fittings.
  - .2 CAN/CSA-C22.2 No.65-[03(R2008)], Wire Connectors (Tri-National Standard with UL 486A-486B and NMX-J-543- ANCE-03).
- .2 Electrical and Electronic Manufacturers' Association of Canada(EEMAC)
  - EEMAC 1Y-2-[1961], Bushing Stud Connectors and AluminumAdapters (1200 .1 Ampere Maximum Rating).
- .3 National Electrical Manufacturers Association (NEMA)

#### ACTION AND INFORMATIONAL SUBMITTALS 1.02

- Submit in accordance with Section [00 10 00]. .1
- .2 Product Data:
  - Submit manufacturer's instructions, printed product literatureand data sheets for [wire and .1 box connectors] and include product characteristics, performance criteria, physical size, finish and limitations.

#### **CLOSEOUT SUBMITTALS** 1.03

- Submit in accordance with Section 01 78 00 CloseoutSubmittals. .1
- .2 Operation and Maintenance Data: submit operation and maintenance data for [wire and box connectors] for incorporation into manual.

#### 1.04 DELIVERY, STORAGE AND HANDLING

- Deliver, store and handle materials in accordance withmanufacturer's written instructions. .1
- .2 Delivery and Acceptance Requirements: deliver materials to site inoriginal factory packaging, labelled with manufacturer's name andaddress.
- .3 Storage and Handling Requirements:
  - Store materials in dry location andin accordance with manufacturer's recommendations in .1 clean, dry, well-ventilated area.
  - .2 Store and protect wire and box connectors from nicks, scratches, and blemishes.
  - .3 Replace defective or damaged materials with new.

#### 2 **PRODUCTS**

#### 2.01 **MATERIALS**

.1 Pressure type wire connectors to: CAN/CSA-C22.2 No.65, with current carrying parts of copper sized to fit copper conductors asrequired.

NRC-CNRC	Section 26 05 20
Project No.	WIRE AND BOX CONNECTORS (0-1000 V)
S77-6295	Page 2 of 2

- .2 Fixture type splicing connectors to: CAN/CSA-C22.2 No.65, withcurrent carrying parts of copper sized to fit copper conductors 10 AWG or less.
- .3 Bushing stud connectors: NEMA to consist of:
  - .1 Connector body and stud clamp for stranded copper conductors.
  - .2 Clamp for stranded copper conductors.
  - .3 Stud clamp bolts.
  - .4 Bolts for copper conductors.
  - .5 Sized for conductors as indicated.
- .4 Clamps or connectors for flexible conduit as required to: CAN/CSA-C22.2 No.18.

### 3 EXECUTION

# 3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substrate previously installed under other Sections or Contracts are acceptable for wire and box connectors installation in accordance with manufacturer's written instructions.
  - .1 Visually inspect substrate in presence of DepartmentalRepresentative.
  - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
  - .3 Proceed with installation only after unacceptable conditionshave been remedied and after receipt of written approval to proceed from Departmental Representative.

### 3.02 INSTALLATION

- .1 Remove insulation carefully from ends of conductors and cables and:
  - .1 Install mechanical pressure type connectors and tighten screws with appropriate compression tool recommended by manufacturer. Installation shall meet secureness tests inaccordance with CAN/CSA-C22.2 No.65
  - .2 Install fixture type connectors and tighten to CAN/CSA-C22.2No.65. Replace insulating cap.
  - .3 Install bushing stud connectors in accordance with NEMA.

## 3.03 CLEANING

- .1 Progress Cleaning:
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish,tools and equipment.
- .3 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

NRC-CNRC Section 26 05 21
Project No. WIRES AND CABLES (0-1000 V)
S77-6295 Page 1 of 3

## 1 GENERAL

### 1.01 REFERENCE STANDARDS

- .1 CSA C22.1-[Latest], Canadian Electrical Code, Part 1 (22nd Edition), Safety Standard for Electrical Installations.
- .2 CSA C22.2 No.41-[Latest], Grounding and Bonding Equipment (Tri-National Standard, with NMX-J-590ANCE and UL 467)

# 1.02 RELATED REQUIREMENTS

- .1 26 05 00 Common Work Results for Electrical
- .2 26 05 20 Wire and Box Connectors (0-1000 V)
- .3 26 05 34 Conduits, Conduit Fastenings and Conduit Fittings

### 1.03 PRODUCT DATA

.1 Provide product data in accordance with Section 00 10 00.

## 1.04 DELIVERY, STORAGE AND HANDLING

.1 Deliver, store and handle materials in accordance and with manufacturer's written instructions.

## 2 PRODUCTS

#### 2.01 BUILDING WIRES

- .1 Conductors: stranded copper, minimum 12AWG for power circuit.
- .2 Type R90 XLPE cross-link polyethylene stranded for applications using wires sized No. 8 and larger.
- .3 Type T90 stranded for applications using wires sized No. 10 and smaller.
- .4 Neutral wire: continuous throughout its length without breaks.
- .5 Separate insulated green grounding conductors in all electrical conduits

### 2.02 TECK 90 CABLE

- .1 Cable: in accordance with Section 26 05 00 Common Work Resultsfor Electrical.
- .2 Conductors:
  - .1 Grounding conductor: stranded copper.
  - .2 Circuit conductors: stranded copper
- .3 Insulation:
  - .1 Cross-linked polyethylene XLPE.
  - .2 Rating: 1000 V.
- .4 Inner jacket: Black, lead-free, flame retardant, moisture and sunlight resistant Polyvinyl Chloride.
- .5 Armour: Aluminum interlocked armour.

NRC-CNRC Section 26 05 21
Project No. WIRES AND CABLES (0-1000 V)
S77-6295 Page 2 of 3

Overall covering: Black, lead-free, flame retardant, moisture and sunlight resistant Polyvinyl Chloride.

## .7 Fastenings:

- .1 One hole malleable iron straps to secure surface cables 50 mm and smaller. Two hole steel strapsfor cables larger than 50 mm.
- .2 Channel type supports for two or more cables.
- .3 Threaded rods: 6 mm diameter to support suspended channels.

### .8 Connectors:

- .1 Water tight approved for TECK cable.
- .2 Explosion proof approved for TECK cable in hazardous area.

## 2.03 ARMOURED CABLES

- .1 Conductors: insulated, copper, size as indicated.
- .2 Type: AC90.
- .3 Armour: interlocking type fabricated from aluminum strip.
- .4 Connectors: anti short connectors.
- .5 Use AC90 (BX) cable only under the following conditions:
  - .1 Wiring from a junction box to a recessed lighting fixture in suspended ceilings. Cable length not to exceed 1.5 m (5'), or
  - Wiring switches or receptacles in existing or new hollow gypsum partitions, vertical runs only with cable length not to exceed 3.5m (12'), or
  - .3 When specifically called for on drawings or approved in writing by departmental representative.
  - .4 AC90 shall not be used in isolated walls or masonry walls.
  - .5 Only AC90 cable of No. 12 AWG will be accepted.

### 2.04 CONTROL CABLES

- .1 Type: LVT: soft annealed copper conductors, sized asindicated:
  - .1 Insulation: thermoplastic.
  - .2 Sheath: thermoplastic jacket.
- .2 Type: Specified on drawing.

## 2.05 NON-METALLIC SHEATHED CABLE

.1 Non-metallic sheathed copper cable type: ROMEX SIMpull NMD90 nylon, size as indicated.

### 3 EXECUTION

# 3.01 FIELD QUALITY CONTROL

- .1 Perform tests in accordance with Section [26 05 00 Common WorkResults for Electrical].
- .2 Perform tests before energizing electrical system.

## 3.02 GENERAL CABLE INSTALLATION

- .1 Lay cable in cable trays in accordance with Section [26 05 36 -Cable Trays for Electrical Systems].
- .2 Terminate cables in accordance with Section [26 05 20 Wire andBox Connectors (0-1000 V)].
- .3 Cable Colour Coding: to Section [26 05 00 Common Work Results for Electrical].
- .4 Conductor length for parallel feeders to be identical.
- .5 Lace or clip groups of feeder cables at distribution centres, pullboxes, and termination points.
- .6 Wiring in walls: typically drop or loop vertically from above to better facilitate future renovations. Generally wiring from belowand horizontal wiring in walls to be avoided unless indicated.
- .7 Branch circuit wiring for surge suppression receptacles and permanently wired computer and electronic equipment to be 2-wirecircuits only, i.e. common neutrals not permitted.
- .8 Provide numbered wire collars for control wiring. Numbers to correspond to control shop drawing legend. Obtain wiring diagramfor control wiring.

## 3.03 INSTALLATION OF BUILDING WIRES

- .1 Install wiring as follows:
  - In conduit systems in accordance with Section [26 05 34 Conduits, Conduit Fastenings and Conduit Fittings].

## 3.04 INSTALLATION OF TECK90 CABLE (0 -1000 V)

- .1 Group cables wherever possible on channels.
- .2 Install cable, securely supported bystraps.

### 3.05 INSTALLATION OF ARMOURED CABLES

.1 Group cables wherever possible on channels.

### 3.06 INSTALLATION OF CONTROL CABLES

- .1 Install control cables in conduit.
- .2 Ground control cable shield.

## 3.07 INSTALLATION OF NON-METALLIC SHEATHED CABLE

- .1 Install cables.
- .2 Install straps and box connectors to cables as required.

#### **END OF SECTION**

### 1 GENERAL

### 1.01 REFERENCE STANDARDS

- .1 CSA Group
  - .1 CSA C22.1-12, Canadian Electrical Code, Part 1 (22nd Edition), Safety Standard for Electrical Installations.
  - .2 CSA C22.2 No.41-[Latest], Grounding and Bonding Equipment (Tri-National Standard, with NMX-J-590ANCE and UL 467).
  - .3 CSA C22.2 No.65-13, Wire connectors (Tri-NationalStandard, with UL 486A-486B NMX-J-543-ANCE).

# 1.02 RELATED REQUIREMENTS

.1 26 05 00 - Common Work Results

#### 1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Submit in accordance with Section 00 10 00.
- .2 Product Data:
  - .1 Submit manufacturer's instructions, printed product literatureand data sheets for [connectors and terminations] and includeproduct characteristics, performance criteria, physical size, finish and limitations.
- .3 Certificates: obtain inspection certificate of compliance coveringhigh voltage stress from inspection authority and include it with maintenance manuals.

### 1.04 CLOSEOUT SUBMITTALS

- .1 Submit in accordance with Section 01 78 00 CloseoutSubmittals.
- .2 Operation and Maintenance Data: submit operation and maintenancedata for connectors and terminations for incorporation into manual.

## 1.05 DELIVERY, STORAGE AND HANDLING

- .1 Deliver, store and handle materials in accordance withmanufacturer's written instructions.
- .2 Delivery and Acceptance Requirements: deliver materials to site inoriginal factory packaging, labelled with manufacturer's name and address.
- .3 Storage and Handling Requirements:
  - .1 Store materials indoors in dry location and in accordance with manufacturer's recommendations in clean,dry, well-ventilated area.
  - .2 Replace defective or damaged materials with new.

## 2 PRODUCTS

#### 2.01 CONNECTORS AND TERMINATIONS

- .1 Copper compression connectors to CSA C22.2 No.65 as required sized for conductors.
- .2 When used in hazardous area, connectors shall be certified for such location in Class, Division and

NRC-CNRC	Section 26 05 22
Project No.	CONNECTORS AND TERMINATIONS
S77-6295	Page 2 of 2
a	

Group.

- .3 For conductor size of 8 AWG or larger, use bolted or compression solderless type connectors.
- .4 Use high temperature connectors and insulation on all connections of high temperature conductors.
- .5 Where connector types are called for on the drawings or in the specification, do not use other types.
- .6 Lugs, terminals, screws used for termination of wiring to be suitable for copper conductors.
- .7 Contact aid for aluminum cables where applicable.
- .8 For fire alarm wiring refer to Section 28 31 00.
- .9 Make joints, taps and splices in approved boxes with solderless connectors. Joints and/or splices are not acceptable inside a panelboard.

## 3 EXECUTION

### 3.01 EXAMINATION

- .1 Verification of Conditions: verify that conditions of substratepreviously installed under other Sections or Contracts are acceptable for connectors and terminations installation in accordance with manufacturer's written instructions.
  - .1 Visually inspect substrate in presence of DepartmentalRepresentative.
  - .2 Inform Departmental Representative of unacceptable conditions immediately upon discovery.
  - .3 Proceed with installation only after unacceptable conditionshave been remedied.

## 3.02 INSTALLATION

- .1 Install stress cones, terminations, and splices in accordance withmanufacturer's instructions.
- .2 Bond and ground as required to CSA C22.2No.41.

#### 3.03 CLEANING

- .1 Progress Cleaning:
  - .1 Leave Work area clean at end of each day.
- .2 Final Cleaning: upon completion remove surplus materials, rubbish,tools and equipment.
- .3 Remove recycling containers and bins from site and dispose of materials at appropriate facility.

## **END OF SECTION**

S77-6295

### 1 GENERAL

## 1.01 REFERENCE STANDARDS

- .1 CSA Group (CSA)
  - .1 CAN/CSA C22.2 No. 18-[98(R2003)], Outlet Boxes, ConduitBoxes, Fittings and Associated Hardware, A National Standard of Canada.
  - .2 CSA C22.2 No. 45-[M1981(R2003)], Rigid Metal Conduit.
  - .3 CSA C22.2 No. 56-[04], Flexible Metal Conduit and Liquid-Tight Flexible Metal
  - .4 CSA C22.2 No. 83-[M1985(R2003)], Electrical MetallicTubing.
  - .5 CSA C22.2 No. 211.2-[M1984(R2003)], Rigid PVC (Unplasticized) Conduit.
  - .6 CAN/CSA C22.2 No. 227.3-[05], Nonmetallic Mechanical Protection Tubing (NMPT), A National Standard of Canada(February 2006).

# 1.02 RELATED REQUIREMENTS

.1 Section 260521 – Wires and Cables 0-1000V.

#### 1.03 ACTION AND INFORMATIONAL SUBMITTALS

- .1 Provide submittals in accordance with Section 01 33 00 -Submittal Procedures.
- .2 Product data: submit manufacturer's product literature, specifications and datasheets.
  - .1 Submit cable manufacturing data.
- .3 Quality assurance submittals:
  - .1 Test reports: submit certified test reports.
  - .2 Certificates: submit certificates signed by manufacturer certifying that materials comply with specified performancecharacteristics and physical properties.
  - .3 Instructions: submit manufacturer's installation instructions.

### 1.04 WASTE MANAGEMENT AND DISPOSAL

- Separate waste materials for reuse and recycling inaccordance with Section [01 74 19
   Waste Management and Disposal].
- .2 Place materials defined as hazardous or toxic waste in designated containers.
- .3 Ensure emptied containers are sealed and stored safely fordisposal away from children.

## 2 PRODUCTS

### 2.01 CABLES AND REELS

- .1 Provide cables on reels or coils.
  - .1 Mark or tag each cable and outside of each reel or coil, toindicate cable length, voltage rating, conductor size, andmanufacturer's lot number and reel number.

NRC-CNRC

Project No.

Section 26 05 34

CONDUITS, CONDUIT FASTENINGS AND CONDUIT FITTINGS

S77-6295

Page 2 of 4

- .2 Each coil or reel of cable to contain only one continuous cablewithout splices.
  - .3 Identify cables for exclusively dc applications.
  - .4 Reel and mark shielded cables rated [2,001] volts and above.

#### 2.02 CONDUITS

- . 1 Rigid metal conduit: to CSA C22.2 No. 45, hotdipped galvanized steel threaded.
- . 2 Epoxy coated conduit: to CSA C22.2 No. 45, with zinc coating and corrosion resistant epoxy finish inside and outside
- . 3 Electrical metallic tubing (EMT): to CSA C22.2 No. 83, withcouplings.
- . 4 Rigid pvc conduit: to CSA C22.2 No. 211.2
- . 5 Flexible metal conduit: to CSA C22.2 No. 56, liquid-tight flexible metal.
- . 6 Flexible pvc conduit: to CAN/CSA-C22.2 No. 227.3.

### 2.03 CONDUIT FASTENINGS

- .1 One hole malleable irons traps to secure surfaceconduits 50 mm and smaller.
  - .1 Two hole steel straps for conduits larger than 50mm.
- .2 Beam clamps to secure conduits to exposed steel work.
- .3 Channel type supports for two or more conduits.
- .4 Threaded rods, 6 mm diameter, to support suspended channels.

#### 2.04 CONDUIT FITTINGS

- .1 Fittings: to CAN/CSA C22.2 No. 18, manufactured for use withconduit specified. Coating: same as conduit.
- .2 Ensure factory "ells" where 90 degrees bends for 25 mmand larger conduits.
- .3 Watertight connectors and couplings for EMT.
  - .1 Set-screws are not acceptable.

# 2.05 EXPANSION FITTINGS FOR RIGID CONDUIT

.1 Watertight expansion fittings with integral bonding jumpersuitable for linear expansion.

### 2.06 FISH CORD

.1 Polypropylene.

## 3 EXECUTION

#### 3.01 MANUFACTURER'S INSTRUCTIONS

.1 Compliance: comply with manufacturer's written recommendations orspecifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

# 3.02 INSTALLATION

NRC-CNRC
Project No.
CONDUITS, CONDUIT FASTENINGS AND CONDUIT FITTINGS
S77-6295
Page 3 of 4

- .1 Install conduits to conserve headroom in exposed locations and cause minimum interference in spaces through which they pass.
- .2 Use electrical metallic tubing (EMT) except where specified otherwise.
- .3 Use rigid pvc conduit underground.
- .4 Use flexible metal conduit for connection to surface or recessed fixtures work in movable metal partitions.
- .5 Use liquid tight flexible metal conduit for connection to motorsor vibrating equipment.
- .6 Use explosion proof flexible connection for connection to explosion proof motors.
- .7 Install conduit sealing fittings in hazardous areas.
  - .1 Fill with compound.
- .8 Install EMT conduit from computer room branchcircuit panel to junction box in sub-floor immediately below panel unless otherwise specified.
  - .1 Run flexible conduit from junction box to outlet boxes foreach computer in sub-floor.
- .9 Bend conduit cold:
  - .1 Replace conduit if kinked or flattened more than 1/10th of itsoriginal diameter.
- .10 Mechanically bend steel conduit over 41 mm diameter.
- .11 Field threads on rigid conduit must be of sufficient length todraw conduits up tight.
- .12 Install fish cord in empty conduits.
- .13 Remove and replace blocked conduit sections.
  - .1 Do not use liquids to clean out conduits.
- .14 Dry conduits out before installing wire.

## 3.03 SURFACE CONDUITS

- .1 Run parallel or perpendicular to building lines.
- .2 Locate conduits behind infrared or gas fired heaters with 1.5 mclearance.
- .3 Run conduits in flanged portion of structural steel.
- .4 Group conduits wherever possible on channels.
- .5 Do not pass conduits through structural members except as indicated.
- .6 Do not locate conduits less than 75 mm parallel to steam or hotwater lines with minimum of 25 mm at crossovers.

#### 3.04 CONCEALED CONDUITS

- .1 Run parallel or perpendicular to building lines.
- .2 Do not install horizontal runs in masonry walls.
- .3 Do not install conduits in terrazzo or concrete toppings.

## 3.05 CONDUITS IN CAST-IN-PLACE CONCRETE

- .1 Locate to suit reinforcing steel.
  - .1 Install in centre one third of slab.

NRC-CNRC	Section 26 05 34
Project No.	CONDUITS, CONDUIT FASTENINGS AND CONDUIT FITTINGS
S77-6295	Page 4 of 4

- .2 Protect conduits from damage where they stub out of concrete.
- .3 Install sleeves where conduits pass through slab or wall.
- .4 Provide oversized sleeve for conduits passing through waterproofmembrane, before membrane is installed.
  - .1 Use cold mastic between sleeve and conduit.
- .5 Conduits in slabs: minimum slab thickness 4 times conduitdiameter.
- .6 Encase conduits completely in concrete with minimum 25 mm concretecover.
- .7 Organize conduits in slab to minimize cross-overs.

## 3.06 CONDUITS IN CAST-IN-PLACE SLABS ON GRADE

- .1 Run conduits 25 mm and larger below slab and encase in 75 mm concrete envelope.
  - .1 Provide 50 mm of sand over concrete envelope below floor slab.

## 3.07 CONDUITS UNDERGROUND

- .1 Slope conduits to provide drainage.
- .2 Waterproof joints (pvc excepted) with heavy coat of bituminous paint.

## 3.08 CLEANING

. 1 On completion and verification of performance of installation, remove surplus materials, excess materials, rubbish, tools and equipment.

### END OF SECTION

# TP1 Amount Payable - General

- 1.1 Subject to any other provisions of the contract, Her Majesty shall pay the Contractor, at the times and in the manner hereinafter set out, the amount by which
  - 1.1.1 the aggregate of the amounts described in TP2 exceeds
  - 1.1.2 the aggregate of the amounts described in TP3

and the Contractor shall accept that amount as payment in full satisfaction for everything furnished and done by him in respect of the work to which the payment relates.

# TP2 Amounts Payable to the Contractor

- 2.1 The amounts referred to in TP1.1.1 are the aggregate of
  - 2.1.1 the amounts referred to in the Articles of Agreement, and
  - 2.1.2 the amounts, if any, that are payable to the Contractor pursuant to the General Conditions.

## TP3 Amounts Payable to Her Majesty

- 3.1 The amounts referred to in TP1.1.2 are the aggregate of the amounts, in any, that the Contractor is liable to pay Her Majesty pursuant to the contract.
- 3.2 When making any payments to the Contractor, the failure of Her Majesty to deduct an amount referred to in TP3.1 from an amount referred to in TP2 shall not be constitute a waiver of the right to do so, or an admission of lack of entitlement to do so in any subsequent payment to the Contractor.

## TP4 Time of Payment

- 4.1 In these Terms of Payment
  - 4.1.1 The "payment period" means a period of 30 consecutive days or such other longer period as is agreed between the Contractor and the Departmental Representative.
  - 4.1.2 An amount is "due and payable" when it is due and payable by Her Majesty to the Contractor according to TP4.4, TP4.7 or TP4.10.
  - 4.1.3 An amount is overdue when it is unpaid on the first day following the day upon which it is due and payable.
  - 4.1.4 The "date of payment" means the date of the negotiable instrument of an amount due and payable by the Receiver General for Canada and given for payment.
  - 4.1.5 The "Bank Rate" means the discount rate of interest set by the Bank of Canada in effect at the opening of business on the date of payment.

4.2 The Contractor shall, on the expiration of a payment period, deliver to the Departmental Representative in respect of that payment period a written progress claim that fully describes any part of the work that has been completed, and any material that was delivered to the work site but not incorporated into the work during that payment period.

B

- 4.3 The Departmental Representative shall, not later than ten days after receipt by him of a progress claim referred to in TP4.2,
  - 4.3.1 inspect the part of the work and the material described in the progress claim; and
  - 4.3.2 issue a progress report, a copy of which the Departmental Representative will give to the Contractor, that indicates the value of the part of the work and the material described in the progress claim that, in the opinion of the Departmental Representative,
    - 4.3.2.1 is in accordance with the contract, and
    - 4.3.2.2 was not included in any other progress report relating to the contract.
- 4.4 Subject to TP1 and TP4.5 Her Majesty shall, not later than 30 days after receipt by the Departmental Representative of a progress claim referred to in TP4.2, pay the Contractor
  - 4.4.1 an amount that is equal to 95% of the value that is indicated in the progress report referred to in TP4.3.2 if a labour and material payment bond has been furnished by the Contractor, or
  - 4.4.2 an amount that is equal to 90% of the value that is indicated in the progress report referred to in TP4.3.2 if a labour and material payment bond has not been furnished by the Contractor.
- 4.5 It is a condition precedent to Her Majesty's obligation under TP4.4 that the Contractor has made and delivered to the Departmental Representative.
  - 4.5.1 a statutory declaration described in TP4.6 in respect of a progress claim referred to in TP4.2,
  - 4.5.2 in the case of the Contractor's first progress claim, a construction schedule in accordance with the relevant sections of the Specifications, and
  - 4.5.3 if the requirement for a schedule is specified, an update of the said schedule at the times identified in the relevant sections of the Specifications.
- 4.6 A statutory declaration referred to in TP4.5 shall contain a deposition by the Contractor that
  - 4.6.1 up to the date of the Contractor's progress claim, the Contractor has complied with all his lawful obligations with respect to the Labour Conditions; and
  - up to the date of the Contractor's immediately preceding progress claim, all lawful 4.6.2 obligations of the Contractor to subcontractors and suppliers of material in respect of the

work under the contract have been fully discharged.

- 4.7 Subject to TP1 and TP4.8, Her Majesty shall, not later than 30 days after the date of issue of an Interim Certificate of Completion referred to in GC44.2, pay the Contractor the amount referred to in TP1 less the aggregate of
  - 4.7.1 the sum of all payments that were made pursuant to TP4.4;
  - 4.7.2 an amount that is equal to the Departmental Representative's estimate of the cost to Her Majesty or rectifying defects described in the Interim Certificate of Completion; and
  - 4.7.3 an amount that is equal to the Departmental Representative's estimate of the cost to Her Majesty of completing the parts of the work described in the Interim Certificate of Completion other than the defects referred to in TP4.7.2.
- 4.8 It is a condition precedent to Her Majesty's obligation under TP4.7 that the Contractor has made and delivered to the Departmental Representative,
  - 4.8.1 a statutory declaration described in TP4.9 in respect of an Interim Certificate of Completion referred to in GC44.2, and
  - 4.8.2 if so specified in the relevant sections of the Specifications, and update of the construction schedule referred to in TP4.5.2 and the updated schedule shall, in addition to the specified requirements, clearly show a detailed timetable that is acceptable to the Departmental Representative for the completion of any unfinished work and the correction of all defects.
- 4.9 A statutory declaration referred to in TP4.8 shall contain a deposition by the contractor that up to the date of the Interim Certificate of Completion the Contractor has
  - 4.9.1 complied with all of the Contractor's lawful obligations with respect to the Labour Conditions:
  - 4.9.2 discharged all of the Contractor's lawful obligations to the subcontractors and suppliers of material in respect of the work under the contract; and
  - 4.9.3 discharged the Contractor's lawful obligations referred to in GC14.6.
- 4.10 Subject to TP1 and TP4.11, Her Majesty shall, not later than 60 days after the date of issue of a Final Certificate of Completion referred to in GC44.1, pay the Contractor the amount referred to in TP1 less the aggregate of
  - 4.10.1 the sum of all payments that were made pursuant to TP4.4; and
  - 4.10.2 the sum of all payments that were made pursuant to TP4.7.
- 4.11 It is a condition precedent to Her Majesty's obligation under TP4.10 that the Contractor has made and delivered a statutory declaration described in TP4.12 to the Departmental Representative.

4.12 A statutory declaration referred to in TP4.11 shall, in addition to the depositions described in TP4.9, contain a deposition by the Contractor that all of the Contractor's lawful obligations and any lawful claims against the Contractor that arose out of the performance of the contract have been discharged and satisfied.

# TP5 Progress Report and Payment Thereunder Not Binding on Her Majesty

Neither a progress report referred to in TP4.3 nor any payment made by Her Majesty pursuant to these Terms of Payment shall be construed as an admission by Her Majesty that the work, material or any part thereof is complete, is satisfactory or is in accordance with the contract.

# TP6 Delay in Making Payment

- Nothwithstanding GC7 any delay by Her Majesty in making any payment when it is due pursuant to these Terms of Payment shall not be a breach of the contract by Her Majesty.
- 6.2 Her Majesty shall pay, without demand from the Contractor, simple interest at the Bank Rate plus 1-1/4 per centum on any amount which is overdue pursuant to TP4.1.3, and the interest shall apply from and include the day such amount became overdue until the day prior to the date of payment except that
  - 6.2.1 interest shall not be payable or paid unless the amount referred to in TP6.2 has been overdue for more that 15 days following
    - 6.2.1.1 the date the said amount became due and payable, or
    - 6.2.1.2 the receipt by the Departmental Representative of the Statutory Declaration referred to in TP4.5, TP4.8 or TP4.11,

whichever is the later, and

6.6.2 interest shall not be payable or paid on overdue advance payments if any.

## **TP7 Right of Set-off**

- 7.1 Without limiting any right of set-off or deduction given or implied by law or elsewhere in the contract, Her Majesty may set off any amount payable to Her Majesty by the Contractor under this contract or under any current contract against any amount payable to the Contractor under this contract.
- 7.2 For the purposes of TP7.1, "current contract" means a contract between Her Majesty and the Contractor
  - 7.2.1 under which the Contractor has an undischarged obligation to perform or supply work, labour or material, or
  - 7.2.2 in respect of which Her Majesty has, since the date of which the Articles of Agreement were made, exercised any right to take the work that is the subject of the contract out of the Contractor's hands.

## TP8 Payment in Event of Termination

8.1 If the contract is terminated pursuant to GC41, Her Majesty shall pay the Contractor any amount that is lawfully due and payable to the Contractor as soon as is practicable under the circumstances.

### **TP9 Interest on Settled Claims**

- 9.1 Her Majesty shall pay to the Contractor simple interest on the amount of a settled claim at an average Bank Rate plus 1 1/4 per centum from the date the settled claim was outstanding until the day prior to the date of payment.
- 9.2 For the purposes of TP9.1,
  - 9.2.1 a claim is deemed to have been settled when an agreement in writing is signed by the Departmental Representative and the Contractor setting out the amount of the claim to be paid by Her Majesty and the items or work for which the said amount is to be paid.
  - 9.2.2 an "average Bank Rate" means the discount rate of interest set by the Bank of Canada in effect at the end of each calendar month averaged over the period the settled claim was outstanding.
  - 9.2.3 a settled claim is deemed to be outstanding from the day immediately following the date the said claim would have been due and payable under the contract had it not been disputed.
- 9.3 For the purposes of TP9 a claim means a disputed amount subject to negotiation between Her Majesty and the Contractor under the contract.

<b>a</b>	ъ.	** 1'					
Section	Page	Heading					
GC1	1	Interpretation					
GC2	2	Successors and Assigns					
GC3	2	Assignment of Contract					
GC4	2	Subcontracting by Contractor					
GC5	2	Amendments					
GC6	3	No Implied Obligations					
GC7	3	Time of Essence					
GC8	3	Indemnification by Contractor					
GC9	3	Indemnification by Her Majesty					
GC10	3	Members of House of Commons Not to Benefit					
GC11	4	Notices					
GC12	4	Material, Plant and Real Property Supplied by Her Majesty					
GC13	5	Material, Plant and Real Property Become Property of Her Majesty					
GC14	5	Permits and Taxes Payable					
GC15	6	Performance of Work under Direction of Departmental Representative					
GC16	6	Cooperation with Other Contractors					
GC17	7	Examination of Work					
GC18	7	Clearing of Site					
GC19	7	Contractor's Superintendent					
GC20	8	National Security					
GC21	8	Unsuitable Workers					
GC22	8	Increased or Decreased Costs					
GC23	9	Canadian Labour and Material					
GC24	9	Protection of Work and Documents					
GC25	10	Public Ceremonies and Signs					
GC26	10	Precautions against Damage, Infringement of Rights, Fire, and Other Hazards					
GC27	11	Insurance					
GC28	11	Insurance Proceeds					
GC29	12	Contract Security					
GC30	12	Changes in the Work					
GC31	13	Interpretation of Contract by Departmental Representative					
GC32	14	Warranty and Rectification of Defects in Work					
GC33	14	Non-Compliance by Contractor					
GC34	14	Protesting Departmental Representative's Decisions					
GC35	15	Changes in Soil Conditions and Neglect or Delay by Her Majesty					
GC36	16	Extension of Time					
GC37	16	Assessments and Damages for Late Completion					
GC38	17	Taking the Work Out of the Contractor's Hands					
GC39	18	Effect of Taking the Work Out of the Contractor's Hands					
GC40	18	Suspension of Work by Minister					
GC41 GC42	19 19	Termination of Contract					
GC42 GC43		Claims Against and Obligations of the Contractor or Subcontractor					
	21	Security Deposit – Forfeiture or Return					
GC44 GC45	22 23	Departmental Representative's Certificates					
GC45 GC46	23 24	Return of Security Deposit Clarification of Terms in GC47 to GC50					
GC40 GC47	24	Additions or Amendments to Unit Price Table					
GC47 GC48	24	Determination of Cost – Unit Price Table					
GC48 GC49	24 25	Determination of Cost – Only Price Table  Determination of Cost – Negotiation					
GC49 GC50	25 25	•					
GC50 GC51	25 26	Determination of Cost – Failing Negotiation  Percentage to be kept by Contractor					
GC51 GC52		Records to be kept by Contractor Conflict of Interest					
	27						
GC53	27	Contractor Status					

## GC1 Interpretation

#### 1.1 In the contract

- 1.1.1 where reference is made to a part of the contract by means of numbers preceded by letters, the reference shall be construed to be a reference to the particular part of the contract that is identified by that combination of letters and numbers and to any other part of the contract referred to therein;
- 1.1.2 "contract" means the contract document referred to in the Articles of Agreement;
- 1.1.3 "contract security" means any security given by the Contractor to Her Majesty in accordance with the contract;
- 1.1.4 "Departmental Representative" means the officer or employee or Her Majesty who is designated pursuant to the Articles of Agreement and includes a person specially authorized by him to perform, on his behalf, any of his functions under the contract and is so designated in writing to the Contractor;
- 1.1.5 "material" includes all commodities, articles and things required to be furnished by or for the Contractor under the contract for incorporation into the work;
- 1.1.6 "Minister" includes a person acting for, or if the office is vacant, in place of the Minister and his successors in the office, and his or their lawful deputy and any of his or their representatives appointed for the purposes of the contract;
- 1.1.7 "person" includes, unless the context otherwise requires, a partnership, proprietorship, firm, joint venture, consortium and a corporation;
- 1.1.8 "plant" includes all animals, tools, implements, machinery, vehicles, buildings, structures, equipment and commodities, articles and things other than material, that are necessary for the due performance of the contract;
- 1.1.9 "subcontractor' means a person to whom the Contractor has, subject to GC4, subcontracted the whole or any part of the work;
- 1.1.10 "superintendant" means the employee of the Contractor who is designated by the Contractor to act pursuant to GC19;
- 1.1.11 "work includes, subject only to any express stipulation in the contract to the contrary, everything that is necessary to be done, furnished or delivered by the Contractor to perform the contract.
- 1.2 The headings in the contract documents, other than in the Plans and Specifications, form no part of the contract but are inserted for convenience of reference only.
- 1.3 In interpreting the contract, in the event of discrepancies or conflicts between anything in the Plans and Specifications and the General Conditions, the General Conditions govern.

بنائد	Government of	Gouvernement	С	
	Canada	du Canada	General Conditions	Page 2 de 27

- 1.4 In interpreting the Plans and Specifications, in the event of discrepancies or conflicts between
  - 1.4.1 the Plans and Specifications, the Specifications govern;
  - 1.4.2 the Plans, the Plans drawn with the largest scale govern; and
  - 1.4.3 figured dimensions and scaled dimensions, the figured dimensions govern.

## GC2 Successors and Assigns

2.1 The contract shall inure to the benefit of and be binding upon the parties hereto and their lawful heirs, executors, administrators, successors and assigns.


## GC3 Assignment of Contract

3.1 The contract may not be assigned by the Contractor, either in whole or in part, without the written consent of the Minister.

# GC4 Subcontracting by Contractor

- 4.1 Subject to this General Condition, the Contractor may subcontract any part of the work.
- 4.2 The Contractor shall notify the Departmental Representative in writing of his intention to subcontract.
- 4.3 A notification referred to in GC4.2 shall identify the part of the work, and the subcontractor with whom it is intended to subcontract.
- 4.4 The Departmental Representative may object to the intended subcontracting by notifying the Contractor in writing within six days of receipt by the Departmental Representative of a notification referred to in GC4.2.
- 4.5 If the Departmental Representative objects to a subcontracting pursuant to GC4.4, the Contractor shall not enter into the intended subcontract.
- 4.6 The contractor shall not, without the written consent of the Departmental Representative, change a subcontractor who has been engaged by him in accordance with this General Condition.
- 4.7 Every subcontract entered into by the Contractor shall adopt all of the terms and conditions of ths contract that are of general application.
- 4.8 Neither a subcontracting nor the Departmental Representative's consent to a subcontracting by the Contractor shall be construed to relieve the Contractor from any obligation under the contract or to impose any liability upon Her Majesty.

#### GC5 Amendments



## GC6 No Implied Obligations

- 6.1 No implied terms or obligations of any kind by or on behalf of Her Majesty shall arise from anything in the contract and the express covenants and agreements therein contained and made by Her Majesty are the only covenants and agreements upon which any rights against Her Majesty are to be founded.
- 6.2 The contract supersedes all communications, negotiations and agreements, either written or oral, relating to the work that were made prior to the date of the contract.

#### GC7 Time of Essence

7.1 Time is of the essence of the contract.

### GC8 Indemnification by Contractor

- 8.1 The Contractor shall indemnify and save Her Majesty harmless from and against all claims, demand, losses, costs, damages, actions, suits, or proceedings by whomever made, brought or prosecuted and in any manner based upon, arising out of, related to, occasioned by or attributable to the activities of the Contractor, his servants, agents, subcontractors and sub-subcontractors in performing the work including an infringement or an alleged infringement of a patent of invention or any other kind of intellectual property.
- 8.2 For the purpose of GC8.1, "activities" includes any act improperly carried out, any omission to carry out an act and any delay in carrying out an act.

## GC9 Indemnification by Her Majesty

- 9.1 Her Majesty shall, subject to the Crown Liability Act, the Patent Act, and any other law that affects Her Majesty's rights, powers, privileges or obligations, indemnify and save the Contractor harmless from and against all claims, demands, losses, costs, damage, actions, suits or proceedings arising out of his activities under the contract that are directly attributable to
  - 9.1.1 lack of or a defect in Her Majesty's title to the work site whether real or alleged; or
  - 9.1.2 an infringement or an alleged infringement by the Contractor of any patent of invention or any other kind of intellectual property occurring while the Contractor was performing any act for the purposes of the contract employing a model, plan or design or any other thing related to the work that was supplied by Her Majesty to the Contractor.

## GC10 Members of House of Commons Not to Benefit

10.1 As required by the Parliament of Canada Act, it is an express condition of the contract that no member of the House of Commons shall be admitted to any share of part of the contract or to any benefit arising therefrom.

### **GC11 Notices**

- Any notice, consent, order, decision, direction or other communication, other than a notice referred to in GC11.4, that may be given to the Contractor pursuant to the contract may be given in any manner.
- Any notice, consent, order, decision, direction or other communication required to be given in writing, to any party pursuant to the contract shall, subject to GC11.4, be deemed to have been effectively given
  - 11.2.1 to the Contractor, if delivered personally to the Contractor or the Contractor's superintendent, or forwarded by mail, telex or facsimile to the Contractor at the address set out in A4.1, or
  - 11.2.2 to Her Majesty, if delivered personally to the Departmental Representative, or forwarded by mail, telex or facsimile to the Departmental Representative at the address set out in A1.2.1.
- 11.3 Any such notice, consent, order, decision, direction or other communication given in accordance with GC11.2 shall be deemed to have been received by either party
  - 11.3.1 if delivered personally, on the day that it was delivered,
  - 11.3.2 if forwarded by mail, on the earlier of the day it was received and the sixth day after it was mailed, and
  - 11.3.3 if forwarded by telex or facsimile, 24 hours after it was transmitted.
- A notice given under GC38.1.1, GC40 and GC41, if delivered personally, shall be delivered to the Contractor if the Contractor is doing business as sole proprietor or, if the Contractor is a partnership or corporation, to an officer thereof.

# GC12 Material, Plant and Real Property Supplied by Her Majesty

- 12.1 Subject to GC12.2, the Contractor is liable to Her Majesty for any loss of or damage to material, plant or real property that is supplied or placed in the care, custody and control of the Contractor by Her Majesty for use in connection with the contract, whether or not that loss or damage is attributable to causes beyond the Contractor's control.
- 12.2 The Contractor is not liable to Her Majesty for any loss or damage to material, plant or real property referred to in GC12.1 if that loss or damage results from and is directly attributable to reasonable wear and tear.
- 12.3 The Contractor shall not use any material, plant or real property referred to in GC12.1 except for

the purpose of performing this contract.

- When the Contractor fails to make good any loss or damage for which he is liable under GC12.1 within a reasonable time after being required to do so by the Departmental Representative, the Departmental Representative may cause the loss or damage to be made good at the Contractor's expense, and the Contractor shall thereupon be liable to Her Majesty for the cost thereof and shall, on demand, pay to Her Majesty an amount equal to that cost.
- 12.5 The Contractor shall keep such records of all material, plant and real property referred to in GC12.1 as the Departmental Representative from time to time requires and shall satisfy the Departmental Representative, when requested, that such material, plant and real property are at the place and in the condition which they ought to be.

## GC13 Material, Plant and Real Property Become Property of Her Majesty

- 13.1 Subject to GC14.7 all material and plant and the interest of the Contractor in all real property, licenses, powers and privileges purchased, used or consumed by the Contractor for the contract shall, after the time of their purchase, use or consumption be the property of Her Majesty for the purposes of the work and they shall continue to be the property of Her Majesty.
  - 13.1.1 in the case of material, until the Departmental Representative indicates that he is satisfied that it will not be required for the work, and
  - 13.1.2 in the case of plant, real property, licenses, powers and privileges, until the Departmental Representative indicates that he is satisfied that the interest vested in Her Majesty therein is no longer required for the purposes of the work.
- 13.2 Material or plant that is the property of Her Majesty by virtue of GC13.1 shall not be taken away from the work site or used or disposed of except for the purposes of the work without the written consent of the Departmental Representative.
- 13.3 Her Majesty is not liable for loss of or damage from any cause to the material or plant referred to in GC13.1 and the Contractor is liable for such loss or damage notwithstanding that the material or plant is the property of Her Majesty.

#### GC14 Permits and Taxes Payable

- 14.1 The Contractor shall, within 30 days after the date of the contract, tender to a municipal authority an amount equal to all fees and charges that would be lawfully payable to that municipal authority in respect of building permits as if the work were being performed for a person other than Her Majesty.
- 14.2 Within 10 days of making a tender pursuant to GC14.1, the Contractor shall notify the Departmental Representative of his action and of the amount tendered and whether or not the municipal authority has accepted that amount.
- 14.3 If the municipal authority does not accept the amount tendered pursuant to GC14.1 the Contractor shall pay that amount to Her Majesty within 6 days after the time stipulated in GC14.2.



- 14.4 For the purposes of GC14.1 to GC14.3 "municipal authority" means any authority that would have jurisdiction respecting permission to perform the work if the owner were not Her Majesty.
- 14.5 Notwithstanding the residency of the Contractor, the Contractor shall pay any applicable tax arising from or related to the performance of the work under the contract.
- 14.6 In accordance with the Statutory Declaration referred to in TP4.9, a Contractor who has neither residence nor place of business in the province in which work under the contract is being performed shall provide Her Majesty with proof of registration with the provincial sales tax authorities in the said province.
- 14.7 For the purpose of the payment of any applicable tax or the furnishing of security for the payment of any applicable tax arising from or related to the performance of the work under the contract, the Contractor shall, notwithstanding the fact that all material, plant and interest of the Contractor in all real property, licenses, powers and privileges, have become the property of Her Majesty after the time of purchase, be liable, as a user or consumer, for the payment or for the furnishing of security for the payment of any applicable tax payable, at the time of the use or consumption of that material, plant or interest of the Contractor in accordance with the relevant legislation.

## GC15 Performance of Work under Direction of Departmental Representative

- 15.1 The Contractor shall
  - 15.1.1 permit the Departmental Representative to have access to the work and its site at all times during the performance of the contract;
  - 15.1.2 furnish the Departmental Representative with such information respecting the performance of the contract as he may require; and
  - 15.1.3 give the Departmental Representative every possible assistance to enable the Departmental Representative to carry out his duty to see that the work is performed in accordance with the contract and to carry out any other duties and exercise any powers specially imposed or conferred on the Departmental Representative under the contract.

## **CG16** Cooperation with Other Contractors

- Where, in the opinion of the Departmental Representative, it is necessary that other contractors or workers with or without plant and material, be sent onto the work or its site, the Contractor shall, to the satisfaction of the Departmental Representative, allow them access and cooperate with them in the carrying out of their duties and obligation.
- 16.2 If
  - 16.2.1 the sending onto the work or its site of other contractors or workers pursuant to GC16.1 could not have been reasonably foreseen or anticipated by the Contractor when entering into the contract, and

- 16.2.2 the Contractor incurs, in the opinion of the Departmental Representative, extra expense in complying with GC16.1, and
- 16.2.3 The Contractor has given the Departmental Representative written notice of his claim for the extra expense referred to in GC16.2.2 within 30 days of the date that the other contractors or workers were sent onto the work or its site,

Her Majesty shall pay the Contractor the cost, calculated in accordance with GC48 to GC50, of the extra labour, plant and material that was necessarily incurred.

#### GC17 Examination of Work

- 17.1 If, at any time after the commencement of the work but prior to the expiry of the warranty or guarantee period, the Departmental Representative has reason to believe that the work or any part thereof has not been performed in accordance with the contract, the Departmental Representative may have that work examined by an expert of his choice.
- 17.2 If, as a result of an examination of the work referred to in GC17.1, it is established that the work was not performed in accordance with the contract, then, in addition to and without limiting or otherwise affecting any of Her Majesty's rights and remedies under the contract either at law or in equity, the Contractor shall pay Her Majesty, on demand, all reasonable costs and expenses that were incurred by Her Majesty in having that examination performed.

### GC18 Clearing of Site

- 18.1 The Contractor shall maintain the work and its site in a tidy condition and free from the accumulation of waste material and debris, in accordance with any directions of the Departmental Representative.
- 18.2 Before the issue of an interim certificate referred to in GC44.2, the Contractor shall remove all the plant and material not required for the performance of the remaining work, and all waste material and other debris, and shall cause the work and its site to be clean and suitable for occupancy by Her Majesty's servants, unless otherwise stipulated in the contract.
- 18.3 Before the issue of a final certificate referred to in GC44.1, the Contractor, shall remove from the work and its site all of the surplus plant and material and any waste material and other debris.
- 18.4 The Contractor's obligations described in GC18.1 to GC18.3 do not extend to waste material and other debris caused by Her Majesty's servants or contractors and workers referred to in GC16.1.

### GC19 Contractor's Superintendent

- 19.1 The Contractor shall, forthwith upon the award of the contract, designate a superintendent.
- 19.2 The Contractor shall forthwith notify the Departmental Representative of the name, address and telephone number of a superintendent designate pursuant to GC19.1.

344	Government of	Gouvernement	С	,,,,,
	Canada	du Canada	General Conditions	Page 8 de 27

- 19.3 A superintendent designated pursuant to GC19.1 shall be in full charge of the operations of the Contractor in the performance of the work and is authorized to accept any notice, consent, order, direction, decision or other communication on behalf of the Contractor that may be given to the superintendent under the contract.
- 19.4 The Contractor shall, until the work has been completed, keep a competent superintendent at the work site during working hours.
- 19.5 The Contractor shall, upon the request of the Departmental Representative, remove any superintendent who, in the opinion of the Departmental Representative, is incompetent or has been conducting himself improperly and shall forthwith designate another superintendent who is acceptable to the Departmental Representative.
- 19.6 Subject to GC19.5, the Contractor shall not substitute a superintendent without the written consent of the Departmental Representative.
- 19.7 A breach by the Contractor of GC19.6 entitles the Departmental Representative to refuse to issue any certificate referred to in GC44 until the superintendent has returned to the work site or another superintendent who is acceptable to the Departmental Representative has been substituted.

## GC20 National Security

- 20.1 If the Minister is of the opinion that the work is of a class or kind that involves the national security, he may order the Contractor
  - 20.1.1 to provide him with any information concerning persons employed or to be employed by him for purposes of the contract; and
  - 20.1.2 to remove any person from the work and its site if, in the opinion of the Minister, that person may be a risk to the national security.
- 20.2 The Contractor shall, in all contracts with persons who are to be employed in the performance of the contract, make provision for his performance of any obligation that may be imposed upon him under GC19 to GC21.
- 20.3 The Contractor shall comply with an order of the Minister under GC20.1

### GC21 Unsuitable Workers

21.1 The Contractor shall, upon the request of the Departmental Representative, remove any person employed by him for purposes of the contract who, in the opinion of the Departmental Representative, is incompetent or has conducted himself improperly, and the Contractor shall not permit a person who has been removed to return to the work site.

## GC22 Increased or Decreased Costs

- 22.1 The amount set out in the Articles of Agreement shall not be increased or decreased by reason of any increase or decrease in the cost of the work that is brought about by an increase or decrease in the cost of labour, plant or material or any wage adjustment arising pursuant to the Labour Conditions.
- 22.2 Notwithstanding GC22.1 and GC35, an amount set out in the Articles of Agreement shall be adjusted in the manner provided in GC22.3, if any change in a tax imposed under the Excise Act, the Excise Tax Act, the Old Age Security Act, the Customs Act, the Customs Tariff or any provincial sales tax legislation imposing a retail sales tax on the purchase of tangible personal property incorporated into Real Property
  - 22.2.1 occurs after the date of the submission by the Contractor of his tender for the contract,
  - 22.2.2 applies to material, and
  - 22.2.3 affects the cost to the Contractor of that material.
- 22.3 If a change referred to in GC22.2 occurs, the appropriate amount set out in the Articles of Agreement shall be increased or decreased by an amount equal to the amount that is established by an examination of the relevant records of the Contractor referred to in GC51 to be the increase or decrease in the cost incurred that is directly attributable to that change.
- For the purpose of GC22.2, where a tax is changed after the date of submission of the tender but public notice of the change has been given by the Minister of Finance before that date, the change shall be deemed to have occurred before the date of submission of the tender.

#### GC23 Canadian Labour and Material

- 23.1 The Contractor shall use Canadian labour and material in the performance of the work to the full extent to which they are procurable, consistent with proper economy and expeditious carrying out of the work.
- 23.2 Subject to GC23.1, the Contractor shall, in the performance of the work, employ labour from the locality where the work is being performed to the extent to which it is available, and shall use the offices of the Canada Employment Centres for the recruitment of workers wherever practicable.
- 23.3 Subject to GC23.1 and GC23.2, the Contractor shall, in the performance of the work, employ a reasonable proportion of persons who have been on active service with the armed forces of Canada and have been honourably discharged therefrom.

## GC24 Protection of Work and Documents

24.1 The Contractor shall guard or otherwise protect the work and its site, and protect the contract, specifications, plans, drawings, information, material, plant and real property, whether or not they are supplied by Her Majesty to the Contractor, against loss or damage from any cause, and he shall not use, issue, disclose or dispose of them without the written consent of the Minister, except as may be essential for the performance of the work.

1	Government of	Gouvernement	С	
T	Canada	du Canada	General Conditions	Page 10 de 27

- 24.2 If any document or information given or disclosed to the Contractor is assigned a security rating by the person who gave or disclosed it, the Contractor shall take all measures directed by the Departmental Representative to be taken to ensure the maintenance of the degree of security that is ascribed to that rating.
- 24.3 The Contractor shall provide all facilities necessary for the purpose of maintaining security, and shall assist any person authorized by the Minister to inspect or to take security measures in respect of the work and its site.
- 24.4 The Departmental Representative may direct the Contractor to do such things and to perform such additional work as the Departmental Representative considers reasonable and necessary to ensure compliance with or to remedy a breach of GC24.1 to GC24.3.

## GC25 Public Ceremonies and Signs

- 25.1 The Contractor shall not permit any public ceremony in connection with the work without the prior consent of the Minister.
- 25.2 The Contractor shall not erect or permit the erection of any sign or advertising on the work or its site without the prior consent of the Departmental Representative.

# GC26 Precautions against Damage, Infringement of Rights, Fire, and Other Hazards

- 26.1 The Contractor shall, at his own expense, do whatever is necessary to ensure that
  - 26.1.1 no person, property, right, easement or privilege is injured, damaged or infringed by reasons of the Contractor's activities in performing the contract;
  - 26.1.2 pedestrian and other traffic on any public or private road or waterway is not unduly impeded, interrupted or endangered by the performance or existence of the work or plant;
  - 26.1.3 fire hazards in or about the work or its site are eliminated and, subject to any direction that may be given by the Departmental Representative, any fire is promptly extinguished;
  - 26.1.4 the health and safety of all persons employed in the performance of the work is not endangered by the method or means of its performance;
  - 26.1.5 adequate medical services are available to all persons employed on the work or its site at all times during the performance of the work;
  - 26.1.6 adequate sanitation measures are taken in respect of the work and its site; and
  - 26.1.7 all stakes, buoys and marks placed on the work or its site by or under the authority of the Departmental Representative are protected and are not removed, defaced, altered or destroyed.
- 26.2 The Departmental Representative may direct the Contractor to do such things and to perform such additional work as the Departmental Representative considers reasonable and necessary to ensure

compliance with or to remedy a breach of GC26.1.

26.3 The Contractor shall, at his own expense, comply with a direction of the Departmental Representative made under GC26.2.

#### GC27 Insurance

- 27.1 The Contractor shall, at his own expense, obtain and maintain insurance contracts in respect of the work and shall provide evidence thereof to the Departmental Representative in accordance with the requirements of the Insurance Conditions "E".
- 27.2 The insurance contracts referred to in GC27.1 shall
  - 27.2.1 be in a form, of the nature, in the amounts, for the periods and containing the terms and conditions specified in Insurance Conditions "E", and
  - 27.2.2 provide for the payment of claims under such insurance contracts in accordance with GC28.

#### **GC28** Insurance Proceeds

- 28.1 In the case of a claim payable under a Builders Risk/Installation (All Risks) insurance contract maintained by the Contractor pursuant to GC27, the proceeds of the claim shall be paid directly to Her Majesty, and
  - 28.1.1 the monies so paid shall be held by Her Majesty for the purposes of the contract, or
  - 28.1.2 if Her Majesty elects, shall be retained by Her Majesty, in which event they vest in Her Majesty absolutely.
- 28.2 In the case of a claim payable under a General Liability insurance contract maintained by the Contractor pursuant to GC27, the proceeds of the claim shall be paid by the insurer directly to the claimant.
- 28.3 If an election is made pursuant to GC28.1, the Minister may cause an audit to be made of the accounts of the Contractor and of Her Majesty in respect of the part of the work that was lost, damaged or destroyed for the purpose of establishing the difference, if any, between
  - 28.3.1 the aggregate of the amount of the loss or damage suffered or sustained by Her Majesty, including any cost incurred in respect of the clearing and cleaning of the work and its site and any other amount that is payable by the Contractor to Her Majesty under the contract, minus any monies retained pursuant to GC28.12, and
  - 28.3.2 the aggregate of the amounts payable by Her Majesty to the Contractor pursuant to the contract up to the date of the loss or damage.
- A difference that is established pursuant to GC28.3 shall be paid forthwith by the party who is determined by the audit to be the debtor to the party who is determined by the audit to be the

Gouvernement du Canada C General Conditions

Page 12 de 27

creditor.

- When payment of a deficiency has been made pursuant to GC28.4, all rights and obligations of Her Majesty and the Contractor under the contract shall, with respect only to the part of the work that was the subject of the audit referred to in GC28.3, be deemed to have been expended and discharged.
- 28.6 If an election is not made pursuant to GC28.1.2 the Contractor shall, subject to GC28.7, clear and clean the work and its site and restore and replace the part of the work that was lost, damaged or destroyed at his own expense as if that part of the work had not yet been performed.
- 28.7 When the Contractor clears and cleans the work and its site and restores and replaces the work referred to in GC 28.6, Her Majesty shall pay him out of the monies referred to in GC28.1 so far as they will thereunto extend.
- 28.8 Subject to GC28.7, payment by Her Majesty pursuant to GC28.7 shall be made in accordance with the contract but the amount of each payment shall be 100% of the amount claimed notwithstanding TP4.4.1 and TP4.4.2.

## GC29 Contract Security

- 29.1 The Contractor shall obtain and deliver contract security to the Departmental Representative in accordance with the provisions of the Contract Security Conditions.
- 29.2 If the whole or a part of the contract security referred to in GC29.1 is in the form of a security deposit, it shall be held and disposed of in accordance with GC43 and GC45.
- 29.3 If a part of the contract security referred to in GC29.1 is in the form of a labour and material payment bond, the Contractor shall post a copy of that bond on the work site.

## GC30 Changes in the Work

- 30.1 Subject o GC5, the Departmental Representative may, at any time before he issues his Final Certificate of Completion,
  - 30.1.1 order work or material in addition to that provided for in the Plans and Specifications; and
  - 30.1.2 delete or change the dimensions, character, quantity, quality, description, location or position of the whole or any part of the work or material proved for in the Plans and Specifications or in any order made pursuant to GC30.1.1,
  - if that additional work or material, deletion, or change is, in his opinion, consistent with the general intent of the original contract.
- The Contractor shall perform the work in accordance with such orders, deletions and changes that are made by the Departmental Representative pursuant to GC30.1 from time to time as if they had appeared in and been part of the Plans and Specifications.

مكانو	Government of	Gouvernement	C	
7	Canada	du Canada	General Conditions	Page 13 de 27

- 30.3 The Departmental Representative shall determine whether or not anything done or omitted by the Contractor pursuant to an order, deletion or change referred to in GC30.1 increased or decreased the cost of the work to the Contractor.
- 30.4 If the Departmental Representative determines pursuant to GC30.3 that the cost of the work to the Contractor has been increased, Her Majesty shall pay the Contractor the increased cost that the Contractor necessarily incurred for the additional work calculated in accordance with GC49 or GC50.
- 30.5 If the Departmental Representative determines pursuant to GC303.3 that the cost of the work to the Contractor has been decreased, Her Majesty shall reduce the amount payable to the Contractor under the contract by an amount equal to the decrease in the cost caused by the deletion or change referred to in GC30.1.2 and calculated in accordance with GC49.
- 30.6 GC30.3 to GC30.5 are applicable only to a contract or a portion of a contract for which a Fixed Price Arrangement is stipulated in the contract.
- An order, deletion or change referred to in GC30.1 shall be in writing, signed by the Departmental Representative and given to the Contractor in accordance with GC11.

## GC31 Interpretation of Contract by Departmental Representative

- 31.1 If, ar any time before the Departmental Representative has issued a Final Certificate of Completion referred to in GC44.1, any question arises between the parties about whether anything has been done as required by the contract or about what the Contractor is required by the contract to do, and, in particular but without limiting the generality of the foregoing, about
  - 31.1.1 the meaning of anything in the Plans and Specification,
  - 31.1.2 the meaning to be given to the Plans and Specifications in case of any error therein, omission therefrom, or obscurity or discrepancy in their working or intention,
  - 31.1.3 whether or not the quality or quantity of any material or workmanship supplied or proposed to be supplied by the Contractor meets the requirements of the contract,
  - 31.1.4 whether or not the labour, plant or material provided by the Contractor for performing the work and carrying out the contract are adequate to ensure that the work will be performed in accordance with the contract and that the contract will be carried out in accordance with its terms.
  - 31.1.5 what quantity of any kind of work has been completed by the Contractor, or
  - 31.1.6 the timing and scheduling of the various phases of the performance of the work,

the question shall be decided by the Departmental Representative whose decision shall be final and conclusive in respect of the work.

31.2 The Contractor shall perform the work in accordance with any decisions of the Departmental

Representative that are made under GC31.1 and in accordance with any consequential directions given by the Departmental Representative.

## GC32 Warranty and Rectification of Defects in Work


- Without restricting any warranty or guarantee implied or imposed by law or contained in the contract documents, the Contractor shall, at his own expense,
  - 32.1.1 rectify and make good any defect or fault that appears in the work or comes to the attention of the Minister with respect to those parts of the work accepted in connection with the Interim Certificate of Completion referred to GC44.2 within 12 months from the date of the Interim Certificate of Completion;
  - 32.1.2 rectify and make good any defect or fault that appears in or comes to the attention of the Minister in connection with those parts of the work described in the Interim Certificate of Completion referred to in GC44.2 within 12 months from the date of the Final Certificate of Completion referred to in GC44.1.
- 32.2 The Departmental Representative may direct the Contractor to rectify and make good any defect or fault referred to in GC32.1 or covered by any other expressed or implied warranty or guarantee.
- A direction referred to in GC32.2 shall be in writing, may include a stipulation in respect of the time within which a defect or fault is required to be rectified and made good by the Contractor, and shall be given to the Contractor in accordance with GC11.
- 32.4 The Contractor shall rectify and make good any defect or fault described in a direction given pursuant to GC32.2 within the time stipulated therein.

## GC33 Non-Compliance by Contractor

- 33.1 If the Contractor fails to comply with any decision or direction given by the Departmental Representative pursuant to GC18, GC24, GC26, GC31 or GC32, the Departmental Representative may employ such methods as he deems advisable to do that which the Contractor failed to do.
- The Contractor shall, on demand, pay Her Majesty an amount that is equal to the aggregate of all cost, expenses and damage incurred or sustained by Her Majesty by reason of the Contractor's failure to comply with any decision or direction referred to in GC33.1, including the cost of any methods employed by the Departmental Representative pursuant to GC33.1.

## GC34 Protesting Departmental Representative's Decisions

- 34.1 The Contractor may, within ten days after the communication to him of any decision or direction referred to in GC30.3 or GC33.1, protest that decision or direction.
- 34.2 A protest referred to in GC34.1 shall be in writing, contain full reasons for the protest, be signed



Gouvernement du Canada C General Conditions

Page 15 de 27

by the Contractor and be given to Her Majesty by delivery to the Departmental Representative.

- 34.3 If the Contractor gives a protest pursuant to GC34.2, any compliance by the Contractor with the decision or direction that was protested shall not be construed as an admission by the Contractor of the correctness of that decision or direction, or prevent the Contractor from taking whatever action he considers appropriate in the circumstances.
- 34.4 The giving of a protest by the Contractor pursuant to GC34.2 shall not relieve him from complying with the decision or direction that is the subject of the protest.
- 34.5 Subject to GC34.6, the Contractor shall take any action referred to in GC34.3 within three months after the date that a Final Certificate of Completion is issued under GC44.1 and not afterwards.
- 34.6 The Contractor shall take any action referred to in GC34.3 resulting from a direction under GC32 within three months after the expiry of a warranty or guarantee period and not afterwards.
- 34.7 Subject to GC34.8, if Her Majesty determines that the Contractor's protest is justified, Her Majesty shall pay the Contractor the cost of the additional labour, plant and material necessarily incurred by the Contractor in carrying out the protested decision or direction.
- 34.8 Costs referred to in GC34.7 shall be calculated in accordance with GC48 to GC50.

## GC35 Changes in Soil Conditions and Neglect or Delay by Her Majesty

- 35.1 Subject to GC35.2 no payment, other than a payment that is expressly stipulated in the contract, shall be made by Her Majesty to the Contractor for any extra expense or any loss or damage incurred or sustained by the Contractor.
- 35.2 If the Contractor incurs or sustains any extra expense or any loss or damage that is directly attributable to
  - 35.2.1 a substantial difference between the information relating to soil conditions at the work site that is contained in the Plans and Specifications or other documents supplied to the Contractor for his use in preparing his tender or a reasonable assumption of fact based thereon made by the Contractor, and the actual soil conditions encountered by the Contractor at the work site during the performance of the contract, or
  - 35.2.2 any neglect or delay that occurs after the date of the contract on the part of Her Majesty in providing any information or in doing any act that the contract either expressly requires Her Majesty to do or that would ordinarily be done by an owner in accordance with the usage of the trade,

he shall, within ten days of the date the actual soil conditions described in GC35.2.1 were encountered or the neglect or delay described in GC35.2.2 occurred, give the Departmental Representative written notice of his intention to claim for that extra expense or that loss or damage.

When the Contractor has given a notice referred to in GC35.2, he shall give the Departmental Representative a written claim for extra expense or loss or damage within 30 days of the date that

a Final Certificate of Completion referred to in GC44.1 is issued and not afterwards.

- A written claim referred to in GC35.3 shall contain a sufficient description of the facts and circumstances of the occurrence that is the subject of the claim to enable the Departmental Representative to determine whether or not the claim is justified and the Contractor shall supply such further and other information for that purpose as the Departmental Representative requires from time to time.
- 35.5 If the Departmental Representative determines that a claim referred to in GC35.3 is justified, Her Majesty shall make an extra payment to the Contractor in an amount that is calculated in accordance with GC47 to GC50.
- 35.6 If, in the opinion of the Departmental Representative, an occurrence described in GC35.2.1 results in a savings of expenditure by the Contractor in performing the contract, the amount set out in the Articles of Agreement shall, subject to GC35.7, be reduced by an amount that is equal to the saving.
- 35.7 The amount of the saving referred to in GC35.6 shall be determined in accordance with GC47 to GC49.
- 35.8 If the Contractor fails to give a notice referred to in GC35.2 and a claim referred to in GC35.3 within the times stipulated, an extra payment shall not be made to him in respect of the occurrence.

### GC36 Extension of Time

- 36.1 Subject to GC36.2, the Departmental Representative may, on the application of the Contractor made before the day fixed by the Articles of Agreement for completion of the work or before any other date previously fixed under this General Condition, extend the time for its completion by fixing a new date if, in the opinion of the Departmental Representative, causes beyond the control of the Contractor have delayed its completion.
- 36.2 An application referred to in GC36.1 shall be accompanied by the written consent of the bonding company whose bond forms part of the contract security.

### GC37 Assessments and Damages for Late Completion

- 37.1 For the purposes of this General Condition
  - 37.1.1 the work shall be deemed to be completed on the date that an Interim Certificate of Completion referred to in GC44.2 is issued, and
  - 37.1.2 "period of delay" means the number of days commencing on the day fixed by the Articles of Agreement for completion of the work and ending on the day immediately preceding the day on which the work is completed but does not include any day within a period of extension granted pursuant to GC36.1, and any other day on which, in the opinion of the Departmental Representative, completion of the work was delayed for reasons beyond the control of the Contractor.

- 37.2 If the Contractor does not complete the work by the day fixed for its completion by the Articles of Agreement but completes it thereafter, the Contractor shall pay Her Majesty an amount equal to the aggregate of
  - 37.2.1 all salaries, wages and travelling expenses incurred by Her Majesty in respect of persons overseeing the performance of the work during the period of delay;
  - 37.2.2 the cost incurred by Her Majesty as a result of the inability to use the completed work for the period of delay; and
  - 37.2.3 all other expenses and damages incurred or sustained by Her Majesty during the period of delay as a result of the work not being completed by the day fixed for its completion.
- 37.3 The Minister may waive the right of Her Majesty to the whole or any part of the amount payable by the Contractor pursuant to GC37.2 I, in the opinion of the Minister, it is in the public interest to do so.

## GC38 Taking the Work Out of the Contractor's Hands

- 38.1 The Minister may, at his sole discretion, by giving a notice in writing to the Contractor in accordance with GC11, take all or any part of the work out of the Contractor's hands, and may employ such means as he sees fit to have the work completed if the Contractor
  - 38.1.1 Has not, within six days of the Minister or the Departmental Representative giving notice to the Contractor in writing in accordance with GC11, remedied any delay in the commencement or any default in the diligent performance of the work to the satisfaction of the Departmental Representative;
  - 38.1.2 has defaulted in the completion of any part of the work within the time fixed for its completion by the contract;
  - 38.1.3 has become insolvent;
  - 38.1.4 has committed an act of bankruptcy;
  - 38.1.5 has abandoned the work;
  - 38.1.6 has made an assignment of the contract without the consent required by GC3.1; or
  - 38.1.7 has otherwise failed to observe or perform any of the provisions of the contract.
- 38.2 If the whole or any part of the work is taken out of the Contractor's hands pursuant to GC38.1,
  - 38.2.1 the Contractor's right to any further payment that is due or accruing due under the contract is, subject only to GC38.4, extinguished, and
  - 38.2.2 the Contractor is liable to pay Her Majesty, upon demand, an amount that is equal to the amount of all loss and damage incurred or sustained by Her Majesty in respect of the

Gouvernement du Canada C General Conditions

Page 18 de 27

## Contractor's failure to complete the work.


- 38.3 If the whole or any part of the work that is taken out of the Contractor's hands pursuant to GC38.1 is completed by Her Majesty, the Departmental Representative shall determine the amount, if any, of the holdback or a progress claim that had accrued and was due prior to the date on which the work was taken out of the Contractor's hands and that is not required for the purposes of having the work performed or of compensating Her Majesty for any other loss or damage incurred or sustained by reason of the Contractor's default.
- Her Majesty may pay the Contractor the amount determined not to be required pursuant to GC38.3.

## GC39 Effect of Taking the Work Out of the Contractor's Hands

- 39.1 The taking of the work or any part thereof out of the Contractor's hands pursuant to GC38 does not operate so as to relieve or discharge him from any obligation under the contract or imposed upon him by law except the obligation to complete the performance of that part of the work that was taken out of his hands.
- 39.2 If the work or any part thereof is taken out of the Contractor's hands pursuant to GC38, all plant and material and the interest of the Contractor is all real property, licenses, powers and privileges acquired, used or provided by the Contractor under the contract shall continue to be the property of Her Majesty without compensation to the Contractor.
- When the Departmental Representative certifies that any plant, material, or any interest of the Contractor referred to in GC39.2 is no longer required for the purposes of the work, or that it is not in the interest of Her Majesty to retain that plant, material or interest, it shall revert to the Contractor.

## G40 Suspension of Work by Minister

- 40.1 The Minister may, when in his opinion it is in the public interest to do so, require the Contractor to suspend performance of the work either for a specified or an unspecified period by giving a notice of suspension in wiring to the Contractor in accordance with GC11.
- When a notice referred to in GC40.1 is received by the Contractor in accordance with GC11, he shall suspend all operations in respect of the work except those that, in the opinion of the Departmental Representative, are necessary for the care and preservation of the work, plant and material.
- 40.3 The Contractor shall not, during a period of suspension, remove any part of the work, plant or material from its site without the consent of the Departmental Representative.
- 40.4 If a period of suspension is 30 days or less, the Contractor shall, upon the expiration of that period, resume the performance of the work and he is entitled to be paid the extra cost, calculated in accordance with GC48 to GC50, of any labour, plant and material necessarily incurred by him as a result of the suspension.



nment of Gouvernement du Canada

C General Conditions

Page 19 de 27

- 40.5 If, upon the expiration of a period of suspension of more than 30 days, the Minister and the Contractor agree that the performance of the work will be continued by the Contractor, the Contractor shall resume performance of the work subject to any terms and conditions agreed upon by the Minister and the Contractor.
- 40.6 If, upon the expiration of a period of suspension of more than 30 days, the Minister and the Contractor do not agree that performance of the work will be continued by the Contractor or upon the terms and conditions under which the Contractor will continue the work, the notice of suspension shall be deemed to be a notice of termination pursuant to GC41.

#### **GC41** Termination of Contract

- 41.1 The Minister may terminate the contract at any time by giving a notice of termination in writing to the Contractor in accordance with GC11.
- When a notice referred to in GC41.1 is received by the Contractor in accordance with GC11, he shall, subject to any conditions stipulated in the notice, forthwith cease all operations in performance of the contract.
- 41.3 If the contract is terminated pursuant to GC41.1, Her Majesty shall pay the Contractor, subject to GC41.4, an amount equal to
  - 41.3.1 the cost to the contractor of all labour, plant and material supplied by him under the contract up to the date of termination in respect of a contract or part thereof for which a Unit Price Arrangement is stipulated in the contract, or
  - 41.3.2 the lesser of
    - 41.3.2.1 an amount, calculated in accordance with the Terms and Payment, that would have been payable to the Contractor had he completed the work, and
    - 41.3.2.2 an amount that is determined to be due to the Contractor pursuant to GC49 in respect of a contract or part thereof for which a Fixed Price Arrangement is stipulated in the contract

less the aggregate of all amounts that were paid to the Contractor by Her Majesty and all amounts that are due to Her Majesty from the Contractor pursuant to the contract.

41.4 If Her Majesty and the Contractor are unable to agree about an amount referred to in GC41.3 that amount shall be determined by the method referred to in GC50.

## GC42 Claims Against and Obligations of the Contractor or Subcontractor

42.1 Her Majesty may, in order to discharge lawful obligations of and satisfy claims against the Contractor or a subcontractor arising out of the performance of the contract, pay any amount that is due and payable to the Contractor pursuant to the contract directly to the obligees of and the claimants against the Contractor or the subcontractor but such amount if any, as is paid by Her Majesty, shall not exceed that amount which the Contractor would have been obliged to pay to

such claimant had the provisions of the Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, been applicable to the work. Any such claimant need not comply with the provisions of such legislation setting out the steps by way of notice, registration or otherwise as might have been necessary to preserve or perfect any claim for lien or privilege which claimant might have had;

- 42.2 Her Majesty will not make any payment as described in GC42.1 unless and until that claimant shall have delivered to Her Majesty:
  - 42.2.1 a binding and enforceable Judgment or Order of a court of competent jurisdiction setting forth such amount as would have been payable by the Contractor to the claimant pursuant to the provisions of the applicable Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, had such legislation been applicable to the work; or
  - 42.2.2 a final and enforceable award of an arbitrator setting forth such amount as would have been payable by the Contractor to the claimant pursuant to the provisions of the applicable Provincial or Territorial lien legislation, or, in the Province of Quebec, the law relating to privileges, had such legislation been applicable to the work; or
  - 42.2.3 the consent of the Contractor authorizing a payment.

For the purposes of determining the entitlement of a claimant pursuant to GC42.2.1 and GC42.2.2, the notice required by GC42.8 shall be deemed to replace the registration or provision of notice after the performance of work as required by any applicable legislation and no claim shall be deemed to have expired, become void or unenforceable by reason of the claimant not commencing any action within the time prescribed by any applicable legislation.

- 42.3 The Contractor shall, by the execution of his contract, be deemed to have consented to submit to binding arbitration at the request of any claimant those questions that need be answered to establish the entitlement of the claimant to payment pursuant to the provisions of GC42.1 and such arbitration shall have as parties to it any subcontractor to whom the claimant supplied material, performed work or rented equipment should such subcontractor wish to be adjoined and the Crown shall not be a party to such arbitration and, subject to any agreement between the Contractor and the claimant to the contrary, the arbitration shall be conducted in accordance with the Provincial or Territorial legislation governing arbitration applicable in the Province or Territory in which the work is located.
- A payment made pursuant to GC42.1 is, to the extent of the payment, a discharge of Her Majesty's liability to the Contractor under the contract and may be deducted from any amount payable to the Contractor under the contract.
- To the extent that the circumstances of the work being performed for Her Majesty permit, the Contractor shall comply with all laws in force in the Province or Territory where the work is being performed relating to payment period, mandatory holdbacks, and creation and enforcement of mechanics' liens, builders' liens or similar legislation or in the Province of Quebec, the law relating to privileges.
- 42.6 The Contractor shall discharge all his lawful obligations and shall satisfy all lawful claims against him arising out of the performance of the work at least as often as the contract requires Her

Majesty to pay the Contractor.

- 42.7 The Contractor shall, whenever requested to do so by the Departmental Representative, make a statutory declaration deposing to the existence and condition of any obligations and claims referred to in GC42.6.
- 42.8 GC42.1 shall only apply to claims and obligations
  - 42.8.1 the notification of which has been received by the Departmental Representative in writing before payment is made to the Contractor pursuant to TP4.10 and within 120 days of the date on which the claimant
    - 42.8.1.1 should have been paid in full under the claimant's contract with the Contractor or subcontractor where the claim is for money that was lawfully required to be held back from the claimant; or
    - 42.8.1.2 performed the last of the services, work or labour, or furnished the last of the material pursuant to the claimant's contract with the Contractor or subcontractor where the claim is not for money referred to in GC42.8.1.1, and
  - 42.8.2 the proceedings to determine the right to payment of which, pursuant to GC42.2. shall have commenced within one year from the date that the notice referred to in GC42.8.1 was received by the Departmental Representative, and

the notification required by GC42.8.1 shall set forth the amount claimed to be owing and the person who by contract is primarily liable.

- 42.9 Her Majesty may, upon receipt of a notice of claim under GC42.8.1, withhold from any amount that is due and payable to the Contractor pursuant to the contract the full amount of the claim or any portion thereof.
- 42.10 The Departmental Representative shall notify the Contractor in writing of receipt of any claim referred to in GC42.8.1 and of the intention of Her Majesty to withhold funds pursuant to GC42.9 and the Contractor may, at any time thereafter and until payment is made to the claimant, be entitled to post, with Her Majesty, security in a form acceptable to Her Majesty in an amount equal to the value of the claim, the notice of which is received by the Departmental Representative and upon receipt of such security Her Majesty shall release to the Contractor any funds which would be otherwise payable to the Contractor, that were withheld pursuant to the provisions of GC42.9 in respect of the claim of any claimant for whom the security stands.

# GC43 Security Deposit - Forfeiture or Return

- 43.1 If
  - 43.1.1 the work is taken out of the Contractor's hands pursuant to GC38.
  - 43.1.2 the contract is terminated pursuant to GC41, or
  - 43.1.3 the Contractor is in breach of or in default under the contract,

Her Majesty may convert the security deposit, if any, to Her own use.

- 43.2 If Her Majesty converts the contract security pursuant to GC43.1, the amount realized shall be deemed to be an amount due from Her Majesty to the Contractor under the contract.
- Any balance of an amount referred to in GC43.2 that remains after payment of all losses, damage and claims of Her Majesty and others shall be paid by Her Majesty to the Contractor if, in the opinion of the Departmental Representative, it is not required for the purposes of the contract.

# GC44 Departmental Representative's Certificates


- 44.1 On the date that
  - 44.1.1 the work has been completed, and
  - 44.1.2 the Contractor has complied with the contract and all orders and directions made pursuant thereto,

both to the satisfaction of the Departmental Representative, the Departmental Representative shall issue a Final Certificate of Completion to the Contractor.

- 44.2 If the Departmental Representative is satisfied that the work is substantially complete he shall, at any time before he issues a certificate referred to in GC44.1, issue an Interim Certificate of Completion to the Contractor, and
  - 44.2.1 for the purposes of GC44.2 the work will be considered to be substantially complete,
    - 44.2.1.1 when the work under the contract or a substantial part thereof is, in the opinion of the Departmental Representative, ready for use by Her Majesty or is being used for the purpose intended; and
    - 44.2.1.2 when the work remaining to be done under the contract is, in the opinion of the Departmental Representative, capable of completion or correction at accost of not more that
      - 44.2.1.2.1 -3% of the first \$500,000, and
      - 44.2.1.2.2 -2% of the next \$500,000, and
      - 44.2.1.2.3 -1% of the balance

of the value of the contract at the time this cost is calculated.

44.3 For the sole purpose of GC44.2.1.2, where the work or a substantial part thereof is ready for use or is being used for the purposes intended and the remainder of the work or a part thereof cannot be completed by the time specified in A2.1, or as amended pursuant to GC36, for reasons beyond the control of the Contractor or where the Departmental Representative and the Contractor agree not to complete a part of the work within the specified time, the cost of that part of the work



C General Conditions

Page 23 de 27

which was either beyond the control of the Contractor to complete or the Departmental Representative and the Contractor have agreed not to complete by the time specified shall be deducted from the value of the contract referred to GC44.2.1.2 and the said cost shall not form part of the cost of the work remaining to be done in determining substantial completion.

- 44.4 An Interim Certificate of Completion referred to in GC44.2 shall describe the parts of the work not completed to the satisfaction of the Departmental Representative and all things that must be done by the Contractor
  - 44.4.1 before a Final Certificate of Completion referred to in GC44.1 will be issued, and
  - 44.4.2 before the 12-month period referred to in GC32.1.2 shall commence for the said parts and all the said things.
- The Departmental Representative may, in addition to the parts of the work described in an Interim Certificate of Completion referred to in GC44.2, require the Contractor to rectify any other parts of the work not completed to his satisfaction and to do any other things that are necessary for the satisfactory completion of the work.
- 44.6 If the contract or a part thereof is subject to a Unit Price Arrangement, the Departmental Representative shall measure and record the quantities of labour, plant and material, performed, used and supplied by the Contractor in performing the work and shall, at the request of the Contractor, inform him of those measurements.
- 44.7 The Contractor shall assist and co-operate with the Departmental Representative in the performance of his duties referred to in GC44.6 and shall be entitled to inspect any record made by the Departmental Representative pursuant to GC44.6.
- 44.8 After the Departmental Representative has issued a Final Certificate of Completion referred to in GC44.1, he shall, if GC44.6 applies, issue a Final Certificate of Measurement.
- 44.9 A Final Certificate of Measurement referred to in GC44.8 shall
  - 44.9.1 contain the aggregate of all measurements of quantities referred to in GC44.6, and
  - 44.9.2 be binding upon and conclusive between Her Majesty and the Contractor as to the quantities referred to therein.

# GC45 Return of Security Deposit

- 45.1 After an Interim Certificate of Completion referred to in GC44.2 has been issued, Her Majesty shall, if the Contractor is not in breach of or in default under the contract, return to the Contractor all or any part of the security deposit that, in the opinion of the Departmental Representative, is not required for the purposes of the contract.
- 45.2 After a Final Certificate of Completion referred to in GC44.1 has been issued, Her Majesty shall return to the Contractor the remainder of any security deposit unless the contract stipulates otherwise.

4	Government o
	Canada

C General Conditions

Page 24 de 27

45.3 If the security deposit was paid into the Consolidated Revenue Fund of Canada, Her Majesty shall pay interest thereon to the Contractor at a rate established from time to time pursuant to section 21(2) of the Financial Administration Act.

# GC46 Clarification of Terms in GC47 to GC50

- 46.1 For the purposes of GC47 to GC50,
  - 46.1.1 "Unit Price Table" means the table set out in the Articles of Agreement, and
  - 46.1.2 "plant" does not include tools customarily provided by a tradesman in practicing his trade.

# GC47 Additions or Amendments to Unit Price Table

- Where a Unit Price Arrangement applies to the contract or a part thereof the Departmental Representative and the Contractor may, by an agreement in writing,
  - 47.1.1 add classes of labour or material, and units of measurement, prices per unit and estimated quantities to the Unit Price Table if any labour, plant or material that is to be included in the Final Certificate of Measurement referred to in GC44.8 is not included in any class of labour, plant or material set out in the Unit Price Table; or
  - 47.1.2 subject to GC47.2 and GC47.3, amend a price set out in the Unit Price Table for any class of labour, plant or material included therein if the Final Certificate of Measurement referred to in GC44.8 shows or is expected to show that the total quantity of that class of labour, plant or material actually performed, used or supplied by the Contractor in performing the work is
    - 47.1.2.1 less than 85% of that estimated total quantity, or
    - 47.1.2.2 in excess of 115% of that estimated total quantity.
- In no event shall the total cost of an item set out in the Unit Price Table that has been amended pursuant to GC47.1.2.1 exceed the amount that would have been payable to the Contractor had the estimated total quantity actually been performed, used or supplied.
- 47.3 An amendment that is made necessary by GC47.1.2.2 shall apply only to the quantities that are in excess of 115%.
- 47.4 If the Departmental Representative and the Contractor do not agree as contemplated in GC47.1, the Departmental Representative shall determine the class and the unit of measurement of the labour, plant or material and, subject to GC47.2 and GC47.3, the price per unit therefore shall be determined in accordance with GC50.

# GC48 Determination of Cost – Unit Price Table



C General Conditions

Page 25 de 27

Whenever, for the purposes of the contract, it is necessary to determine the cost of labour, plant or material, it shall be determined by multiplying the quantity of that labour, plant or material expressed in the unit set out in column 3 of the Unit Price Table by the price of that unit set out in column 5 of the Unit Price Table.

# GC49 Determination of Cost - Negotiation

- 49.1 If the method described in GC48 cannot be used because the labour, plant or material is of a kind or class that is not set out in the Unit Price Table, the cost of that labour, plant or material for the purposes of the contract shall be the amount agreed upon from time to time by the Contractor and the Departmental Representative.
- 49.2 For the purposes of GC49.1, the Contractor shall submit to the Departmental Representative any necessary cost information requested by the Departmental Representative in respect of the labour, plant and material referred to in GC49.1

# GC50 Determination of Cost - Failing Negotiation

- 50.1 If the methods described in GC47, GC48 or GC49 fail for any reason to achieve a determination of the cost of labour, plant and material for the purposes referred to therein, that cost shall be equal to the aggregate of
  - 50.1.1 all reasonable and proper amounts actually expended or legally payable by the Contractor in respect of the labour, plant and material that falls within one of the classes of expenditure described in GC50.2 that are directly attributable to the performance of the contract,
  - 50.1.2 an allowance for profit and all other expenditures or costs, including overhead, general administration cost, financing and interest charges, and every other cost, charge and expenses, but not including those referred to in GC50.1.1 or GC50.1.3 or a class referred to in GC50.2, in an amount that is equal to 10% of the sum of the expenses referred to in GC50.1.1, and
  - 50.1.3 interest on the cost determined under GC50.1.1 and GC50.1.2, which interest shall be calculated in accordance with TP9.

provide that the total cost of an item set out n the Unit Price Table that is subject to the provisions of GC47.1.2.1 does not exceed the amount that would have been payable to the Contractor had the estimated total quantity of the said item actually be performed, used or supplied.

- For purposes of GC50.1.1 the classes of expenditure that may be taken into account in determining the cost of labour, plant and material are,
  - 50.2.1 payments to subcontractors;
  - 50.2.2 wages, salaries and travelling expenses of employees of the Contractor while they are actually and properly engaged on the work, other than wages, salaries, bonuses, living

C General Conditions

Page 26 de 27


and travelling expenses of personnel of the Contractor generally employed at the head office or at a general office of the Contractor unless they are engaged at the work site with the approval of the Departmental Representative,

- 50.2.3 assessments payable under any statutory authority relating to workmen's compensation, unemployment insurance, pension plan or holidays with pay;
- 50.2.4 rent that is paid for plant or an amount equivalent of the said rent if the plant is owned by the Contractor that is necessary for and used in the performance of the work, if the rent of the equivalent amount is reasonable and use of that plant has been approved by the Departmental Representative;
- 50.2.5 payments for maintaining and operating plant necessary for and used in the performance of the work, and payments for effecting such repairs thereto as, in the opinion of the Departmental Representative, are necessary to the proper performance of the contract other than payments for any repairs to the plant arising out of defects existing before its allocation to the work;
- 50.2.6 payments for material that is necessary for and incorporated in the work, or that is necessary for and consumed in the performance of the contract;
- 50.2.7 payments for preparation, delivery, handling, erection, installation, inspection protection and removal of the plant and material necessary for and used in the performance of the contract; and
- 50.2.8 any other payments made by the Contractor with the approval of the Departmental Representative that are necessary for the performance of the contract.

# GC51 Records to be kept by Contractor

# 51.1 The Contractor shall

- 51.1.1 maintain full records of his estimated and actual cost of the work together with all tender calls, quotations, contracts, correspondence, invoices, receipts and vouchers relating thereto.
- 51.1.2 make all records and material referred to in GC5.1.1 available to audit and inspection by the Minister and the Deputy Receiver General for Canada or by persons acting on behalf of either of both of them, when requested;
- 51.1.3 allow any of the person referred to in GC51.1.2 to make copies of and to take extracts from any of the records and material referred to in GC51.1.1; and
- 51.1.4 furnish any person referred to in GC51.1.2 with any information he may require from time to time in connection with such records and material.
- The records maintained by the Contractor pursuant to GC51.1.1 shall be kept intact by the Contractor until the expiration of two years after the date that a Final Certificate of Completion referred to in GC44.1 was issued or until the expiration of such other period of time as the



C General Conditions

Page 27 de 27

Minister may direct.

51.3 The Contractor shall cause all subcontractors and all other persons directly or indirectly controlled by or affiliated with the Contractor and all persons directly or indirectly having control of the Contractor to comply with GC51.1 and GC51.2 as if they were the Contractor.

# GC52 Conflict of Interest

52.1 It is a term of this contract that no former public office holder who is not in compliance with the Conflict of Interest and Post-Employment Code for Public Office Holders shall derive a direct benefit from this contract.

# GC53 Contractor Status

- 53.1 The Contractor shall be engaged under the contract as an independent contractor.
- The Contractor and any employee of the said Contractor is not engaged by the contract as an employee, servant or agent of Her Majesty.
- For the purposes of GC53.1 and GC53.2 the Contractor shall be solely responsible for any and all payments and deductions required to be made by law including those required for Canada or Quebec Pension Plans, Unemployment Insurance, Worker's Compensation or Income Tax.

# **GENERAL CONDITONS**

IC	1	Proof of Insurance	
$\mathbf{r}$		i i ovi vi insulance	

- IC 2 Risk Management
- IC 3 Payment of Deductible
- IC 4 Insurance Coverage

# GENERAL INSUANCE COVERAGES

- GCI 1 Insured
- GIC 2 Period of Insurance
- GIC 3 Proof of Insurance
- GIC 4 Notification

# COMMERCIAL GENERAL LIABILITY

- **CGL 1 Scope of Policy**
- CGL 2 Coverages/Provisions
- **CGL 3 Additional Exposures**
- **CGL 4 Insurance Proceeds**
- CGL 5 Deductible

# BUILDER'S RISK - INSTALLATION FLOATER - ALL RISKS

- BR 1 Scope of Policy
- **BR 2** Property Insured
- **BR3** Insurance Proceeds
- BR 4 Amount of Insurance
- BR 5 Deductible
- BR 6 Subrogation
- **BR 7** Exclusion Qualifications

# INSURER'S CERTIFICATE OF INSURANCE

# ■↑■ Ir

# IC 1 Proof of Insurance (02/12/03)

**General Conditions** 

Within thirty (30) days after acceptance of the Contractor's tender, the Contractor shall, unless otherwise directed in writing by the Contracting Officer, deposit with the Contracting Officer an Insurer's Certificate of Insurance in the form displayed in this document and, if requested by the Contracting Officer, the originals or certified true copies of all contracts of insurance maintained by the Contractor pursuant to the Insurance Coverage Requirements shown hereunder.

# IC 2 Risk Management (01/10/94)

The provisions of the Insurance Coverage Requirements contained hereunder are not intended to cover all of the Contractor's obligations under GC8 of the General Conditions "C" of the contract. Any additional risk management measures or additional insurance coverages the Contractor may deem necessary to fulfill its obligations under GC8 shall be at its own discretion and expense.

# IC 3 Payment of Deductible (01/10/94)

The payment of monies up to the deductible amount made in satisfaction of a claim shall be borne by the . Contactor.

# IC 4 Insurance Coverage (02/12/03)

The Contractor has represented that it has in place and effect the appropriate and usual liability insurance coverage as required by these Insurance Conditions and the Contractor has warranted that it shall obtain, in a timely manner and prior to commencement of the Work, the appropriate and usual property insurance coverage as required by these Insurance Conditions and, further, that it shall maintain all required insurance policies in place and effect as required by these Insurance Conditions.

# Insurance Conditions - Construction

# INSURANCE COVERAGE REQUIREMENTS

# PART I GENERAL INSUANCE COVERAGES (GIC)

GCI 1 Insured (02/12/03)

Each insurance policy shall insure the Contractor, and shall include, as an Additional Named Insured, Her Majesty the Queen in right of Canada, represented by the National Research Council Canada.

# GIC 2 Period of Insurance (02/12/03)

Unless otherwise directed in writing by the Contracting Officer or otherwise stipulated elsewhere in these Insurance Conditions, the policies required hereunder shall be in force and be maintained from the date of the contract award until the day of issue of the Departmental Representative's Final Certificate of Completion.

# GIC 3 Proof of Insurance (01/10/94)

Within twenty five (25) days after acceptance of the Contractor's tender, the Insurer shall, unless otherwise directed by the Contractor, deposit with the Contractor an Insurer's Certificate of Insurance in the form displayed in the document and, if requested, the originals or certified true copies of all contracts of insurance maintained by the Contractor pursuant to the requirements of these Insurance Coverages.

# GIC 4 Notification (01/10/94)

Each Insurance policy shall contain a provision that (30) days prior written notice shall be given by the Insurer to Her Majesty in the event of any material change in or cancellation of coverage. Any such notice received by the Contractor shall be transmitted forthwith to Her Majesty.

# PART II COMMERCIAL GENERAL LIABILITY

# CGL 1 Scope of Policy (01/10/94)

The policy shall be written on a form similar to that known and referred to in the insurance industry as IBC 2100 - Commercial General Liability policy (Occurrence form) and shall provide for limit of liability of not less than \$2,000,000 inclusive for Bodily Injury and Property Damage for any one occurrence or series of occurrences arising out of one cause. Legal or defence cost incurred in respect of a claim or claims shall not operate to decrease the limit of liability.

# CGL 2 Coverages/Provisions (01/10/94)

The policy shall include but not necessarily be limited to the following coverages/provisions.

- 2.1 Liability arising out of or resulting from the ownership, existence, maintenance or use of premises by the Contractor and operations necessary or incidental to the performance of this contract.
- 2.2 "Broad Form" Property Damage including the loss of use of property.
- 2.3 Removal or weakening of support of any building or land whether such support be natural or otherwise.
- 2.4 Elevator liability (including escalators, hoists and similar devices).
- 2.5 Contractor's Protective Liability
- 2.6 Contractual and Assumed Liabilities un this contact.
- 2.7 Completed Operations Liability The insurance, including all aspects of this Part II of these Insurance Conditions shall continue for a period of at least one (1) year beyond the date of the Departmental Representative's Final Certificate of Completion for the Completed Operations.
- 2.8 Cross Liability The Clause shall be written as follows:

Cross Liability – The insurance as is afforded by this policy shall apply in respect to any claim or action brought against any one Insured by any other Insured. The coverage shall apply in the same manner and to the same extent as though a separate policy had been issued to each Insured. The inclusion herein of more than one Insured shall not increase the limit of the Insurer's liability.

2.9 Severability of Interests – The Clause shall be written as follows:

Severability of Interests – This policy, subject to the limits of liability stated herein, shall apply separately to each Insured in the same manner and to the same extent as if a separate policy had been issued to each. The inclusion herein of more than one insured shall not increase the limit of the Insurer's liability.

# CGL 3 Additional Exposures (02/12/03)

The policy shall either include or be endorsed to include the following exposures of hazards if the Work is subject thereto:

- 3.1 Blasting
- 3.2 Pile driving and calsson work
- 3.3 Underpinning
- 3.4 Risks associated with the activities of the Contractor on an active airport

- 3.5 Radioactive contamination resulting from the use of commercial isotopes
- 3.6 Damage to the portion of an existing building beyond that directly associated with an addition, renovation or installation contract.
- 3.7 Marine risks associated with the contraction of piers, wharves and docks.

# **CGL 4 Insurance Proceeds** (01/10/94)

Insurance Proceeds from this policy are usually payable directly to a Claimant/Third Party.

# CGL 5 Deductible (02/12/03)

This policy shall be issued with a deductible amount of not more than \$10,000 per occurrence applying to Property Damage claims only.

# PART III **BUILDER'S RISK - INSTALLATION FLOATER - ALL RISKS**

# BR 1 Scope of Policy (01/10/94)

The policy shall be written on an "All Risks" basis granting coverages similar to those provided by the forms known and referred to in the insurance industry as "Builder's Risk Comprehensive Form" or "Installation Floater - All Risks".

# BR 2 Property Insured (01/10/94)

The property insured shall include:

- 2.1 The Work and all property, equipment and materials intended to become part of the finished Work at the site of the project while awaiting, during and after installation, erection or construction including testing.
- 2.2 Expenses incurred in the removal from the construction site of debris of the property insured, including demolition of damaged property, de-icing and dewatering, occasioned by loss, destruction or damage to such property and in respect of which insurance is provided by this policy.

# **Insurance Proceeds** (01/10/94)

- 3.1 Insurance proceeds from this policy are payable in accordance with GC28 of the General Conditions "C" of the contract.
- 3.2 This policy shall provide that the proceeds thereof are payable to Her Majesty or as the Minister may direct.

# BR 4 Amount of Insurance (01/10/94)

The amount of insurance shall not be less than the sum of the contract value plus the declared value (if any) set forth in the contract documents of all material and equipment supplied by Her Majesty at the site of the project to be incorporated into and form part of the finished Work.

# BR 5 Deductible (02/12/03)

The Policy shall be issued with a deductible amount of not more than \$10,000.

# BR 6 Subrogation (01/10/94)

The following Clause shall be included in the policy:

"All rights of subrogation or transfer of rights are hereby waived against any corporation, firm, individual or other interest, with respect to which, insurance is provided by this policy".

# BR 7 Exclusion Qualifications (01/10/94)

The policy may be subject to the standard exclusions but the following qualifications shall apply:

- 7.1 Faulty materials, workmanship or design may be excluded only to the extent of the cost of making good thereof and shall not apply to loss or damage resulting therefrom.
- 7.2 Loss or damage caused by contamination by radioactive material may be excluded except for loss or damage resulting from commercial isotopes used for industrial measurements, inspection, quality control radiographic or photographic use.
- 7.3 Use and occupancy of the project or any part of section thereof shall be permitted where such use and occupancy is for the purpose for which the project is intended upon completion.

# INSURER'S CERTIFICATE OF INSURANCE

(TO BE COMPLETED BY INSURER (NOT BOKER) AND DELIVERD TO NATIONAL RESEARCH COUNCIL CANADA WITH 30 DAYS FOLLOWING ACCEPTANCE OF TENDER)

CONTRACT					
DESCRIPTION	OF WORK	CONTRACT NUI	MBER	AWARD DATE	
LOCATION					
INSURER			•		
NAME		***************************************			
, , , , , , , , , , , , , , , , , , , ,					
ADDRESS					
			•		
BROKER					
NAME					
· · · · · · · · · · · · · · · · · · ·					
ADDRESS					
DIGITOR					
INSURED NAME OF CONT	ED A CTOD				
NAME OF CON.	IKACIOK				
ADDRESS				***************************************	
ADDITIONAL IN	NSURED				
HER MAJESTY THE	QUEEN IN RIGHT OF	CANADA AS REPRESE	NTED BY THE NATIO	NAL RESEARCH COU	JNCIL CANADA
THIS DOCUENT CE	RTIFIES THAT THE FO	LLOWING POLICES OF	INSURANCE ARE A	T PRESENT IN FORCE	COVERING ALL
		CTION WITH THE CON			
NATIONAL RESEAR	CH COUNCIL CANAD	A AND IN ACCORDAN POL		ANCE CONDITIONS	E
TYPE	NUMBER	INCEPTION DATE	EXPIRY DATE	LIMITS OF	DEDUCTIBLE
COMMERCIAL			***************************************	LIABILITY	
GENERAL					
LIABILITY					
BUILDERS RISK "AL RISKS"					
INSTALLATION					
FLOATER "ALL					
RISKS"	<u> </u>	*******			
		~~~~			
THE INSURER AGRE MATERIAL CHANGI	SES TO NOTIFY THE NEW TO SELLATE	ATIONAL RESEARCH ON OF ANY POLICY OI	COUNCIL CANADA I R COVERAGE SPECIF	N WRITING 30 DAYS TCALLY RELATED TO	PRIOR TO ANY THE CONTRACT
NAME OF INSURER' AUTHORIZED EMPL		SIGNATURE		DATE:	
TIOTHERE DIVINE	O LILL			TELEPHONE NUMB	ER:

# CS1 Obligation to provide Contract Security

- 1.1 The Contractor shall, at the Contractor's own expense, provide one or more of the forms of contract security prescribed in CS2.
- 1.2 The Contractor shall deliver to the Departmental Representative the contract security referred to in CS1.1 within 14 days after the date that the Contractor receives notice that the Contractor's tender or offer was accepted by Her Majesty.

# CS2 Prescribed Types and Amounts of Contract Security

- 2.1 The Contractor shall deliver to the Departmental Representative pursuant to CS1
  - 2.1.1 a performance bond and a labour and material payment bond each in an amount that is equal to not less than 50% of the contract amount referred to in the Articles of Agreement, or
  - 2.1.2 a labour and material payment bond in an amount that is equal to not less than 50% of the contract amount referred to in the Articles of Agreement, and a security deposit in an amount that is equal to
    - 2.1.2.1 not less than 10% of the contract amount referred to in the Articles of Agreement where that amount does not exceed \$250,000, or
    - 2.1.2.2 \$25,000 plus 5% of the part of the contract amount referred to in the Articles of Agreement that exceeds \$250,000, or
  - 2.1.3 a security deposit in an amount prescribed by CS2.12 plus an additional amount that is equal to 10% of the contract amount referred to in the Articles of Agreement.
- A performance bond and a labour and material payment bond referred to in CS2.1 shall be in a form and be issued by a bonding or surety company that is approved by Her Majesty.
- 2.3 The amount of a security deposit referred to in CS2.1.2 shall not exceed \$250,000 regardless of the contract amount referred to in the Articles of Agreement.
- 2.4 A security deposit referred to in CS2.1.2 and CS2.1.3 shall be in the form of
  - 2.4.1 a bill of exchange made payable to the Receiver General of Canada and certified by an approved financial institution or drawn by an approved financial institution on itself, or
  - 2.4.2 bonds of or unconditionally guaranteed as to principal and interest by the Government of Canada.
- 2.5 For the purposes of CS2.4
  - a bill of exchange is an unconditional order in writing signed by the Contractor and addressed to an approved financial institution, requiring the said institution to pay, on demand, at a fixed or determinable future time a sum certain of money to, or to the order

of, the Receiver General for Canada, and

- 2.5.2 If a bill of exchange is certified by a financial institution other than a chartered bank then it must be accompanied by a letter or stamped certification confirming that the financial institution is in a t least one of the categories referred to in CS2.5.3
- 2.5.3 an approved financial institution is
  - 2.5.3.1 any corporation or institution that is a member of the Canadian Payments Association,
  - 2.5.3.2 a corporation that accepts deposits that are insured by the Canada Deposit Insurance Corporation or the Régie de l'assurance-dépôts du Québec to the maximum permitted by law,
  - 2.5.3.3 a credit union as defined in paragraph 137(6)(b) of the *Income Tax Act*,
  - 2.5.3.4 a corporation that accepts deposits from the public, if repayment of the deposit is guaranteed by Her Majesty in right of a province, or
  - 2.5.3.5 The Canada Post Corporation.
- 2.5.4 the bonds referred to in CS2.4.2 shall be
  - 2.5.4.1 made payable to bearer, or
  - 2.5.4.2 accompanied by a duly executed instrument of transfer of the bonds to the Receiver General for Canada in the form prescribed by the Domestic Bonds of Canada Regulations, or
  - 2.5.4.3 registered, as to principal or as to principal and interest in the name of the Receiver General for Canada pursuant to the Domestic Bonds of Canada Regulations, and
  - 2.5.4.4 provided on the basis of their market value current at the date of the contract.



Contract Number / Numéro du contrat	
Security Classification / Classification de sécurité	

SECURITY REQUIREMENTS CHECK LIST (SRCL)

PART A - CONTRACT INFORMATION / PARTIE A	CATION DES EXIGENCES REL - INFORMATION CONTRACTUELL		ECURITE (LVERS)	
Originating Government Department or Organizati			or Directorate / Direction généra	le ou Direction
Ministère ou organisme gouvernemental d'origine			ŭ	
3. a) Subcontract Number / Numéro du contrat de so	us-traitance 3. b) Name and	Address of Subcor	ntractor / Nom et adresse du sou	us-traitant
4. Brief Description of Work / Brève description du tra	avail			
5. a) Will the supplier require access to Controlled G				No Yes
Le fournisseur aura-t-il accès à des marchandis		nuncialana af tha Ta	salariani Data Cantral	Non Oui
5. b) Will the supplier require access to unclassified Regulations?	fillitary technical data subject to the	provisions of the Te	ecnnicai data Control	No Yes
Le fournisseur aura-t-il accès à des données te	chniques militaires non classifiées q	ui sont assujetties a	aux dispositions du Règlement	
sur le contrôle des données techniques?  6. Indicate the type of access required / Indiquer le t	ype d'accès requis			
6. a) Will the supplier and its employees require acce	,	FIFD information or	assets?	No Yes
Le fournisseur ainsi que les employés auront-ils				Non Oui
(Specify the level of access using the chart in Q				
(Préciser le niveau d'accès en utilisant le tablea 6. b) Will the supplier and its employees (e.g. cleane		access to restricted	access areas? No access to	□ No □ Yes
PROTECTED and/or CLASSIFIED information	or assets is permitted.			Non Oui
Le fournisseur et ses employés (p. ex. nettoyeu à des renseignements ou à des biens PROTÉG			d'accès restreintes? L'accès	
6. c) Is this a commercial courier or delivery requiren	nent with <b>no</b> overnight storage?			No Yes
S'agit-il d'un contrat de messagerie ou de livrais	son commerciale <b>sans</b> entreposage	de nuit?		Non Oui
7. a) Indicate the type of information that the supplied	will be required to access / Indiquer	r le type d'information	on auquel le fournisseur devra a	voir accès
Canada	NATO / OTAN		Foreign / Étranger	
7. b) Release restrictions / Restrictions relatives à la	diffusion			
No release restrictions	All NATO countries		No release restrictions	
Aucune restriction relative  à la diffusion	Tous les pays de l'OTAN		Aucune restriction relative à la diffusion	
Not releasable À ne pas diffuser				
/ The pas diffuser				
Restricted to: / Limité à :	Restricted to: / Limité à :		Restricted to: / Limité à :	
Specify country(ies): / Préciser le(s) pays :	Specify country(ies): / Préciser le(	s) pays :	Specify country(ies): / Précise	r le(s) pays :
7. c) Level of information / Niveau d'information PROTECTED A	NATO UNCLASSIFIED		PROTECTED A	
PROTÉGÉ A	NATO UNCLASSIFIED		PROTÉGÉ A	
PROTECTED B	NATO RESTRICTED		PROTECTED B	一
PROTÉGÉ B	NATO DIFFUSION RESTREINTE	: []	PROTÉGÉ B	
PROTECTED C	NATO CONFIDENTIAL		PROTECTED C	
PROTÉGÉ C	NATO CONFIDENTIEL		PROTÉGÉ C	<u> </u>
CONFIDENTIAL	NATO SECRET		CONFIDENTIAL	
CONFIDENTIEL	NATO SECRET COSMIC TOP SECRET		CONFIDENTIEL	片
SECRET SECRET	COSMIC TOP SECRET		SECRET SECRET	
TOP SECRET	GOOWIIG TREG SECRET		TOP SECRET	計
TRÈS SECRET			TRÈS SECRET	
TOP SECRET (SIGINT)			TOP SECRET (SIGINT)	
TRÈS SECRET (SIGINT)			TRÈS SECRET (SIGINT)	

TBS/SCT 350-103(2004/12)

Security Classification / Classification de sécurité

Canadä



Contract Number / Numéro du contrat	
Security Classification / Classification de sécurité	

-							
PAR I 8. Wil	A (cont I the sup	inued) / PARTIE A (suite) plier require access to PROTECTE	D and/or CLASSIFIED COMSEC	information or assets?		□ No □	Yes
Le	fournisse	eur aura-t-il accès à des renseignen			IFIÉS?	Non L	Oui
		ate the level of sensitivity: native, indiquer le niveau de sensibi	ilité ·				
9. Wil	I the sup	plier require access to extremely se	ensitive INFOSEC information or a			No	Yes
Le	fournisse	eur aura-t-il accès à des renseignen	nents ou à des biens INFOSEC de	e nature extrêmement délicate?		Non	Oui
Sho	ort Title(s	s) of material / Titre(s) abrégé(s) du	matériel :				
		lumber / Numéro du document :					
		SONNEL (SUPPLIER) / PARTIE E el security screening level required					
		RELIABILITY STATUS COTE DE FIABILITÉ	CONFIDENTIAL CONFIDENTIEL	SECRET SECRET	TOP SECR TRÈS SEC		
		TOP SECRET- SIGINT	NATO CONFIDENTIAL	NATO SECRET	COSMIC TO	OP SECRET	
		TRÈS SECRET – SIGINT SITE ACCESS	NATO CONFIDENTIEL	L NATO SECRET	COSMIC II	RÉS SECRET	
		ACCÈS AUX EMPLACEMENTS					
		Special comments:  Commentaires spéciaux :					
		,					
		NOTE: If multiple levels of screening			and a constitution of the first		
10. b)	May uns	REMARQUE: Si plusieurs niveau creened personnel be used for por		luis, un guide de classification de l	a securite doit etre t	ourni.	Yes
,		onnel sans autorisation sécuritaire		du travail?		Non	Oui
		vill unscreened personnel be escort				No	Yes
	Dans ra	ffirmative, le personnel en question	sera-t-ii escorte?			Non	Oui
		EGUARDS (SUPPLIER) / PARTIE		N (FOURNISSEUR)			
INFO	ORMATI	ON/ASSETS / RENSEIGNEMI	ENTS / BIENS				
11. a)	Will the	supplier be required to receive and	store PROTECTED and/or CLAS	SIFIED information or assets on it	s site or	□ No □	Yes
<b>'</b>	premise	s?				└── Non └	Oui
	Le fourr	isseur sera-t-il tenu de recevoir et d FIÉS?	d'entreposer sur place des renseig	gnements ou des biens PROTEGE	:S et/ou		
11. b)		supplier be required to safeguard C isseur sera-t-il tenu de protéger de		OMSEC?		No Non	Yes Oui
			o remodiginamente da dos pieno o				
PRO	DUCTIO	ON .					
44 - 33	VAZIL 41: -	made ation (many factors and to	:	TED and/an OI ACCIETED		A1-	
11. C)		roduction (manufacture, and/or repair the supplier's site or premises?	ir and/or modification) of PROTECT	ED and/or CLASSIFIED material of	r equipment	No Non	Yes Oui
	Les insta	allations du fournisseur serviront-elles	s à la production (fabrication et/ou re	éparation et/ou modification) de ma	tériel PROTÉGÉ		
	et/ou CL	ASSIFIE?					
INFO	ORMATIC	ON TECHNOLOGY (IT) MEDIA /	SUPPORT RELATIF À LA TECHN	IOLOGIE DE L'INFORMATION (TI)	)		
11. d)		supplier be required to use its IT syste	ems to electronically process, produ	ice or store PROTECTED and/or C	LASSIFIED	No T	Yes
		ion or data? isseur sera-t-il tenu d'utiliser ses prop	ores systèmes informatiques nour tr	raiter, produire ou stocker électropiq	uement des	Non	Oui
		iements ou des données PROTÉGÉ		and, produire od stocker electroniq	aomont aoo		
	1 A P.H 2		P 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1			N <sub>0</sub>	□v <sub>aa</sub>
11. e)		e be an electronic link between the su ra-t-on d'un lien électronique entre le			ce	No Non L	Yes — Oui
		ementale?	,				-

TBS/SCT 350-103(2004/12)

Security Classification / Classification de sécurité

**Canadä** 

*	Government	Gouvernement
	of Canada	du Canada

Contract Number / Numéro du contrat	
Security Classification / Classification de sécurité	

PART C - (continued)	/ PARTIE C - (	(suite)	١
----------------------	----------------	---------	---

For users completing the form manually use the summary chart below to indicate the category(ies) and level(s) of safeguarding required at the supplier's site(s) or premises.

Les utilisateurs qui remplissent le formulaire **manuellement** doivent utiliser le tableau récapitulatif ci-dessous pour indiquer, pour chaque catégorie, les niveaux de sauvegarde requis aux installations du fournisseur.

For users completing the form online (via the Internet), the summary chart is automatically populated by your responses to previous questions. Dans le cas des utilisateurs qui remplissent le formulaire en ligne (par Internet), les réponses aux questions précédentes sont automatiquement saisies dans le tableau récapitulatif.

#### SUMMARY CHART / TABLEAU RÉCAPITULATIF

Category Catégorie	PROTECTED PROTÉGÉ				ASSIFIED ASSIFIÉ			NATO				COMSEC					
	Α	В	С	CONFIDENTIAL	SECRET	TOP SECRET	NATO RESTRICTED	NATO CONFIDENTIAL	NATO SECRET	COSMIC TOP	TOP PROTÉGÉ			CONFIDENTIAL	CONFIDENTIAL SECRET	TOP SECRET	
				CONFIDENTIEL		TRÈS SECRET	NATO DIFFUSION RESTREINTE	NATO CONFIDENTIEL		SECRET COSMIC TRÈS SECRET	Α	В	С	CONFIDENTIEL		TRES SECRET	
nformation / Assets Renseignements / Biens																	
Production																	
T Media / Support TI																	
T Link / Lien électronique																	
2. a) Is the descrip								and/or CLAS ROTÉGÉE et		SIFIÉF?				ſ	No Non	☐ Y	

Information / Assets Renseignements / Biens						TREGITE								
Production														
IT Media / Support TI														
IT Link / Lien électronique														
12. a) Is the descrip									OJEJÉFO				No	Yes
La description du travail visé par la présente LVERS est-elle de nature PROTÉGÉE et/ou CLASSIFIÉE?  If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification".  Dans l'affirmative, classifier le présent formulaire en indiquant le niveau de sécurité dans la case intitulée										∟ Oui				
« Classification							eau de secui	ite dalis	ia case iii	tituic	•			
12. b) Will the documentation attached to this SRCL be PROTECTED and/or CLASSIFIED?  La documentation associée à la présente LVERS sera-t-elle PROTÉGÉE et/ou CLASSIFIÉE?										No Non	Yes Oui			
If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification" and indicate with attachments (e.g. SECRET with Attachments).  Dans l'affirmative, classifier le présent formulaire en indiquant le niveau de sécurité dans la case intitulée « Classification de sécurité » au haut et au bas du formulaire et indiquer qu'il y a des pièces jointes (p. ex. SECRET avec des pièces jointes).														



Contract Number / Numéro du contrat	
Security Classification / Classification de sécurité	

DART D. AUTHORIZATION ( DART	TIE D. ALITODIOATIO	NI.			
PART D - AUTHORIZATION / PART					
13. Organization Project Authority / C	. ,	· ·		•	
Name (print) - Nom (en lettres moulé	ees)	Title - Titre		Signature	
Telephone No N° de téléphone	Facsimile No N° de	télécopieur	E-mail address - Adresse coul	rriel	Date
14. Organization Security Authority /	Responsable de la séc	urité de l'orgar	nisme		
Name (print) - Nom (en lettres moulé	ees)	Title - Titre		Signature	
Telephone No N° de téléphone	Facsimile No N° de	télécopieur	E-mail address - Adresse coul	rriel	Date
15. Are there additional instructions ( Des instructions supplémentaires				t-elles jointes	No Yes Non Oui
16. Procurement Officer / Agent d'ap	provisionnement				
Name (print) - Nom (en lettres moulé	ees)	Title - Titre		Signature	
Telephone No N° de téléphone	Facsimile No N° de	télécopieur	E-mail address - Adresse con	urriel	Date
17. Contracting Security Authority / A	Autorité contractante en	n matière de sé	curité		
Name (print) - Nom (en lettres moulé	ees)	Title - Titre		Signature	
Telephone No N° de téléphone	Facsimile No N° de	e télécopieur	E-mail address - Adresse con	urriel	Date

Security Classification / Classification de sécurité

#### Instructions for completion of a Security Requirements Check List (SRCL)

The instruction sheet should remain attached until Block #17 has been completed.

#### **GENERAL - PROCESSING THIS FORM**

The project authority shall arrange to complete this form.

The organization security officer shall review and approve the security requirements identified in the form, in cooperation with the project authority.

The contracting security authority is the organization responsible for ensuring that the suppliers are compliant with the security requirements identified in the SRCL.

All requisitions and subsequent tender / contractual documents including subcontracts that contain PROTECTED and/or CLASSIFIED requirements must be accompanied by a completed SRCL.

It is important to identify the level of PROTECTED information or assets as Level "A," "B" or "C," when applicable; however, certain types of information may only be identified as "PROTECTED". No information pertaining to a PROTECTED and/or CLASSIFIED government contract may be released by suppliers, without prior written approval of the individual identified in Block 17 of this form.

The classification assigned to a particular stage in the contractual process does not mean that everything applicable to that stage is to be given the same classification. Every item shall be PROTECTED and/or CLASSIFIED according to its own content. If a supplier is in doubt as to the actual level to be assigned, they should consult with the individual identified in Block 17 of this form.

### PART A - CONTRACT INFORMATION

#### Contract Number (top of the form)

This number must be the same as that found on the requisition and should be the one used when issuing an RFP or contract. This is a unique number (i.e. no two requirements will have the same number). A new SRCL must be used for each new requirement or requisition (e.g. new contract number, new SRCL, new signatures).

## 1. Originating Government Department or Organization

Enter the department or client organization name or the prime contractor name for which the work is being performed.

### 2. Directorate / Branch

This block is used to further identify the area within the department or organization for which the work will be conducted.

#### 3. a) Subcontract Number

If applicable, this number corresponds to the number generated by the Prime Contractor to manage the work with its subcontractor.

# b) Name and Address of Subcontractor

Indicate the full name and address of the Subcontractor if applicable.

#### 4. Brief Description of Work

Provide a brief explanation of the nature of the requirement or work to be performed.

# 5. a) Will the supplier require access to Controlled Goods?

The Defence Production Act (DPA) defines "Controlled Goods" as certain goods listed in the Export Control List, a regulation made pursuant to the Export and Import Permits Act (EIPA). Suppliers who examine, possess, or transfer Controlled Goods within Canada must register in the Controlled Goods Directorate or be exempt from registration. More information may be found at www.cgd.gc.ca.

# b) Will the supplier require access to unclassified military technical data subject to the provisions of the Technical Data Control Regulations?

The prime contractor and any subcontractors must be certified under the U.S./Canada Joint Certification Program if the work involves access to unclassified military data subject to the provisions of the Technical Data Control Regulations. More information may be found at www.dlis.dla.mil/jcp.

#### 6. Indicate the type of access required

Identify the nature of the work to be performed for this requirement. The user is to select one of the following types:

### a) Will the supplier and its employees require access to PROTECTED and/or CLASSIFIED information or assets?

The supplier would select this option if they require access to PROTECTED and/or CLASSIFIED information or assets to perform the duties of the requirement.

b) Will the supplier and its employees (e.g. cleaners, maintenance personnel) require access to restricted access areas? No access to PROTECTED and/or CLASSIFIED information or assets is permitted.

The supplier would select this option if they require regular access to government premises or a secure work site only. The supplier will not have access to PROTECTED and/or CLASSIFIED information or assets under this option.

#### c) Is this a commercial courier or delivery requirement with no overnight storage?

The supplier would select this option if there is a commercial courier or delivery requirement. The supplier will not be allowed to keep a package overnight. The package must be returned if it cannot be delivered.

#### 7. Type of information / Release restrictions / Level of information

Identify the type(s) of information that the supplier may require access to, list any possible release restrictions, and if applicable, provide the level(s) of the information. The user can make multiple selections based on the nature of the work to be performed.

Departments must process SRCLs through PWGSC where:

- contracts that afford access to PROTECTED and/or CLASSIFIED foreign government information and assets;
- contracts that afford foreign contractors access to PROTECTED and/or CLASSIFIED Canadian government information and assets; or
- contracts that afford foreign or Canadian contractors access to PROTECTED and/or CLASSIFIED information and assets
  as defined in the documents entitled Identifying INFOSEC and INFOSEC Release.

### a) Indicate the type of information that the supplier will be required to access

#### Canadian government information and/or assets

If Canadian information and/or assets are identified, the supplier will have access to PROTECTED and/or CLASSIFIED information and/or assets that are owned by the Canadian government.

#### NATO information and/or assets

If NATO information and/or assets are identified, this indicates that as part of this requirement, the supplier will have access to PROTECTED and/or CLASSIFIED information and/or assets that are owned by NATO governments. NATO information and/or assets are developed and/or owned by NATO countries and are not to be divulged to any country that is not a NATO member nation. Persons dealing with NATO information and/or assets must hold a NATO security clearance and have the required need-to-know.

Requirements involving CLASSIFIED NATO information must be awarded by PWGSC. PWGSC / CIISD is the Designated Security Authority for industrial security matters in Canada.

#### Foreign government information and/or assets

If foreign information and/or assets are identified, this requirement will allow access to information and/or assets owned by a country other than Canada.

### b) Release restrictions

If **Not Releasable** is selected, this indicates that the information and/or assets are for **Canadian Eyes Only (CEO)**. Only Canadian suppliers based in Canada can bid on this type of requirement. NOTE: If Canadian information and/or assets coexists with CEO information and/or assets, the CEO information and/or assets must be stamped **Canadian Eyes Only (CEO)**.

If No Release Restrictions is selected, this indicates that access to the information and/or assets are not subject to any restrictions.

If ALL NATO countries is selected, bidders for this requirement must be from NATO member countries only.

NOTE: There may be multiple release restrictions associated with a requirement depending on the nature of the work to be performed. In these instances, a security guide should be added to the SRCL clarifying these restrictions. The security guide is normally generated by the organization's project authority and/or security authority.

#### c) Level of information

Using the following chart, indicate the appropriate level of access to information/assets the supplier must have to perform the duties of the requirement.

PROTECTED	CLASSIFIED	NATO
PROTECTED A	CONFIDENTIAL	NATO UNCLASSIFIED
PROTECTED B	SECRET	NATO RESTRICTED
PROTECTED C	TOP SECRET	NATO CONFIDENTIAL
	TOP SECRET (SIGINT)	NATO SECRET
		COSMIC TOP SECRET

# 8. Will the supplier require access to PROTECTED and/or CLASSIFIED COMSEC information or assets?

If Yes, the supplier personnel requiring access to COMSEC information or assets must receive a COMSEC briefing. The briefing will be given to the "holder" of the COMSEC information or assets. In the case of a "personnel assigned" type of contract, the customer department will give the briefing. When the supplier is required to receive and store COMSEC information or assets on the supplier's premises, the supplier's COMSEC Custodian will give the COMSEC briefings to the employees requiring access to COMSEC information or assets. If Yes, the Level of sensitivity must be indicated.

#### 9. Will the supplier require access to extremely sensitive INFOSEC information or assets?

If Yes, the supplier must provide the Short Title of the material and the Document Number. Access to extremely sensitive INFOSEC information or assets will require that the supplier undergo a Foreign Ownership Control or Influence (FOCI) evaluation by CIISD.

#### PART B - PERSONNEL (SUPPLIER)

#### 10. a) Personnel security screening level required

Identify the screening level required for access to the information/assets or client facility. More than one level may be identified depending on the nature of the work. Please note that Site Access screenings are granted for access to specific sites under prior arrangement with the Treasury Board of Canada Secretariat. A Site Access screening only applies to individuals, and it is not linked to any other screening level that may be granted to individuals or organizations.

RELIABILITY STATUS	CONFIDENTIAL	SECRET
TOP SECRET	TOP SECRET (SIGINT)	NATO CONFIDENTIAL
NATO SECRET	COSMIC TOP SECRET	SITE ACCESS

If multiple levels of screening are identified, a Security Classification Guide must be provided.

# b) May unscreened personnel be used for portions of the work?

Indicating Yes means that portions of the work are not PROTECTED and/or CLASSIFIED and may be performed outside a secure environment by unscreened personnel. The following question must be answered if unscreened personnel will be used:

#### Will unscreened personnel be escorted?

If No, unscreened personnel may not be allowed access to sensitive work sites and must not have access to PROTECTED and/or CLASSIFIED information and/or assets.

If Yes, unscreened personnel must be escorted by an individual who is cleared to the required level of security in order to ensure there will be no access to PROTECTED and/or CLASSIFIED information and/or assets at the work site.

## PART C - SAFEGUARDS (SUPPLIER)

# 11. INFORMATION / ASSETS

# a) Will the supplier be required to receive and store PROTECTED and/or CLASSIFIED information and/or assets on its site or premises?

If Yes, specify the security level of the documents and/or equipment that the supplier will be required to safeguard at their own site or premises using the summary chart.

## b) Will the supplier be required to safeguard COMSEC information or assets?

If Yes, specify the security level of COMSEC information or assets that the supplier will be required to safeguard at their own site or premises using the summary chart.

# **PRODUCTION**

c) Will the production (manufacture, repair and/or modification) of PROTECTED and/or CLASSIFIED material and/or equipment occur at the supplier's site or premises?

Using the summary chart, specify the security level of material and/or equipment that the supplier manufactured, repaired and/or modified and will be required to safeguard at their own site or premises.

# **INFORMATION TECHNOLOGY (IT)**

# d) Will the supplier be required to use its IT systems to electronically process and/or produce or store PROTECTED and/or CLASSIFIED information and/or data?

If Yes, specify the security level in the summary chart. This block details the information and/or data that will be electronically processed or produced and stored on a computer system. The client department and/or organization will be required to specify the IT security requirements for this procurement in a separate technical document. The supplier must also direct their attention to the following document: Treasury Board of Canada Secretariat - Operational Security Standard: Management of Information Technology Security (MITS).

#### e) Will there be an electronic link between the supplier's IT systems and the government department or agency?

If Yes, the supplier must have their IT system(s) approved. The Client Department must also provide the Connectivity Criteria detailing the conditions and the level of access for the electronic link (usually not higher than PROTECTED B level).

#### **SUMMARY CHART**

For users completing the form **manually** use the summary chart below to indicate the category(ies) and level(s) of safeguarding required at the supplier's site(s) or premises.

For users completing the form **online** (via the Internet), the Summary Chart is automatically populated by your responses to previous questions.

PROTECTED	CLASSIFIED	NATO	COMSEC
PROTECTED A	CONFIDENTIAL	NATO RESTRICTED	PROTECTED A
PROTECTED B	SECRET	NATO CONFIDENTIAL	PROTECTED B
PROTECTED C	TOP SECRET	NATO SECRET	PROTECTED C
	TOP SECRET (SIGINT)	COSMIC TOP SECRET	CONFIDENTIAL
			SECRET
			TOP SECRET

#### 12. a) Is the description of the work contained within this SRCL PROTECTED and/or CLASSIFIED?

If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification".

### b) Will the documentation attached to this SRCL be PROTECTED and/or CLASSIFIED?

If Yes, classify this form by annotating the top and bottom in the area entitled "Security Classification" and indicate with attachments (e.g. SECRET with Attachments).

#### PART D - AUTHORIZATION

# 13. Organization Project Authority

This block is to be completed and signed by the appropriate project authority within the client department or organization (e.g. the person responsible for this project or the person who has knowledge of the requirement at the client department or organization). This person may on occasion be contacted to clarify information on the form.

#### 14. Organization Security Authority

This block is to be signed by the Departmental Security Officer (DSO) (or delegate) of the department identified in Block 1, or the security official of the prime contractor.

## 15. Are there additional instructions (e.g. Security Guide, Security Classification Guide) attached?

A Security Guide or Security Classification Guide is used in conjunction with the SRCL to identify additional security requirements which do not appear in the SRCL, and/or to offer clarification to specific areas of the SRCL.

# 16. Procurement Officer

This block is to be signed by the procurement officer acting as the contract or subcontract manager.

# 17. Contracting Security Authority

This block is to be signed by the Contract Security Official. Where PWGSC is the Contract Security Authority, Canadian and International Industrial Security Directorate (CIISD) will complete this block.

#### Instructions pour établir la Liste de vérification des exigences relatives à la sécurité (LVERS)

La feuille d'instructions devrait rester jointe au formulaire jusqu'à ce que la case 17 ait été remplie.

#### GÉNÉRALITÉS - TRAITEMENT DU PRÉSENT FORMULAIRE

Le responsable du projet doit faire remplir ce formulaire.

L'agent de sécurité de l'organisation doit revoir et approuver les exigences de sécurité qui figurent dans le formulaire, en collaboration avec le responsable du projet.

Le responsable de la sécurité des marchés est le responsable chargé de voir à ce que les fournisseurs se conforment aux exigences de sécurité mentionnées dans la LVERS.

Toutes les demandes d'achat ainsi que tous les appels d'offres et les documents contractuels subséquents, y compris les contrats de sous-traitance, qui comprennent des exigences relatives à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS doivent être accompagnés d'une LVERS dûment remplie.

Il importe d'indiquer si les renseignements ou les biens PROTÉGÉS sont de niveau A, B ou C, le cas échéant; cependant, certains types de renseignements peuvent être indiqués par la mention « PROTÉGÉ » seulement. Aucun renseignement relatif à un contrat gouvernemental PROTÉGÉ ou CLASSIFIÉ ne peut être divulgué par les fournisseurs sans l'approbation écrite préalable de la personne dont le nom figure à la case 17 de ce formulaire.

La classification assignée à un stade particulier du processus contractuel ne signifie pas que tout ce qui se rapporte à ce stade doit recevoir la même classification. Chaque article doit être PROTÉGÉ et/ou CLASSIFIÉ selon sa propre nature. Si un fournisseur ne sait pas quel niveau de classification assigner, il doit consulter la personne dont le nom figure à la case 17 de ce formulaire.

#### **PARTIE A - INFORMATION CONTRACTUELLE**

#### Numéro du contrat (au haut du formulaire)

Ce numéro doit être le même que celui utilisé sur la demande d'achat et services et devrait être celui utilisé dans la DDP ou dans le contrat. Il s'agit d'un numéro unique (c.-à-d. que le même numéro ne sera pas attribué à deux besoins distincts). Une nouvelle LVERS doit être utilisée pour chaque nouveau besoin ou demande (p. ex. un nouveau numéro de contrat, une nouvelle LVERS, de nouvelles signatures).

## 1. Ministère ou organisme gouvernemental d'origine

Inscrire le nom du ministère ou de l'organisme client ou le nom de l'entrepreneur principal pour qui les travaux sont effectués.

# 2. Direction générale ou Direction

Cette case peut servir à fournir plus de détails quant à la section du ministère ou de l'organisme pour qui les travaux sont effectués.

## 3. a) Numéro du contrat de sous-traitance

S'il y a lieu, ce numéro correspond au numéro généré par l'entrepreneur principal pour gérer le travail avec son sous-traitant.

### b) Nom et adresse du sous-traitant

Indiquer le nom et l'adresse au complet du sous-traitant, s'il y a lieu.

## 4. Brève description du travail

Donner un bref aperçu du besoin ou du travail à exécuter.

# 5. a) Le fournisseur aura-t-il accès à des marchandises contrôlées?

La Loi sur la production de défense (LPD) définit « marchandises contrôlées » comme désignant certains biens énumérés dans la Liste des marchandises d'exportation contrôlée, un règlement établi en vertu de la Loi sur les licences d'exportation et d'importation (LLEI). Les fournisseurs qui examinent, possèdent ou transfèrent des marchandises contrôlées à l'intérieur du Canada doivent s'inscrire à la Direction des marchandises contrôlées ou être exemptés de l'inscription. On trouvera plus d'information à l'adresse www.cgp.gc.ca.

# b) Le fournisseur aura-t-il accès à des données techniques militaires non classifiées qui sont assujetties aux dispositions du Règlement sur le contrôle des données techniques?

L'entrepreneur et tout sous-traitant doivent être accrédités en vertu du Programme mixte d'agrément Etats-Unis / Canada si le travail comporte l'accès à des données militaires non classifiées qui sont assujetties aux dispositions du Règlement sur le contrôle des données techniques. On trouvera plus d'information à l'adresse www.dlis.dla.mil/jcp/.

#### 6. Indiquer le type d'accès requis

Indiquer la nature du travail à exécuter pour répondre à ce besoin. L'utilisateur doit choisir un des types suivants :

# a) Le fournisseur et ses employés auront-ils accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS?

Le fournisseur choisit cette option s'il doit avoir accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS pour accomplir le travail requis.

# b) Le fournisseur et ses employés (p. ex. nettoyeurs, personnel d'entretien) auront-ils accès à des zones d'accès restreintes? L'accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS n'est pas autorisé.

Le fournisseur choisit cette option seulement s'il doit avoir accès régulièrement aux locaux du gouvernement ou à un lieu de travail protégé. Le fournisseur n'aura pas accès à des renseignements ou à des biens PROTÉGÉS et/ou CLASSIFIÉS en vertu de cette option.

### c) S'agit-il d'un contrat de messagerie ou de livraison commerciale sans entreposage de nuit?

Le fournisseur choisit cette option s'il y a nécessité de recourir à un service de messagerie ou de livraison commerciale. Le fournisseur ne sera pas autorisé à garder un colis pendant la nuit. Le colis doit être retourné s'il ne peut pas être livré.

#### 7. Type d'information / Restrictions relatives à la diffusion / Niveau d'information

Indiquer le ou les types d'information auxquels le fournisseur peut devoir avoir accès, énumérer toutes les restrictions possibles relatives à la diffusion, et, s'il y a lieu, indiquer le ou les niveaux d'information. L'utilisateur peut faire plusieurs choix selon la nature du travail à exécuter.

Les ministères doivent soumettre la LVERS à TPSGC lorsque:

- les marchés prévoient l'accès aux renseignements et aux biens de nature PROTÉGÉS et/ou CLASSIFIÉS étrangers ;
- les marchés prévoient aux entrepreneurs étrangers l'accès aux renseignements et aux biens de nature PROTÉGÉS et/ou CLASSIFIÉS canadiens; ou
- les marchés prévoient aux entrepreneurs étrangers ou canadiens l'accès aux renseignements et aux biens de nature PROTÉGÉS et/ou CLASSIFIÉS tels que définis dans les documents intitulés Moyens INFOSEC détermination et Divulgation de INFOSEC.

#### a) Indiquer le type d'information auquel le fournisseur devra avoir accès

# Renseignements et/ou biens du gouvernement canadien

Si des renseignements et/ou des biens canadiens sont indiqués, le fournisseur aura accès à des renseignements et/ou à des biens PROTÉGÉS et/ou CLASSIFIÉS appartenant au gouvernement canadien.

#### Renseignements et/ou biens de l'OTAN

Si des renseignements et/ou des biens de l'OTAN sont indiqués, cela signifie que, dans le cadre de ce besoin, le fournisseur aura accès à des renseignements et/ou à des biens PROTÉGÉS et/ou CLASSIFIÉS appartenant à des gouvernements membres de l'OTAN. Les renseignements et/ou les biens de l'OTAN sont élaborés par des pays de l'OTAN ou leur appartiennent et ne doivent être divulgués à aucun pays qui n'est pas un pays membre de l'OTAN. Les personnes qui manient des renseignements et/ou des biens de l'OTAN doivent détenir une autorisation de sécurité de l'OTAN et avoir besoin de savoir.

Les contrats comportant des renseignements CLASSIFIÉS de l'OTAN doivent être attribués par TPSGC. La DSICI de TPSGC est le responsable de la sécurité désigné relativement aux questions de sécurité industrielle au Canada.

## Renseignements et/ou biens de gouvernements étrangers

Si des renseignements et/ou des biens de gouvernements étrangers sont indiqués, ce besoin permettra l'accès à des renseignements et/ou à des biens appartenant à un pays autre que le Canada.

# b) Restrictions relatives à la diffusion

Si À ne pas diffuser est choisi, cela indique que les renseignements et/ou les biens sont réservés aux Canadiens. Seuls des fournisseurs canadiens installés au Canada peuvent soumissionner ce genre de besoin. NOTA: Si des renseignements et/ou des biens du gouvernement canadien coexistent avec des renseignements et/ou des biens réservés aux Canadiens, ceux-ci doivent porter la mention Réservé aux Canadiens.

Si Aucune restriction relative à la diffusion est choisi, cela indique que l'accès aux renseignements et/ou aux biens n'est assujetti à aucune restriction.

Si Tous les pays de l'OTAN est choisi, les soumissionnaires doivent appartenir à un pays membre de l'OTAN.

NOTA: Il peut y avoir plus d'une restriction s'appliquant à une demande, selon la nature des travaux à exécuter. Pour ce genre de contrat, un guide de sécurité doit être joint à la LVERS afin de clarifier les restrictions. Ce guide est généralement préparé par le chargé de projet et/ou le responsable de la sécurité de l'organisme.

#### c) Niveau d'information

À l'aide du tableau ci-dessous, indiquer le niveau approprié d'accès aux renseignements et/ou aux biens que le fournisseur doit avoir pour accomplir les travaux requis.

PROTÉGÉ	CLASSIFIÉ	NATO
PROTÉGÉ A	CONFIDENTIEL	NATO NON CLASSIFIÉ
PROTÉGÉ B	SECRET	NATO DIFFUSION RESTREINTE
PROTÉGÉ C	TRÈS SECRET	NATO CONFIDENTIEL
	TRÈS SECRET (SIGINT)	NATO SECRET
		COSMIC TRÈS SECRET

- 8. Le fournisseur aura-t-il accès à des renseignements ou à des biens COMSEC désignés PROTÉGÉS et/ou CLASSIFIÉS?
  Si la réponse est Oui, les membres du personnel du fournisseur qui doivent avoir accès à des renseignements ou à des biens
  COMSEC doivent participer à une séance d'information COMSEC. Cette séance sera donnée au « détenteur autorisé » des
  renseignements ou des biens COMSEC. Dans le cas des contrats du type « personnel affecté », cette séance sera donnée par le
  ministère client. Lorsque le fournisseur doit recevoir et conserver, dans ses locaux, des renseignements ou des biens COMSEC, le
  responsable de la garde des renseignements ou des biens COMSEC de l'entreprise donnera la séance d'information COMSEC aux
  membres du personnel qui doivent avoir accès à des renseignements ou à des biens COMSEC.
- 9. Le fournisseur aura-t-il accès à des renseignements ou à des biens INFOSEC de nature extrêmement délicate? Si la réponse est Oui, le fournisseur doit indiquer le titre abrégé du document, le numéro du document et le niveau de sensibilité. L'accès à des renseignements ou à des biens extrêmement délicats INFOSEC exigera que le fournisseur fasse l'objet d'une vérification Participation, contrôle et influence étrangers (PCIE) effectuée par la DSICI.

# PARTIE B - PERSONNEL (FOURNISSEUR)

## 10. a) Niveau de contrôle de la sécurité du personnel requis

Indiquer le niveau d'autorisation de sécurité que le personnel doit détenir pour avoir accès aux renseignements, aux biens ou au site du client. Selon la nature du travail, il peut y avoir plus d'un niveau de sécurité. Veuillez noter que des cotes de sécurité sont accordées pour l'accès à des sites particuliers, selon des dispositions antérieures prises auprès du Secrétariat du Conseil du Trésor du Canada. La cote de sécurité donnant accès à un site s'applique uniquement aux personnes et n'est liée à aucune autre autorisation de sécurité accordée à des personnes ou à des organismes.

COTE DE FIABILITÉ	CONFIDENTIEL	SECRET
TRÈS SECRET	TRÈS SECRET (SIGINT)	NATO CONFIDENTIEL
NATO SECRET	COSMIC TRÈS SECRET	ACCÈS AUX EMPLACEMENTS

Si plusieurs niveaux d'autorisation de sécurité sont indiqués, un guide de classification de sécurité doit être fourni.

### b) Du personnel sans autorisation sécuritaire peut-il se voir confier des parties du travail?

Si la réponse est Oui, cela veut dire que certaines tâches ne sont pas PROTÉGÉES et/ou CLASSIFIÉES et peuvent être exécutées à l'extérieur d'un environnement sécurisé par du personnel n'ayant pas d'autorisation de sécurité. Il faut répondre à la question suivante si l'on a recours à du personnel n'ayant pas d'autorisation de sécurité :

#### Le personnel n'ayant pas d'autorisation de sécurité sera-t-il escorté?

Si la réponse est Non, le personnel n'ayant pas d'autorisation de sécurité ne pourra pas avoir accès à des lieux de travail dont l'accès est réglementé ni à des renseignements et/ou à des biens PROTÉGÉS et/ou CLASSIFIÉS.

Si la réponse est Oui, le personnel n'ayant pas d'autorisation de sécurité devra être escorté par une personne détenant la cote de sécurité requise, pour faire en sorte que le personnel en question n'ait pas accès à des renseignements et/ou à des biens PROTÉGÉS et/ou CLASSIFIÉS sur les lieux de travail.

### PARTIE C - MESURES DE PROTECTION (FOURNISSEUR)

#### 11. RENSEIGNEMENTS / BIENS:

# a) Le fournisseur sera-t-il tenu de recevoir et d'entreposer sur place des renseignements ou des biens PROTÉGÉS et/ou CLASSIFIÉS?

Si la réponse est Oui, préciser, à l'aide du tableau récapitulatif, le niveau de sécurité des documents ou de l'équipement que le fournisseur devra protéger dans ses installations.

#### b) Le fournisseur sera-t-il tenu de protéger des renseignements ou des biens COMSEC?

Si la réponse est Oui, préciser, à l'aide du tableau récapitulatif, le niveau de sécurité des renseignements ou des biens COMSEC que le fournisseur devra protéger dans ses installations.

#### **PRODUCTION**

c) Les installations du fournisseur serviront-elles à la production (fabrication et/ou réparation et/ou modification) de matériel PROTÉGÉ et/ou CLASSIFIÉ?

Préciser, à l'aide du tableau récapitulatif, le niveau de sécurité du matériel que le fournisseur fabriquera, réparera et/ou modifiera et devra protéger dans ses installations.

#### **TECHNOLOGIE DE L'INFORMATION (TI)**

d) Le fournisseur sera-t-il tenu d'utiliser ses propres systèmes informatiques pour traiter, produire ou stocker électroniquement des renseignements ou des données PROTÉGÉS et/ou CLASSIFIÉS?

Si la réponse est Oui, préciser le niveau de sécurité à l'aide du tableau récapitulatif. Cette case porte sur les renseignements qui seront traités ou produits électroniquement et stockés dans un système informatique. Le ministère/organisme client devra préciser les exigences en matière de sécurité de la TI relativement à cet achat dans un document technique distinct. Le fournisseur devra également consulter le document suivant : Secrétariat du Conseil du Trésor du Canada – Norme opérationnelle de sécurité : Gestion de la sécurité des technologies de l'information (GSTI).

e) Y aura-t-il un lien électronique entre les systèmes informatiques du fournisseur et celui du ministère ou de l'agence gouvernementale?

Si la réponse est Oui, le fournisseur doit faire approuver ses systèmes informatiques. Le ministère client doit aussi fournir les critères de connectivité qui décrivent en détail les conditions et le niveau de sécurité relativement au lien électronique (habituellement pas plus haut que le niveau PROTÉGÉ B).

# TABLEAU RÉCAPITULATIF

Les utilisateurs qui remplissent le formulaire **manuellement** doivent utiliser le tableau récapitulatif ci-dessous pour indiquer, pour chaque catégorie, les niveaux de sauvegarde requis aux installations du fournisseur.

Dans le cas des utilisateurs qui remplissent le formulaire **en ligne** (par Internet), les réponses aux questions précédentes sont automatiquement saisies dans le tableau récapitulatif.

PROTÉGÉ	CLASSIFIÉ	NATO	COMSEC
PROTÉGÉ A	CONFIDENTIEL	NATO DIFFUSION RESTREINTE	PROTÉGÉ A
PROTÉGÉ B	SECRET	NATO CONFIDENTIEL	PROTÉGÉ B
PROTÉGÉ C	TRÈS SECRET	NATO SECRET	PROTÉGÉ C
	TRÈS SECRET (SIGINT)	COSMIC TRÈS SECRET	CONFIDENTIEL
			SECRET
			TRÈS SECRET

# 12. a) La description du travail visé par la présente LVERS est-elle de nature PROTÉGÉE et/ou CLASSIFIÉE?

Si la réponse est Oui, classifier le présent formulaire en indiquant le niveau de sécurité dans la case intitulée « Classification de

sécurité » au haut et au bas du formulaire.

# b) La documentation associée à la présente LVERS sera-t-elle PROTÉGÉE et/ou CLASSIFIÉE?

Si la réponse est Oui, classifier le présent formulaire en indiquant le niveau de sécurité dans la case intitulée « Classification de sécurité » au haut et au bas du formulaire et indiquer qu'il y a des pièces jointes (p. ex. SECRET avec des pièces jointes).

# **PARTIE D - AUTORISATION**

# 13. Chargé de projet de l'organisme

Cette case doit être remplie et signée par le chargé de projet pertinent (c.-à-d. la personne qui est responsable de ce projet ou qui connaît le besoin au ministère ou à l'organisme client. On peut, à l'occasion, communiquer avec cette personne pour clarifier des renseignements figurant sur le formulaire.

#### 14. Responsable de la sécurité de l'organisme

Cette case doit être signée par l'agent de la sécurité du ministère (ASM) du ministère indiqué à la case 1 ou par son remplaçant ou par le responsable de la sécurité du fournisseur.

#### 15. Des instructions supplémentaires (p. ex. Guide de sécurité, Guide de classification de la sécurité) sont-elles jointes?

Un Guide de sécurité ou un Guide de classification de sécurité sont utilisés de concert avec la LVERS pour faire part d'exigences supplémentaires en matière de sécurité qui n'apparaissent pas dans la LVERS et/ou pour éclaircir certaines parties de la LVERS.

# 16. Agent d'approvisionnement

Cette case doit être signée par l'agent des achats qui fait fonction de gestionnaire du contrat ou du contrat de sous-traitance.

#### 17. Autorité contractante en matière de sécurité

Cette case doit être signée par l'agent de la sécurité du marché. Lorsque TPSGC est le responsable de la sécurité du marché, la Direction de la sécurité industrielle canadienne et internationale (DSICI) doit remplir cette case.